

THE ARCHITECTS' JOURNAL



standard contents

every issue does not necessarily contain all these contents, but they are the regular features which continually recur.

NEWS and COMMENT

Diary

News

Astragal's Notes and Topics

Letters

Societies and Institutions

TECHNICAL SECTION

Information Sheets

Information Centre

Current Technique

Questions and Answers

Prices

The Industry

PHYSICAL PLANNING

SUPPLEMENT

CURRENT BUILDINGS

HOUSING STATISTICS

Architectural Appointments
Wanted and Vacant

★ A glossary of abbreviations of Government Departments and Societies and Committees of all kinds, together with their full address and telephone numbers. The glossary is published in two parts—A to I one week, I to Z the next. In all cases where the town is not mentioned the word LONDON is implicit in the address.

IGE	Institution of Gas Engineers. 17, Grosvenor Crescent, S.W.1.	Sloane 8266
IHVE	Institution of Heating and Ventilating Engineers. 75, Eaton Place, S.W.1.	
IIBD	Incorporated Institute of British Decorators. Drayton House, Gordon Street, W.C.1.	Euston 2450
ILA	Institute of Landscape Architects. 12, Gower Street, W.C.1.	Museum 1783
I of Arb.	Institute of Arbitrators, 35/37, Hastings House, 10, Norfolk Street, Strand, W.C.2.	Temple Bar 4071
IOB	Institute of Builders. 48, Bedford Square, W.C.1.	Museum 7197/5176
IR	Institute of Refrigeration. Dalmeny House, Monument Street, E.C.3.	Avenue 6851
IRA	Institute of Registered Architects. 47, Victoria Street, S.W.1.	Abbey 6172
ISE	Institution of Structural Engineers. 11, Upper Belgrave Street, S.W.1.	Sloane 7128
IWA	Inland Waterways Association. 11, Gower Street, W.C.1.	Museum 9200
LIDC	Lead Industries Development Council. Eagle House, Jermyn Street, S.W.1.	Whitehall 7264/4175
LMBA	London Master Builders' Association. 47, Bedford Square, W.C.1.	Museum 3891
MARS	MARS Group (English Branch of CIAM). Secretary: Gontran Goulden, Building Centre, 9, Conduit Street, W.1.	Mayfair 8641
MOA	Ministry of Agriculture and Fisheries. 55, Whitehall, S.W.1.	Whitehall 3400
MOE	Ministry of Education. Curzon Street House, Curzon Street, W.1.	Mayfair 9400
MOH	Ministry of Health. Whitehall, S.W.1.	Whitehall 4300
MOLGP	Ministry of Local Government and Planning. 23, Saville Row, W.1.	Regent 8411
MOLNS	Ministry of Labour and National Service, 8, St. James's Square, S.W.1.	Whitehall 6200
MOS	Ministry of Supply. Shell Mex House, Victoria Embankment, W.C.	Gerrard 6933
MOT	Ministry of Transport. Berkeley Square House, Berkeley Square, W.1.	Mayfair 9494
MOW	Ministry of Works. Lambeth Bridge House, S.E.1.	Reliance 7611
NAMMC	Natural Asphalte Mine-Owners and Manufacturers Council. 94-98, Petty France, S.W.1.	Abbey 1010
NAS	National Association of Shopfitters. 9, Victoria Street, S.W.1.	Abbey 4813
NBR	National Buildings Record. 37, Onslow Gardens, S.W.7.	Kensington 8161
NCBMP	National Council of Building Material Producers. 10, Princes Street, S.W.1.	Abbey 5111
NFBTE	National Federation of Building Trades Employers. 82, New Cavendish Street, W.1.	Langham 4041/4054
NFBTO	National Federation of Building Trades Operatives, Federal House, Cedars Road, Clapham, S.W.4.	Macaulay 4451
NFHS	National Federation of Housing Societies. 13, Suffolk St., S.W.1.	Whitehall 1693
NHBRC	National House Builders Registration Council. 82, New Cavendish Street, W.1.	Langham 4341
NPL	National Physical Laboratory. Head Office, Teddington.	Molesey 1380
NSA	National Sawmilling Association, 14, New Bridge Street, E.C.4.	City 1476
NSAS	National Smoke Abatement Society. Chandos House, Buckingham Gate, S.W.1.	Abbey 1359
NT	National Trust for Places of Historic Interest or Natural Beauty. 42, Queen Anne's Gate, S.W.1.	Whitehall 0211
PEP	Political and Economic Planning. 16, Queen Anne's Gate, S.W.1.	Whitehall 7245
RCA	Reinforced Concrete Association. 94, Petty France, S.W.1.	Whitehall 9936
RIAS	Royal Incorporation of Architects in Scotland. 15, Rutland Square, Edinburgh.	Edinburgh 20396
RIBA	Royal Institute of British Architects. 66, Portland Place, W.1.	Langham 5721
RICS	Royal Institution of Chartered Surveyors, 12, Great George St., S.W.1.	Whitehall 5322/9242
RFAC	Royal Fine Art Commission. 22A, Queen Anne's Gate, S.W.1.	Whitehall 3935
RS	Royal Society. Burlington House, Piccadilly, W.1.	Regent 3335
RSA	Royal Society of Arts. 6, John Adam Street, W.C.2.	Trafalgar 2366
RSI	Royal Sanitary Institute. 90, Buckingham Palace Road, S.W.1.	Sloane 5134
RIB	Rural Industries Bureau. 35, Camp Road, Wimbledon, S.W.19.	Wimbledon 5101
SBPM	Society of British Paint Manufacturers. Grosvenor Gardens House, Grosvenor Gardens, S.W.1.	Victoria 2186
SCR	Society for Cultural Relations with the USSR. 14, Kensington Square, London, W.8.	Western 1571
SE	Society of Engineers. 17, Victoria Street, Westminster, S.W.1.	Abbey 7244
SFMA	School Furniture Manufacturers' Association. 30, Cornhill, London, E.C.3.	Mansion House 3921
SIA	Structural Insulation Association. 14, Moorgate, London, E.C.2.	Central 4444
SIA	Society of Industrial Artists. 7, Woburn Square, W.C.1.	Langham 1984
SNHTPC	Scottish National Housing. Town Planning Council. Hon. Sec., Robert Pollock, Town Clerk, Rutherglen.	
SPAB	Society for the Protection of Ancient Buildings. 55, Great Ormond Street, W.C.1.	Holborn 2646
TCPA	Town and Country Planning Association. 28, King Street, Covent Garden, W.C.2.	Temple Bar 5006
TDA	Timber Development Association. 21, College Hill, E.C.4.	City 4771
TGC	The Gas Council. 1, Grosvenor Place, S.W.1.	Sloane 4554
TPI	Town Planning Institute. 18, Ashley Place, S.W.1.	Victoria 8815
TTF	Timber Trades Federation. 69, Cannon Street, E.C.4.	City 4444
WDC	War Damage Commission. Devonshire House, Mayfair Place, Piccadilly, W.1.	Mayfair 8866
WEDA	Welfare Equipment Development Association. 74, Victoria Street, S.W.1.	Victoria 5783

No. 2951]

[Vol. 114

THE ARCHITECTURAL PRESS

No. 11 and 13, Queen Anne's Gate, Westminster, S.W.1.

'Phone: Whitehall 0611

Price 1s. 0d.

MANUFACTURED
IN FIVE TYPES

"Murite"

REGD. TRADE MARK

GYPSUM PLASTER

EACH SPECIALLY
DESIGNED

1
FIBRED PLASTER
FOR SANDED
UNDERCOATS
ON WALL AND
CEILING BOARDS,
WOOD LATH, ETC.

1A
SPECIAL FIBRED
PLASTER FOR
SANDED UNDER-
COATS ON METAL
LATHING AND
CONCRETE

2
BROWNING
PLASTER FOR
SANDED UNDER-
COATS ON WALLS

3
WALL FINISH FOR
FINISHING ALL
CLASSES OF
SANDED
UNDERCOATS

BOARD FINISH
FOR SINGLE COAT
WORK ON ALL
TYPES OF WALL
AND CEILING
BOARDS. CEMENT
RENDERINGS, ETC

DESCRIPTIVE FOLDER AVAILABLE UPON REQUEST



CAFFERATA & CO. LTD.

NEWARK-ON-TRENT NOTTS NEWARK 2060

YOU will never be
really satisfied...

until you've
specified—



patent glazing

Issued by:
**The Patent Glazing Division of
AYGEE LTD.**

Head Office:
**100 WESTMINSTER BRIDGE ROAD
LONDON, S.E.1**

Telephone: WATERloo 6314 (6 lines)

Branch Works:
AINTREE RD., PERIVALE, MIDDXX.
Telephone: PERivale 6211 (5 lines)


ALUMINIUM ALLOY
SYSTEMS

The strongest bar.

Complete weather-proofing.

Rigid section
glazing wing.

Absence of
vibratory chatter.



A profile
of one of the
AYGEE alloy systems

— PIONEERS OF ALUMINIUM PATENT GLAZING —

A PRODUCT OF ENGLAND'S LARGEST GLAZING CONTRACTORS

t
g




l profile:
one of the
E alloy system

TORS



Permanent ventilation with locked window security!



THE GREENWOOD-AIRVAC "PERMAVENT"

HORIZONTAL WINDOW VENTILATOR OFFERS THESE UNIQUE FEATURES


- * COMPLETELY WEATHERPROOF
- * SUPERSEDES UNSIGHTLY AIRBRICKS
- * MADE TO FIT ANY SIZE OR TYPE OF WINDOW
- * CAN BE FITTED TO WOOD OR METAL FRAMES
- * SUITABLE FOR INTERNAL OR EXTERNAL GLAZING

EXTENSIVELY APPROVED AND SPECIFIED BY ARCHITECTS
AND ENGINEERS FOR USE IN SCHOOLS, HOSPITALS,
FACTORIES AND HOUSING SCHEMES



Specialists in the design of
ventilation equipment for
buildings, vehicles and vessels

GREENWOOD'S AND AIRVAC
Ventilating Company Limited
BEACON HOUSE KING'S WAY LONDON W.C.2



HARCO PATENT METALACE

PRODUCED IN ROLLS OF 25'
TO 100' LONG BY 2'11" WIDE.

The artistic effect of Harco Patent Metalace renders it particularly suitable for use where care of design and appointment are of major importance. Architects will appreciate that it not only screens the unsightly, but allows free circulation of air. The patterns in which Metalace can be woven, make it the perfect selection for Lift Shaft Enclosures, Ventilating Panels, Radiator Covers, Electric Heater Covers, etc.

Illustration shows
Pattern No. M. 1006.
Other Patterns and
full particulars in
Catalogue A.J. 585.

Harvey

G. A. Harvey & Co. (London) Ltd. Woolwich Road, London, S.E.7




THIS COUNTRY'S CLIMATE CALLS FOR CRANE

Some citizens pin their faith to the official weather forecast, some to the Bartlett Brothers, and some have a piece of tame seaweed hanging up in the hall. England's weather always wants watching. But indoors the only thing worth pinning one's faith to is Crane equipment for heating. The name 'Crane' is always warmly thought of where central heating or hot water supply is wanted. Crane boilers and radiators are literally 'cast iron' for any heating specification.

DELIVERIES OF 'PALL MALL',
HOSPITAL AND WALL TYPE RADIATORS
HAVE RECENTLY IMPROVED.

CRANE EQUIPMENT FOR HEATING


PALL MALL RADIATORS
This four-column Pall Mall Cast Iron Radiator is of graceful lines yet of sound and sturdy construction.



CRANE LTD. 45-51 LEMAN STREET, LONDON E.1. Works: IPSWICH • Branches: Birmingham, Brentford, Bristol, Glasgow, Manchester

SAVE COAL - SAVE COSTS

by using




Broad-Acheson
loadbearing cellular
Blocks

for *cavity* and
partition walls

FULL TECHNICAL DATA WITH "U" VALUES AND COST COMPARISONS SENT ON REQUEST

BROAD & CO. LTD., 4 SOUTH WHARF, PADDINGTON, LONDON, W.2 Tel: PAD 7061 (20 lines)

RAW MATERIALS FOR BRITAIN'S RECOVERY...



CEMENT HOUSES THE NATION'S STORES

In the busy traffic of Britain's trade, much depends upon good facilities for warehouses at all strategic points. To build these warehouses well, quickly and inexpensively calls for more and more cement. There is hardly any aspect of Britain's programme of rebuilding for recovery—social and commercial—in which The Blue Circle Cement Organisation is not deeply involved. With its huge resources, it is doing a huge job.



THE CEMENT MARKETING COMPANY LIMITED
PORTLAND HOUSE · TOTHILL STREET · LONDON · S.W.1.

This symbol identifies the products of the largest cement organisation in the world.



BALANCE

Development of strong but ever lighter materials has made it possible for fire escapes to reach increasing heights and progressively defeat the twin problems of balance and load.

Balance and materials are all-important in paint manufacture too, for good covering power, toughness, flexibility, lustre and life depend on meticulous balance in blending of ingredients old and new.

For over 150 years the firm of Joseph Mason has combined craftsmanship with every new development in material and technique to provide a range of balanced paints more than equal to the demands of today and tomorrow. Lynomas Super Gloss Enamel is but one example of the many

Fine Paints by



JOSEPH MASON & CO. LTD
D E R B Y



***"This Finch advertisement
for Wall and Floor Tiling
clinched it"***



***The Finch Wall and
Floor Tiling Division***

The service offered by the Wall and Floor Tiling Division of the Finch Organization consists not only of the materials supplied but in the men to do the job. As well as offering their clients an extremely wide selection of the finest quality tiles, Finch's employ a large team of highly skilled Fixers. This staff of experienced men enables them to carry every contract through to efficient completion at competitive prices.

Architects and Builders who read the Finch advertisements are constantly congratulating themselves on their good sense.

Finch advertising solves so many of their problems by introducing them to the Finch Specialist Divisions, of which there are no fewer than fifteen. These teams of experts in the many aspects of building are qualified by knowledge and experience, to offer not only the most comprehensive supply service in the country, but an enthusiastic personal attention to their clients' requirements, however unusual.

***The Wall & Floor
Tiling Division
of***

Specialist Divisions in: Sanitary Appliances and Plumbers' Brasswork . Fireplaces . Stoves and Ranges . Ironmongery . Tubes and Fittings . Kitchen Equipment . Soil and Drainage . Oils, Paint and Wallpaper . Tools and Hardware . Heavy Building Materials . Roof Tiling and Slating . Wall and Floor Tiling . Glazing and Leaded Lights . Constructional Engineering . Agricultural Buildings and Equipment.



***Building Materials
with Service***

B. FINCH & COMPANY LTD., Head Office and Works: **BELVEDERE WORKS, BARKINGSIDE, ESSEX**
VALENTINE: 8888 (30 LINES)
SHOWROOMS: FINCH CORNER 679/687 EASTERN AVENUE, (SOUTHEND ROAD), ILFORD, ESSEX

Prestressed Concrete

IN BRIDGE CONSTRUCTION

Positioning Dow-Mac Prestressed Beams at Exton Park Road Bridge, near Cottesmore, Rutland, built by the United Steel Companies, Ltd. (Ore Mining Branch). Photograph by courtesy of the United Steel Companies, Ltd.




Loushers Lane Bridge, near Warrington. Lowering Dow-Mac Prestressed Beams into position. Photograph by courtesy of J. V. Hughes, M.I.C.E., Borough Engineer and Surveyor, Warrington County Borough.

Dow-Mac Prestressed Beams are incorporated in 1'6" foot-bridge at Cockbeck, near Leeds, built for the Division of Opencast Coal Production, Ministry of Fuel and Power by William Pepper & Co. Ltd., 19 Park Row, Leeds, 1.




Dow-Mac prestressed bridge beams of standard section and lengths are now available. Research thus combines all the advantages of the Dow-Mac Prestressed system (saving in labour, steel, timber, reduced weight, high flexibility and resilience) with the convenience and economy of the pre-cast unit.

If you have a bridge problem consult the Dow-Mac Organisation. Dow-Mac Prestressed Concrete Units include bridge beams, decking slabs, piles, walings and railway sleepers.



DOW-MAC (PRODUCTS) LIMITED,
TALLINGTON • STAMFORD • LINCOLNSHIRE

Telephone: PETERBOROUGH 4501 (8 LINES)



In well-designed kitchens...




This Large Type **MAIN GAS ROASTING OVEN** is constructed generally of cast-iron and finished externally in Dapple Vitreous Enamel with white enamelled door panels, bakelite door handles and chromium-plated mountings.

The oven interior is 30" wide x 30" deep x 48" high. It has enamelled steel linings and is fitted with three grid shelves carried on removable side hangers. The heating is by two atmospheric gas burners.

The oven is mounted on enamelled cast-iron feet. The storage pan under the oven is of copper construction with an enamelled cast-iron front.

If you have any catering problem, large or small, write to R. & A. Main Ltd. They offer you the benefit of their long experience in the equipping of Kitchens, Canteens, etc. Layouts and estimates prepared on request.




COOKING APPARATUS AND KITCHEN EQUIPMENT

R. & A. MAIN LIMITED

Gothic Works, Edmonton, London, N.18 and Gothic Works, Falkirk

Gas and Steam



*Wheatly Russet Brown "TRITON" 6" x 3" Quarries, laid
basket pattern, at Oxhey Wood School, Northwick Road, Oxhey, Herts.*

Architects: Gollins, Melvin & Partners,

in association with C. H. Aslin, C.B.E., County Architect.

Flooring Contractors: Parkinsons (Wall Tiling) Ltd., Sth. Tottenham.

*Specimens of Wheatly Tiling may be seen at the
Building Centre, London. Wheatly products include
Single-lap Roofing Tiles, Ridge Tiles (blue and red),
Floor Quarries and Briquette Fireplaces.*

WHEATLY & COMPANY LIMITED


SPRINGFIELD TILERIES · TRENT VALE · STOKE-ON-TRENT

Telephone: NEWCASTLE (Staffs) 66981 · Telegrams: WHEATLY, TRENTVALE

WH46


Warm or Cool . . .

**AS THE
SLEEPER
CHOOSES**







Lucky girl to have a bedroom that is always just at the temperature she prefers! That is a pleasure enjoyed by all who have the whole house warmed by Radiation ducted air. Extra warmth at bedtime and in the morning, a cooler atmosphere during the night if you like it that way. With this extremely flexible system one is no longer at the mercy of the English climate—the house warmth is under personal control. It is comfort no longer to be dreamed about—it is a very practical present day reality.

The Radiation system may be installed with either a solid fuel appliance, which burns without smoke any solid fuel, *including bituminous coal*, or as a fully automatic gas unit. Architects, housing authorities and others—especially those interested in smoke abatement—are invited to write for literature explaining the system in full, or to visit the experimental houses at Stanmore where both solid fuel and gas installations may be experienced in action. But please apply first for an appointment to Radiation Group Sales Limited, Lancelot Works, Wembley, Middlesex. Telephone : Wembley 6221.



**Whole House
Warming by
Radiation
ducted air**



STRUCTURAL STEELWORK

The sturdy foundation of any building achievement lies in its bare bones, or structural framework, in which modern architecture demands, above all, strength and endurance.

These fundamental requirements of contemporary building are assured always, when the steel is erected by Thomas Blackburn's. For

our long experience in all branches of structural steelwork, and our strict adherence to the best in materials and methods give you that guarantee.

We are at your service always for:—

RAILINGS, GATES, METAL WINDOWS,
WELDED TANKS, CASTINGS.

THOMAS BLACKBURN & SONS LIMITED
PRESTON · LANCASHIRE

London Office: 8, Bloomsbury Square, W.C.1. Tel.: Holborn 8638.

ΦP



Visual control....

Visual control of industrial processes where steam and fumes arise can be made far more efficient with the use of "ARMOURPLATE" glass screens and hoods. Its great mechanical strength and resistance to thermal shock make it an ideal material for this purpose, and it has many other vital advantages in industrial building and equipment, as well as in all forms of commercial, public and domestic architecture.

Consult the Technical Sales and Service Department at St. Helens, Lancs., or at Selwyn House, Cleveland Row, St. James's, London, S.W.1. Phones: St. Helens 4001, Whitehall 5672. Supplies are available through the usual trade channels.




PILKINGTON BROTHERS LIMITED

"ARMOURPLATE" is the registered trade mark of Pilkington Brothers Limited.

"KISOL"

VERMICULITE INSULATING ROOFING SCREED


for industrial buildings



The photograph is of
Coventry Gas Works
showing a section of
the roof screeded with
"KISOL" Vermiculite
Concrete

"KISOL" Vermiculite concrete is ideal for insulating roofs of factories, power stations, gas works, mills and many other industrial buildings. It can be laid to falls over all types of roof structures, and 1" gives the equivalent insulating value of 15" of ordinary concrete. Because of its extreme lightness as compared with ordinary concrete, architects and builders are finding "KISOL" Vermiculite insulating material of great advantage in building construction, especially where the minimum of weight is necessary on structures. "KISOL" is also a non-conductor of electricity, highly acid-resisting, fungus proof and odourless. Full details available on application.

WILLIAM KENYON & SONS LIMITED
INSULATION ENGINEERS
DUKINFIELD **CHESHIRE**



*The Foyer—laid
in Teak (*Tectona
Grandis*) strip,
over panel heating*

above controversy

Many people have taken sides over the Concert Hall, some applauding its modernism others deploring its departure from tradition. But in all this controversy the one feature at which no criticism has been levelled is the flooring—laid by Vigers in hardwood block and strip.

Indeed, about that there can be no argument. For whatever the architectural style, a hardwood floor is always appropriate. It pleases everybody. Not only aesthetically but economically. A hardwood floor will last a lifetime—the life of the building—providing over the years an investment in charm, comfort and wearing quality that shows no depreciation.


VIGERS HARDWOOD FLOORING in the Festival Concert Hall

Vigers Bros. Limited, Broadway Chambers, Ludgate Broadway, London, E.C.4

Telephone: City 2111 (6 lines) Telegrams: Vigentes, Cent, London

T.A.4031

The finishing touch . .



- "DON" COLOUR-FILLED STAIRTREADS provide a safe tread, giving a firm foothold under all conditions.
- Aluminium nosings, together with the attractive colour range which is available, clearly show up each step, combining artistry with safety.
- Available in the following attractive range of colours: brown, silver, green, gold, blue, maroon, black, white, pink and red.
- The more common type of fabric-filled stairtreads can be supplied as well as our well-known colour range.
- Comprehensive range of nosings available—send for brochure, and copy of Architects' Journal Information Sheet.



COLOUR-FILLED
ALUMINIUM

stairtreads


PATENT No. 645549

SMALL & PARKES LIMITED · MANCHESTER · 9


LONDON: 18 HIGH STREET, WIMBLEDON, S.W.19




SETTING the highest standard in attractive, modern kitchen equipment, the "DALE" series of Kitchen Cabinets and Sinks makes an immediate appeal to every houseproud woman. Beneath the sleek attractive exterior of each cabinet—admirably finished in white or green hard-cream stove enamel, which will neither peel nor crack—lies a dustproof, rustproof construction of Pyluninised Aluminium and Steel. Full details of PAUL Kitchen equipment are given in our latest illustrated leaflet. *May we send you a copy?*



The Aquadale fully Automatic Dish Washer.




21" Wide Sinks with Double Bowls, Drainers and Tapholes.




18" Wide Sinks with Single Drainer—Reversible.

Our Showrooms at No. 7 Royal Arcade, Old Bond Street, London, W.1. where a range of PAUL Kitchen Equipment can be seen and enquiries answered.



W·H·PAUL LTD BREASTON.DERBY

**A
'DOWN TO EARTH'
POLICY**



Works Managers, Maintenance
practical turn of mind appreciate a down
have to fasten things to

The business end of the G K N
the part which does its work unseen.
special lugs give the bolt a holding
strength of the material

Engineers and other folk with a
to earth policy particularly when they
concrete or masonry.

Indented Foundation Bolt is
Grouted into concrete or masonry its
power governed only by the
in which it is set.



G K N

INDENTED FOUNDATION BOLTS

GUEST KEEN & NETTLEFOLDS (MIDLANDS) LIMITED

BOLT & NUT DIVISION Atlas Works, Darlaston, S. Staffs

D/195/3

About Aluminium...

7

CHEMICAL PROPERTIES

This article is one of a series, written for the interest of students and others, outlining some of the main characteristics of the metal and its structural alloys.

THE durability, or resistance to deterioration by corrosive agencies, of aluminium and many of its alloys is exceptionally high, frequently enabling them to be used without surface protection of any sort, so saving both pre-treatment and maintenance costs. This is often of greater value than its more generally appreciated qualities, such as light weight.

Atmospheric Exposure

Aluminium does, in fact, combine readily with atmospheric oxygen, but the oxide, unlike those of iron or copper, forms as a continuous film, which is hard and very adherent. This stable layer of oxide seals the metal from further oxidation, reforming spontaneously when the surface is cut or abraded in air. Its thickness, as naturally formed, depends on the alloy and on the nature and duration of exposure, but is of the order of a hundred-thousandth of an inch. It is transparent or nearly so, becoming visible as a grey film when thickened by age, exposure, or heating. The metal is exposed to attack only when the surface film is broken and, by lack of oxygen, prevented from reforming.

The nature of the film, and the immunity of the metal, are influenced by the presence of alloying constituents, and some of the strong copper-bearing alloys, for instance, normally need some means of protection. However, the medium-strength alloys that are used for building, and for the majority of civil and mechanical engineering purposes, can generally be used without protection.

Particular attention must be given to alloy selection and conditions of use when the surroundings are industrial and the air may carry many kinds of pollution, some of them aggressive. Except in special cases, however, aluminium will generally outlast other metals and is increasingly used, for instance, on factory roofs in place of galvanized steel.

The aluminium-magnesium group of alloys is particularly resistant to sea and coastal atmospheres, and is used in ship and boat construction.

Exposure of the bare metal to any atmosphere must, after a period (perhaps of years) that will depend on the circumstances, impair its original lustre and

smoothness, and, in severe conditions, surface deposits and slight pitting may appear. These changes are almost always superficial, and the appearance can be restored by cleaning.

Aggressive Conditions

Apart from direct attack by corrosive agents, such as alkaline or acidic fumes, or contact with damp cement or plaster, most instances of corrosion in aluminium alloy structures occur in places where air is excluded, often by entrapped moisture. Local corrosion may be the result of an electrochemical process, and when a film of liquid can act as an electrolyte, galvanic action is liable to occur between zones of unequal potential, as provided by dissimilar metals, different alloys of aluminium, or even the aluminium and its own alloying elements or impurities. Copper and nickel are particularly aggressive, iron less so.

Susceptibility of an alloy to corrosion is influenced by other internal factors besides its chemical composition, such as grain size, heat treatment history, and the stress to which the metal is subjected.

Food and Chemicals —

The aluminium employed for processing, packing, and cooking foods does not generally need protection, although for packing some products, cans may be lacquered. As the salts of aluminium are colourless, tasteless, and non-poisonous, there are no ill effects when strongly alkaline or acid foods dissolve minute amounts of the metal.

In the chemical industry, aluminium is extensively used, again generally unalloyed and sometimes of especially high purity. It offers considerable resistance to the action of most organic compounds and of such common chemicals as ammonia, sulphuretted hydrogen, and nitric and acetic acids; it is adversely affected by most alkalis, sulphuric and hydrochloric acids, chlorides, carbonates, and fluorides. Interaction is, however, dependent on the concentration and temperature of the reagent, and may be reduced or inhibited altogether by the presence of other substances. The whole subject is very complex and in the space available it is not possible to be more specific.

Protection

In any metallic structure, corners and crevices in which moisture can lodge should be avoided in design or effectively drained or sealed during construction.

Joints between aluminium and other metals can be insulated with a sealing paint (e.g. bitumen) or, preferably, with

an inhibiting paint containing zinc chromate or barium chromate. Copper and copper alloy parts should not be used near aluminium structures where there is any possibility of interaction through a moisture layer. Steel bolts, nuts and other fittings are best galvanized or cadmium-plated. Where water-absorbent materials, such as wood and cloth, are in contact with an aluminium surface, it is advisable to interpose a coat of varnish or bituminous paint.

In severe conditions, or when an alloy of inferior corrosion-resistance is to be used, all-over painting may be necessary. Correctly applied, paints last particularly well on aluminium, and should the metal be attacked through damage to the paint, there is no tendency, as there is with rust, for the attack to spread under the paint film. A good base coat is provided by the modern priming paints containing an acid reagent that expends itself in lightly etching the metal. In the best work this is followed by an inhibitive zinc or barium chromate paint, before the finishing coats are applied. Bituminous paint is satisfactory where it is not exposed to sunlight.

Another form of surface protection for strong alloy sheet is applied by the metal fabricator, by 'cladding'. The alloy ingot is sandwiched between plates of high-purity aluminium, which the hot-rolling operations bond permanently to the faces. By whatever amount the gauge of the sheet is thereafter reduced, each skin will represent about 5% of the total thickness, insulating the strong alloy core from attack and giving electrolytic protection at cut edges and scratches. 'Alclad' sheet was first developed for aircraft construction.

A protective measure widely used in certain fields is the anodizing process, in which the natural oxide film is thickened electrolytically in an acid bath. The film, when freshly developed, is absorbent, and if desired it can be dyed for decoration, or filled with a grease or wax for added protection.


Plating of aluminium with other metals, such as chromium, is practised on a relatively small scale for decoration or to improve the wearing qualities of machine parts. The presence of the oxide film complicates deposition, but reliable methods of overcoming this have been developed.

It may be found that the Noral Data Sheet, which lists mechanical and physical properties of our alloys, is a useful appendix to these articles. We shall be pleased to send you a copy; please mention this journal when writing.

The eighth article will outline thermal characteristics of the metal.

NORTHERN ALUMINIUM COMPANY LIMITED

TECHNICAL DEVELOPMENT DIVISION · BANBURY, OXON



Boiler house for New Classroom Block, Twickenham Technical College. County Architect : C. G. Stillman, F.R.I.B.A.

GAS solved this school heating problem

Gas-fired low pressure central heating is installed in this most recent extension to Twickenham Technical College, opened in 1948.

Factors which influenced the choice of boiler plant were : the distant situation of the new buildings in relation to the main boiler house ; the difficulty of providing fuel storage and access to it ; and the difficulty of providing a suitable chimney that would be unaffected by the proximity of adjacent high buildings.

The new single-storey block contains eight classrooms with cloakroom accommodation. The total catalogue rating of the two automatically controlled boilers is 720,000 B.T.U's per hour.

Helpful information on this and other aspects of the problem of securing efficient services for cooking, hot water, space heating and refrigeration may be obtained from the local Gas Undertaking.

GAS



"SILVER FOX"
REGD. TRADE MARKS

"SILVER FOX"

STAINLESS STEELS

are

MANY DIFFERENT STEELS

Under the general description 'Stainless Steel' there are available a whole range of alloys which have the general virtue of resisting corrosion. These offer a range of materials differing completely in composition, treatment and properties, in a way which is not always realised by the user who is proposing to solve a corrosion difficulty by employing 'stainless steel'. The "Silver Fox" Stainless Steel Catalogue shows how to determine the steel best suited to the designer's needs.

SHEETS · COLD ROLLED STRIP · WIRE · BARS · FORGINGS



SAMUEL FOX & COMPANY LIMITED

Branch of The United Steel Companies Limited

STOCKSBRIDGE WORKS · NR. SHEFFIELD · ENGLAND

® F235

HOLOPHANE ENCLOSED INDUSTRIAL UNITS

*Vapour proof
and
Dust proof*




Holophane Enclosed Industrial Units are designed for use where working conditions are such that lighting fittings must be vapour-, dust- and weather-proof while continuing to provide a satisfactory light distribution. The body-casting is constructed of silicon aluminium alloy and the prismatic-diffusing bowl encloses an internal prismatic reflector.

HOLOPHANE LTD

SCIENTIFIC LIGHTING ENGINEERS

ELVERTON STREET, LONDON, S.W.1. VICtoria 8062 (4 lines)

PRESSED STEEL TANKS



BRAITHWAITE & CO ENGINEERS LTD




London Office:

DORLAND HOUSE REGENT STREET LONDON S.W.1

Telephone: WHItchall 3993

Bridges · Wharves · Buildings · Screwcrete Foundations · Pressed Steel Tanks



ISOMETRIC VIEW.

A School for the City of Birmingham Education Committee

Siegwart Precast Floors and Roofs are being used extensively in Schools for various Education Authorities.

SIEGWART PRECAST FLOORS

SIEGWART FLOOR CO. LTD. GABLE HOUSE, 40 HIGH STREET, RICKMANSWORTH, HERTS. Telephone: Rickmansworth 2268
Branch Offices at Birmingham, Manchester and Glasgow.

Works at Croxley Green, Enderby near Leicester, and Paisley

S/S/51



We can deliver without delay to your site almost any quantity of standard joinery. What quality? The timber is the best we can buy and well seasoned at our Melton Mowbray works. The standards we work to are very high—for instance, our specification for priming is coating any knots with Shellac Knotting and then applying 100 per cent genuine lead paint by hand; and our window hinges are specially made of non-ferrous metal. May we send you our comprehensive catalogue?

Midland Woodworking

—> Standard Joinery where you want it, when you want it

THE MIDLAND WOODWORKING COMPANY LIMITED * MELTON MOWBRAY



KING'S BEAM HOUSE, MINCING LANE, E.C.

UNDER CONSTRUCTION FOR
THE CITY OF LONDON
REAL PROPERTY Co.

ARCHITECTS:
MESSRS. HOWARD, SOUSTER
AND PARTNERS


At home and overseas Wimpeys have built hospitals, schools, municipal buildings, complete townships overseas, banks, blocks of flats, factories, offices, airport buildings, power stations, film studios and grain silos. Well over 30,000 houses have been built in this country alone since the end of the war.

GEORGE WIMPEY & CO. LTD., HEAD OFFICE:
HAMMERSMITH GROVE, LONDON, W.6. Tel: RIVerside 2000

EDINBURGH · NEWCASTLE · MANCHESTER
NOTTINGHAM · CARDIFF · BIRMINGHAM

BAGHDAD · BORNEO · BRUNEI · SUMATRA
HONG KONG · SINGAPORE · CAIRO · SYDNEY

WIMPEY



"On all post-war housing schemes I have used only clay roofing tiles.
"Our Chidham houses, the subject of the award*, were all completed in 1949 at an average cost of £1,240 per house of three bedrooms with two separate living rooms. This cost compares very favourably with the figure of £1,321 given in the second report of the Girdwood Committee as the average cost for the whole country, and it compares still more favourably with the average cost in the Home Counties, including this area, which is reported to be £1,462 per house."

Extract from a letter received from Mr. J. K. Lawson, F.R.I.C.S., A.M.I.S.E.,
Engineer and Surveyor, Rural District Council, Chichester.

* Ministry Housing Medal.



For information on Clay Roofing Tiles, please apply to The Secretary, The National Federation of Clay Industries, Drayton House, London, W.C.1. (Euston 2568)



BOVIS

The red letters on the white Bovis board, seen on building sites throughout the United Kingdom, bear witness to the success of a system of building contract which is different.

In these days of uncertainty more and more Building Owners and their professional advisers turn to a method which assures control of speed and cost from start to finish.

STANHOPE GATE, LONDON, W.1

**REINFORCED
CONCRETE
ROADS**

***Cheapest in the
long run***



*Architects : Vine & Vine, A.A.R.I.B.A.
Contractors : Holland & Hannen and Cubitts Ltd.*

**WITH
REINFORCEMENT BY**


Matobar welded fabric reinforcement was used in the construction of this road on the Rookery Farm Housing Estate at Dagenham for the County Borough of West Ham.

McCALL'S

McCALL & COMPANY (SHEFFIELD) LIMITED

TEMPLEBOROUGH, SHEFFIELD · · AND AT LONDON

Focus on Floors



Corridors, whether in hospitals, schools or offices, present problems of their own when the floor finish is under consideration. The finish must, of course, be hard wearing and it must not easily become slippery. At the same time, since it is usually not possible economically to insulate wards, classrooms or offices from the corridor, it is important that not too much noise shall be created underfoot. A flooring may fulfil all these requirements, but can it safely be used under radiators? Can it be easily maintained in good condition by unskilled cleaners? Such queries may present no difficulties to you. On the other hand, there may be others, familiar to us, which have never come your way at all. Don't hesitate to use the Semtex Comprehensive Flooring Service. It exists to advise on all floor finishing problems, to supply and install any of the Company's floor finishes, and if desired to maintain them by contract in good condition. Semtex floor surfacings include: SEMASTIC DECORATIVE TILES SEMASTIC DOMESTIC TILES · DUNLOP RUBBER FLOORS · HIGH GRADE LINOLEUM · FLEXIMERS · CORK, CERAMIC AND TERRAZZO TILES.

SEMTEX LTD


(A Dunlop Company)

COMPREHENSIVE FLOORING SERVICE

185-187-189 FINCHLEY ROAD, LONDON, N.W.3

TELEPHONE: MAIDA VALE 6070

ISB/CIE



"THERMOLOK" is a modern aluminium decking of exceptional strength and rigidity, and is suitable for all types of roof structures.

The design is exclusive and embodies features which mark a big advance in roof construction.

The system is flexible and can be adapted to suit special requirements. "THERMOLOK" can be supplied in several gauges, and the bar sections increased to take spans greater than 10 feet.

A high insulation value can be obtained resulting in fuel economy and more comfortable interior conditions; condensation risk is reduced to a minimum.

The interior appearance of "THERMOLOK" with its pleasing design and light aluminium colour eliminates the necessity for a separate ceiling.

The light weight and strength of "THERMOLOK" enable economy in design of the sub-structure to be obtained to the maximum extent.

No scaffolding is necessary and a speedy erection is assured. Fastenings are reduced to a minimum by means of the patent locking device.

Durable waterproofing is provided by Anderson's "DUROK" Roofing System, and a variety of finishes can be given, if desired, to secure a pleasing appearance and to harmonize with surroundings.



D. ANDERSON & SON LTD

"THERMOSTEEL" DIVISION

STRET FORD, MANCHESTER
ROACH ROAD, OLD FORD, LONDON E.3

also at

Belfast • Birmingham • Glasgow • Leeds • Nottingham



FLEXIBLE DESIGN

SPEEDY ERECTION

LIGHT WEIGHT

THERMAL INSULATION

GOOD APPEARANCE

J N 81



TEST FOR A SEALING COMPOUND



Architect: Ralph Tubbs
Consulting Engineers:
Freeman Fox & Partners
Contractors for the Dome of Discovery:
Horseley Bridge & Thomas Piggott Ltd.


Thermal movements, wind vibration, not to speak of man-made structural disturbance during construction and routine inspection, are some of the factors that made weatherproofing the Dome of Discovery a problem. The sealing compound used had to 'give' without cracking, expand or contract without creeping and still be completely waterproof.


SECOMASTIC provided the solution to this problem. Correctly used, it is the best and most economical method of ensuring weatherproof joints wherever movement is likely to occur between two contiguous building units.

If you have a joint sealing problem, please consult our *architectural department*.

SECOMASTIC JOINT SEALING COMPOUND
REGD.

SECOMASTIC LIMITED, 11, UPPER BROOK STREET, PARK LANE, LONDON, W.1.
TELEPHONE: MAYFAIR 9080





The illustration shows two vertical panels on the left, labeled with thicknesses of 3/4" and 1/2". To their right is a large rectangular panel with dimensions 4' in width and 8' in height. The word 'PLIMBERITE' is printed in large, bold, serif capital letters across the top and bottom of the large panel. Between the two vertical panels, the text 'Available in two thicknesses —' is written above the dimension lines. To the right of the vertical panels, a list of applications is provided: 'for PARTITIONING', 'PANELLING', 'WALL CLADDING', 'ROOF LINING AND DECKING', 'FLUSH DOOR CONSTRUCTION', 'FITTED CUPBOARDS', 'SHELVES', 'VENEER CORE', and 'SUSPENDED FLOORING ★'. Below this list, a paragraph describes Plimberite as a high density resin bonded chipboard with structural strength, a hard smooth unpitted surface, and flameproof, sound, and thermal insulating qualities. A star symbol is placed before a note stating that vertical, static, and impact load tests have proved its strength when used as suspended flooring, and that a full report is available on request to British Plimber Limited. At the bottom, the company name 'BRITISH PLIMBER LIMITED' is followed by its address '20 Albert Embankment, London, S.E. 11.' and the reference 'REliance 4242'.

Available in two thicknesses —

3/4" 1/2"

4'

8'

PLIMBERITE

for PARTITIONING
PANELLING
WALL CLADDING
ROOF LINING AND DECKING
FLUSH DOOR CONSTRUCTION
FITTED CUPBOARDS
SHELVES
VENEER CORE
SUSPENDED FLOORING ★

Plimberite is a high density resin bonded chipboard possessing the general characteristics of natural timber and has considerable qualities of structural strength. It has a hard, smooth, unpitted surface on both sides and can be worked or machined using standard woodworking tools and techniques. Plimberite is flameproof, has excellent sound and thermal insulating qualities and provides a suitable base for the application of many surface finishes.

★ Vertical, static and impact load tests carried out by the British Research Station have proved the strength of Plimberite when used as suspended flooring. A copy of the full report on these tests is available to Qualified Architects and Builders on request to British Plimber Limited.

PLIMBERITE

Illustrated literature, technical data and the name of your nearest supplier available from:—

BRITISH PLIMBER LIMITED
20 Albert Embankment, London, S.E. 11. RELiance 4242

"WHAT A JOB
this could have been for
**PORN & DUNWOODY
LIFTS!**"



We make Lifts suitable for **EVERY** purpose. Consult us before completing your Plans. Meanwhile we shall be pleased to send you a copy of our illustrated booklet on request.




PORN & DUNWOODY LTD

UNION WORKS, BEAR GARDENS

Telephone :
WATERloo 7107 (4 lines)


LONDON, S.E.1.

Telegraph :
Ingporuma, Sedist, London



PDL 51/9


The "Plaxstele" suspended ceiling has a substantial plaster finish *with high fire resisting properties*



The "PLAXSTELE" ceiling system is adaptable to any type of building construction and can be suspended horizontally at any level below the main roof structure. It provides a suspended ceiling with a substantial, smooth plaster finish having high fire resisting properties.

The system combines the use of "PLAXSTELE" lath, specially designed for plastering with "PARISTONE" plaster, with metal patented suspension and jointing members which hold the lath rigid and at the same time anchor metal reinforcing rods in the plaster finish.

Advantages of the system include simplification of plastering work, saving of time, elimination of timber framing, superior strength, improved thermal insulation and high fire resistance (B.R.S. One hour. Grade D). Further information about this and other "GYPROC" products or systems will gladly be supplied.



The photographs show
a large area of PLAXSTELE ceiling before
and after plastering, decorating and
fixing strip lighting.

The isometric sketch shows
the general assembly of the component parts.

GYPROC PRODUCTS LIMITED

HEAD OFFICE: Westfield, Upper Singlewell Road, Gravesend, Kent.

Telephone: Gravesend 4251-4. Telegrams: Gyproc, Gravesend.

GLASGOW OFFICE: Gyproc Wharf, Shieldhall, Glasgow, S.W.1.

Telephone: Govan 2141-3. Telegrams: Gyproc, Glasgow.

MIDLAND DISTRICT SALES OFFICE: East Leake, Nr. Loughborough.

Telephone: East Leake 231.

LONDON OFFICE: Morris House, 1-5 Jermyn Street, London, S.W.1.

Telephone: Whitehall 9821-5.

Makers of "GYPKLITH" Light-weight Building Slabs,
"GYPSTELE" Partitions and Ceilings,
"PLAXSTELE" and "ACOUSTELE" Ceilings,
"GYPROC" 2-inch Solid Partitions,
"PARISTONE" Browning Plaster (Haird),
Unhaird and Metal Lathing Qualities,
"PARISTONE" Wall Finishing Plaster,
"CRETESTONE" Concrete Bonding Plaster,
"GYPSTONE" Board Finishing Plaster.

For Elegance, Smoothness & Reliability




ESTATE SLIDING DOOR GEAR

An exclusive "snap-on" pelmet conceals all fittings and will harmonize with picture rail or panelled effect. ESTATE gear is approved by the L.C.C. and is stocked by hardware firms throughout the British Isles and in many countries overseas. Supplies are readily available from your local merchants.

For really pleasing appearance, maximum space economy, swift gliding action, and long life, always specify ESTATE Sliding Door Gear. Consider how easily a lounge can be enlarged to include an adjacent dining room. Again, how convenient it is to enclose a small area for heat and light economy or to provide immediate and intimate seclusion. There are many other advantages which will readily occur to planners who are interested in a high quality product at a keen competitive price. All such purposes are fully covered by the range of ESTATE Sliding Door Gear. Many housing estates throughout the country are using ESTATE Sliding Door Gear.

Please write for descriptive literature and erection data.



CLARKE ELLARD ENGINEERING CO. LTD.
WORKS RD., LETCHWORTH, HERTS. Tel: 979

SEE OUR EXHIBITS AT THE BUILDING CENTRE, 9, CONDUIT STREET, LONDON, W.1
& THE SCOTTISH BUILDING CENTRE, 425-427, SAUCHIEHALL STREET, GLASGOW, C.2

BY APPOINTMENT
TO THE LATE
KING GEORGE V.



Chadderton Works of
A. V. Roe & Co. Ltd.



HEYWOOD'S
OF HUDDERSFIELD

Whenever there's a job to be done—large and expansive or small and intricate—we would like to prove to you that 60 years' experience and responsibility for over 80 million square feet of Patent Glazing has resulted in a Service at once helpful, reliable and speedy. The installation of new machinery has now made it possible to offer immediate service on all contracts.

May we have your enquiry and put forward our estimate and suggestions?

W. H. HEYWOOD & CO. LTD., HUDDERSFIELD. Telephone : 6594 (4 lines)


Branches at **LONDON** : 54 Victoria Street, Westminster, S.W.1.

MANCHESTER : 19 Old Millgate.

NEWCASTLE-UPON-TYNE : 57 Cathedral Buildings.

BELFAST : E. H. Pearce & Son Ltd., 29-33 Laganview Street.

and **LEICESTER, COVENTRY, LIVERPOOL, BIRMINGHAM, BRISTOL, NOTTINGHAM, PLYMOUTH, DUBLIN, GLASGOW** and **EDINBURGH**




The Projected New "South Works" for Messrs. Ashmore, Benson, Pease & Co., Stockton-on-Tees.
(Consulting Engineers: Messrs. F. R. Bullen and Partners, Dacre House, Dean Farrar Street, Westminster, S.W.1.)


STAGE I — *Constructional Shop with ancillary services and buildings.*

STEELWORK BY CARGO FLEET

From start to finish you get sound planning, economical use of materials, and a high standard of workmanship on every contract undertaken by Cargo Fleet. This first phase of 132,000 square feet floor area of the extensive new factory for Messrs. Ashmore, Benson, Pease & Co. Gas, Chemical, Iron Works Plant and General Engineers, now nears completion at Stockton-on-Tees.




Stanchions of a transverse bay, 30 feet high to the crane track. Crane tracks of the low bays are cantilevered out beneath those of the high bays giving easy transfer of material from the high bays to the low bays and vice-versa.



The Shop consists of four transverse bays 85 feet wide by 250 feet long and 30 feet high to the crane tracks, and two longitudinal bays 65 feet wide by 340 feet long and 50 feet high to the crane tracks, served by twelve overhead cranes, the heaviest being 50 tons capacity.

CARGO FLEET IRON CO. LTD., Constructional Dept: Malleable Works, Stockton-on-Tees. Tel: Stockton-on-Tees 66117



As Thermal Insulation Lining and Acoustical Specialists, we have behind us many years' experience in co-operating with architects and contractors, and have been entrusted with the insulation contracts for many large and well-known concerns.

Not only industrial buildings, but aircraft hangers, schools, offices, churches and underground railways have been successfully lined

by our fixing specialists by the Sundeala method. Efficient insulation will reduce the initial outlay on heating plant and decrease fuel consumption, for without insulation a high percentage of heat is wasted through your walls—so telephone now for our technical representative to call and discuss your particular lining problem. Remember, every day without insulation is money lost.

EASTWOODS

**SPECIALISTS IN THE APPLICATION OF THERMAL INSULATION
AND ACOUSTICAL LININGS**

W & C. 3a.

EASTWOODS SPECIALISTS LTD., EASTWOOD HOUSE, 158-160, CITY ROAD, LONDON, E.C.1.


TELEPHONE: CLERKENWELL 4333

A LITTLE **BEETLE** HOLDS GOOD

This is the eighth in a series of factual announcements

Beetle adhesive is the modern medium used today in the age-old craft of sticking wood to wood. Although there are many adhesives there is no type which economically combines with the same efficiency the strength, durability and water-resistant properties required in so many different wood-working applications. Beetle adhesive is available in close-contact and gap-filling forms for use with either hot or cold pressing methods.

Write for booklet giving full particulars.




FACT NO.29 AIRBORNE BEETLE

In a Handley Page "Marathon" aircraft every detail of construction has to pass stringently high standards. Beetle cements are used throughout for bonding the inside panelling of the passenger compartments.




FACT NO.30 BEETLE FOR SAFETY



Traffic signs have to be tough. H. Newsum Sons & Co. Ltd., Lincoln, who make them, find that waterproof plywood bonded to laminated plastic sheet does no more than bruise, even under severe treatment. Bonding by Beetle, of course.

FACT NO.31 BEETLE ON WHEELS

The Lincs Trailer Co. Ltd. specialises in the manufacture of beautifully appointed mobile exhibition trailers. The woodwork of the vehicles is bonded throughout with Beetle adhesive, chosen for its strength, durability and water-resistance.



FACT NO.32 BUOYANT BEETLE

Mr. H. B. Painter of Bristol built this dinghy of resin bonded plywood on oak and mahogany framing. Beetle adhesives did the rest. Mr. Painter wrote: "... your firm was the only one that had anything suitable to offer, and who took any trouble to advise me."



BEETLE ADHESIVES STRONG, DURABLE, WATER-RESISTANT

Sole Agents in the United Kingdom: BARTER TRADING CORPORATION LTD., 14, Waterloo Place, London, S.W.1

Overseas Distributors: Beetle Bond Ltd., 1, Argyll Street, London, W.1

'BEETLE' is a trade mark registered in Great Britain and in most countries of the world

WILD



*Builders
Elevators
now reach still
higher levels!*

—and raise over
2,000 bricks in an hour



Standard "Wild" Elevator in use at a housing site. Note the mortar buckets.

(Inset above). How "Wild" Elevators handle mixed loads of prefabricated units, etc.




For difficult site loading conditions, the "Wild" Conveyor can be attached to and used with either size of Builder's Elevator.

"Wild" Builder's Elevators are made in **two sizes**—the Standard Model, elevating to two storeys, and the larger Model, elevating to three. Both are readily transportable and have the same hourly capacity—2,000 bricks: 4,000 slates: 1,000 breeze blocks. The 30-ft. machine is specially suited for tiling.

PRICES STANDARD ELEVATOR £253
30-ft. ELEVATOR ... £383

(delivered free nearest siding, within 200 miles of our works.)

The "Wild" 30-ft. Elevator can reach the third storey of a building with ease.



The "Wild" 30-ft. Elevator is easily towed behind a lorry.

MANUFACTURED BY

M. B. WILD & CO. LTD., 50 PALL MALL, LONDON, S.W.1

TELEPHONE TRAFALGAR 4686 7

WORKS AND REGISTERED OFFICES: ARGYLE STREET, NECHILLS, BIRMINGHAM, 7

3,000,000

LONDON STOCK BRICKS

have been supplied to

**THE LIVE ARCHITECTURE
EXHIBITION**

Lansbury Site

Through the Member Companies of

**THE STOCK BRICK MANUFACTURERS
ASSOCIATION**

14 QUEEN VICTORIA STREET, LONDON, E.C.4

CITY 4333

NEWALLS

Sprayed
LIMPET ASBESTOS



COUNCIL CHAMBER,
BELFAST CITY HALL.

The ceiling illustrated has been treated with Sprayed Limpet Asbestos to reduce reverberation, and shows the excellent finish which can be obtained by this method of acoustic treatment.

Sprayed Limpet Asbestos is used wherever a Sound Absorbent Surface is required, and because of its Fire-proof and Vermin-proof qualities, it is especially suitable for use in Hospitals, Offices, Swimming Baths, and in other places where reverberation is excessive.

Newalls Sprayed Limpet Asbestos is also widely used for Acoustic Correction in Cinemas, Churches, and other Auditoria.

Newalls Insulation Co. Ltd., maintain a fully equipped Sound Laboratory for the investigation of problems connected with the use of Acoustic materials.

NEWALLS
Insulation Co. Ltd.

HEAD OFFICE: WASHINGTON, COUNTY DURHAM
A MEMBER OF THE TURNER AND NEWALL ORGANISATION.

OFFICES & DEPOTS AT: LONDON, GLASGOW, MANCHESTER, NEWCASTLE, BIRMINGHAM, BELFAST, BRISTOL & CARDIFF




PERMANENT COLOUR of Marley Tiles is achieved by surfacing with fixed-coloured granules. There is no free colour—tests by washing prove this. When these qualities are desired, the Specification should call for "Approved fixed-colour granule-faced concrete tiles."


MARLEY

The Marley Tile Co. Limited, London Road, Riverhead, Kent. Sevenoaks 2251/6



When a job needs  exactitude

 with lightness

 and **strength**


PUT Aluminium FIRST
AND Tl IN FRONT OF IT

T.I. ALUMINIUM LTD REDFERN ROAD, TYSELEY, BIRMINGHAM. TEL: ACOCKS GREEN 3333



THE A

No. 295



LON
TI
cra
ma
the
see
wo
an
alo

I
di
I
ar
in
d
o
C
t
h
f



THE ARCHITECTS' JOURNAL

No. 2951 20 SEPTEMBER 1951 VOL 114

EDITORIAL BOARD: (1) *Consulting Editor*, F. R. Yerbury, Hon. A.R.I.B.A. (2) *Guest Editor*, Frank Russon, F.I.O.B. (3) *Town Planning Editor*, Dr. Thomas Sharp, L.R.I.B.A., P.P.T.P.I. (4) *House Editor*, J. M. Richards, A.R.I.B.A. (5) *Technical Editor*, R. Fitzmaurice, B.Sc., M.I.C.E., Hon. A.R.I.B.A. (6) *Editor Information Sheets*, Cotterell Butler, A.R.I.B.A. (7) *Editorial Director*, H. de C. Hastings.

SPECIALIST EDITORS*: (8) Planning (9) Practice (10) Surveying and Specification (11) Materials (12) General Construction (13) Structural Engineering (14) Sound Insulation and Acoustics. (15) Heating and Ventilation (16) Lighting (17) Sanitation (18) Legal.

ASSISTANT EDITORS: (19) *Chief Assistant Editor*, D. A. C. A. Boyne (20) *Assistant Editor (News)*, K. J. Robinson (21) *Assistant Editors (Buildings)*, (21) L. F. R. Jones, (22) A. P. Lambert, (23) *Assistant Editor (Information Sheets)* E. G. Johnson (24) *Assistant Technical Editor*, M. Jay (25) *Photographic Department*, (25) E. R. H. Read, (26) H. de Burgh Galwey (27) *Editorial Secretary*, Betty E. Harris

* To preserve freedom of criticism these editors, as leaders in their respective fields, remain anonymous

9, 11 & 13 Queen Anne's Gate, Westminster, London, S.W.1 Whitehall 0611

Subscription rates: by post in the U.K. or abroad, £2 10s. 0d. per annum. Single copies, 1s. ; post free, 1s. 3d. Special numbers are included in Subscriptions; single copies, 2s. ; post free, 2s. 3d. Back numbers more than 12 months old (when available), double price. Half-yearly volumes can be bound complete with index in cloth cases for 25s. 0d. ; carriage, 1s. extra.



LONDON RECONSIDERED

The Poles have long been the master craftsmen among architectural model-makers, and the exhibition of plans for the improvement of London now to be seen at the ICA in Dover Street is worth visiting for the exquisite models and the charm of the presentation alone.

*

It is also worth visiting for the ideas displayed, some of which are illustrated, I believe, elsewhere in this issue. They are the product of many years' research into the problem of London by the civic design students and staff at the School of Architecture, Polish University College, London University. Behind them all are the ideas and energy of Konrad Smigielski, the assistant professor of civic design.

I have heard the criticism made that frankly Utopian projects of the kind shown, which take no account of cost or immediate practicability, do harm by identifying town-planning in the public mind with castles in the air rather than everyday realities. But the risk is worth taking if it persuades the London public to look at its own city more critically.

SOUND RESEARCH

I spent a day last week at Division I of the Building Research Congress—the meetings held at the Institute of Civil Engineers in Great George Street. Apart from the heat, which I suppose was due mainly to the weather, I was somewhat shaken by the noises off. Odd thumps I assumed to be pile driving for the Colonial Office, which is being built next door, but inside the building there seemed to be regular plumbing demonstrations and destruction tests on bell metal trays going on. However, the speakers persevered and I managed to hear nearly all that was said.

NEWS ABOUT JACK

The evening of the same day I attended a cocktail party given, with the lavish hospitality which is typical of them, by the LMBA for the overseas delegates of the Research Congress. Amongst the hundreds present I chanced to meet Dr. Walter Taylor of the United States, representing the AIA, whose task it is as Director of the AIA's research department to try and get some co-ordination of research in the States—the equivalent American task, in fact, of that of the European Building Research Organizing Committee whose meeting at Maidenhead I mentioned last week.

*

Dr. Taylor was able to confirm a report, which by an odd coincidence I had received in that morning's post, that

amongst the supplies of building materials and equipment which were getting increasingly scarce in the States (due, of course, to their enormous re-armament programme) there was a great shortage of supplies of jacks for slab-lifting. This technique, which has been copiously reported in the JOURNAL, is the development of the Texas Institute of Inventive Research, and I learn that they have opened negotiations (complicated by currency problems) with a manufacturer over here to make the slab-lifting equipment, with the possibility that, if the equipment is not snapped up for building operations in Britain, they will ship it to America.

*

Dr. Taylor, who had recently visited one of the buildings erected by this method, seemed very enthusiastic about its possibilities, and I gather that there are over fifty jobs using this technique now under way in the States. It is disappointing, though, that things move so slowly as far as this country is concerned.

FROM BRIGHTON TO VERMONT

In my strictures on the creaming of Brighton Pavilion last week I mentioned Clifford Musgrave's new book on the building but omitted to name it. It is called *Royal Pavilion: A Study in the Romantic** and is as admirable a history of its subject as one could well ask for. While the activities of Holland, Porden, Repton and Nash naturally take up most of Mr. Musgrave's space, he also finds room to recall the events (some of them fantastic enough) for which the Pavilion formed the setting.

*

From Brighton let me whisk your thoughts off to Kenwood, near Highgate. It isn't such a far cry as you

* Bredon and Heginbotham, Brighton. 15s

HOPE'S STEEL DOOR FRAMES

*will support 2 ft. of 4½" brickwork without
a lintel. Where an overload is required use*

HOPE'S 'BOXFORM' STEEL LINTEL

Light, clean and easy to handle



NO MORE CONCRETE LINTELS

HENRY HOPE & SONS LTD · SMETHWICK, BIRMINGHAM & 17 BERNERS STREET, LONDON, W.1

might suppose; for was not the architect George Saunders, who added the wings to Kenwood House as Robert Adam left it, "perhaps a pupil and certainly a follower of Henry Holland," who designed the villa which still forms the nucleus of the Pavilion? The phrase in quotes is from an elegant and very well illustrated little booklet just issued by the LCC under the title *The Iveagh Bequest, Kenwood: A Short Account of its History and Architecture**; author, John Summerson. To read it is to resolve to re-visit Kenwood at the earliest opportunity.

If I can't say that A. R. Woolley's *Oxford: University and City*,† made me resolve to re-visit Oxford at the earliest opportunity, it is because no book is necessary for that. But Mr. Woolley's book, which ingeniously contrives to be guide, miniature history and picture book at once, shall certainly go with me on my next visit to that still delectable city. My only quarrel with Mr. Woolley is that he doesn't mention *An Oxford University Chest*, which you will remember for Moholy Nagy's inspired photographs, in his bibliography.

Unfortunately, it isn't much good resolving to visit the buildings described by the late Thomas Tileston Waterman in *The Dwellings of Colonial America*‡—unless you have a cache of dollars in the right place. Most of us will have to be content with brooding over the photographs in this solidly produced book, which is likely to remain the standard work on Transatlantic Georgian (domestic) for many years to come. Its author, who died last January, was well known in the States as an architect who specialized in restoration work, as well as a writer.

CORRECTIONS

Two weeks ago, when referring to the radio exhibition, I commented unfavourably on the appearance of the hall in which it was being held. Unfortunately, I called the building the Empress Hall—which is the name of the nearby sports arena—but I intended my comments to apply, of course, to the Earls Court Exhibition Building. My apologies for this inaccuracy.

* L.C.C. 1s.

† Art and Technics. 21s.

‡ University of North Carolina Press.



Astragal comments on the Building Research Congress this week. Above are two delegates at the Congress: left, P. K. Jærgaard, the Architectural Director of Research in the Danish National Institute of Building Research, and right, W. A. Taylor (USA), Director Department of Education and Research, AIA.

I have, unfortunately, yet another correction to make. Last week I said that the MOW had finished restoring Thomas Archer's pavilion at Wrest Park. I learn now that the repairs are not yet quite finished and that the building will not be open to the public for some time.

FOB LIGHTING RECORD

I have received a copy of the latest issue of the *International Lighting Re-*

view, a sumptuous trade periodical published in several languages in Holland and distributed in this country by Philips Electrical. It is a special issue on the Festival lighting, and it is a particularly sparkling and courageous one in that not only are most of its illustrations night photographs but many of them are night colour photographs. These are no more aesthetically satisfying than most other colour reproductions but their technical brilliance is remarkable. It is pleasing to know that

This week Astragal brightens his pages with a puzzle picture. Where was this photograph taken? The answer, which is not Arizona, and will not—out of consideration for the reader—be printed upside down at the foot of the page, is to be found in the subject for this week's leader. And if that's what you thought Astragal apologises for bothering you.






An Adventure in Town Planning

The ICA's first planning exhibition is on view at 17, Dover Street, until October 6. This exhibition, which is commented on by ASTRAGAL on page 335, consists of a series of projects for the redevelopment of London. They are the work of the Civic Design staff and students of the Polish University College School of Architecture, London, under W. K. Smigielski. Above the St. Paul's area: conception by W. K. Smigielski, N. H. Gorwic and B. Schlaffenber, and detailed planning by M. Baranowski,

R. Kowalewski and W. Sieciechowicz. In the foreground are towers of offices and an exhibition hall for commercial goods. Beyond is a pedestrian way, flanked by the preserved Guildhall and offices, leading to the pedestrian precinct of St. Paul's. On the river front is a museum. The authors call this an "adventure" in town planning and say the exhibition is aimed to direct the public's attention to the almost forgotten aspect of three-dimensional design in town planning. See also page 342.

this full
Festival
gratulation
of Eind

COVI



N



"Pity
pleased

ELECTR

A qui
newspa
press i
of the
Electric
ings no
constru
will no
of an
we are
the m
velopm
be ma
housing
but an
ected
to be
beated
where
"comm
is left

In on
relieve
able s
extens
house
to ma
seem
quired
the in
and e

this full and permanent record of the Festival lighting has been made. Congratulations, Mr. Editor Sybren Kiers of Eindhoven!



"Pity it's so late, Maufe—it might have pleased almost everybody."

ELECTRICITY CUTS

A quiet announcement in some local newspapers, and later in the national press informed those lucky inhabitants of the area covered by the Southern Electricity Board that when their buildings now under construction, or to be constructed, are completed they will not be able to enjoy the blessings of an electricity supply. "Owing" we are informed "to the exhaustion of the money available for capital development no further connections can be made." It appears that the 1951 housing schemes will be in the clear, but any private houses not yet connected and any future work will have to be lit by candles and oil lamps and heated with gas or solid fuel, except where the Board regard themselves as "committed" though what this means is left delightfully vague.

In one case I know of the Board have relieved a house builder of an appreciable sum of money in return for an extension of their main to reach the house and now regret their inability to make a connection. This does not seem to be quite up to the standard required of an industry nationalized in the interests of the consumer, economy and efficiency.

ASTRAGAL

The Editors


WHAT NEXT ON THE SOUTH BANK?

WITH only a week or so to go before the Festival closes, it is natural that there should be a lot of uneasiness about what is to happen next on the South Bank site. The South Bank exhibition was not only a first-rate show, but also served the invaluable purpose of demonstrating how greatly London gained by the presence of good buildings, gay colours and the coming and going of people on a site that had been derelict for generations.

It would be a tragedy if the site were to be allowed to revert to its derelict state on the closing of the exhibition, pending permanent redevelopment by the LCC, which is bound to take many years in the present economic situation. Festival year, it is true, has given us the Royal Festival Hall, and the LCC promise riverside gardens within a short while. But these will not be nearly enough to rescue the site from a return to unsightly squalour if the temporary exhibition buildings are demolished as a matter of routine before plans have been made for the short-term utilization of the site, and if MOW is allowed to start excavations for the Government offices that are to be built alongside County Hall without making sure they can be completed within a reasonable time and without first establishing their relationship with the rest of the area.

There is no shortage of ideas for utilizing exhibition buildings for a few years longer. The public, having enjoyed riverside meals in the various restaurants throughout the summer, would like to see at least one of the restaurants continued, and consideration should be given to this before they are all demolished. The Arts Council wants the Lion and Unicorn building as a gallery for loan exhibitions—a proposal well in keeping with the LCC's zoning of the South Bank as a cultural centre; the cinema industry wants to keep the Telekinema—and so on.

In addition, much of the present planting and layout—especially in the downstream section—could beneficially be made the basis of the proposed public gardens, which need not for the time being be confined to the river front, even though the latter may be the only part of the site permanently allocated for use as gardens. The LCC's own design for the riverside gardens, moreover, could well incorporate such charming features of the exhibition layout as the look-out platforms belonging to the Seaside section which provide such an admirable architectural foil to the mass of the Festival Hall. So various are the possibilities that the Government has felt obliged to set up a "working party" to study them. It is to be hoped that the "working party" will have some positive recommendations to make soon and that no demolitions will begin until a proper plan has been worked out in consultation with the LCC. Only the Government itself is in a position to reconcile competing interests and ensure that the most is made of the opportunities of the site. If it fails to do so many of the long-term advantages of the Festival will be lost.



John H. Markham, F.R.I.B.A.

Geoffrey Dunn

W. E. Wright

H. C. Harris

Hung Drawn and Quartered

SIR,—I feel bound to address to you a few remarks on the subject of ASTRAGAL'S comments appearing in your issue of June 7. There are in it comments on the scheme we are carrying out at Tower Hill for the Tower Hill Improvement Trust. My attention was drawn to these at the time the JOURNAL appeared, but it seemed as though the author did not expect to be taken seriously; and, consequently, I had no idea of interfering, though I think it regrettable that architectural journalism should bring itself into disrepute by offering to its readers flippant observations arising from complete ignorance of the subject matter treated. We did, however, laugh, as I suppose your readers were expected to do. I should not, even now, refer to the matter, were it not that your remarks have ricocheted unpleasantly on to us from many directions and information now reaches us which shows that we are likely to suffer positive detriment.

It is this which prompts me to suggest that you may wish to introduce a little sober restraint in utterances that may do positive harm to members of the profession, though I am quite sure the writer of the remarks in question had no such intention.

May I add that helpful criticism, even if severely adverse, would, I think, be generally appreciated; but for this the critic must be properly informed. In this case—leaving aside fatuities as to "precinct" and "rest"—I might point out that the so-called "privy or mustard pot" is first and foremost an emergency escape stair from vaults below (insisted upon by the LCC). The panelling out of the paving was introduced in deference to a wish expressed by the Planning Authority, and the "off the centre line of the church" is inaccurate; but I am not concerned to refute criticisms, however frivolous. I only thought that for your future guidance you would be interested to know that this sort of levity can do positive damage.

London

JOHN H. MARKHAM.

[Astragal replies:—My criticism of the design (shown right), exhibited at this year's Royal Academy Summer Exhibition, was that it did not live up to its name of "Rest

Precinct." Another point was: why does the escape stair block the paths so carefully indicated by special paving? I regret that my efforts at criticism are so frivolous as to be not worthy of refuting. I further regret that such frivolity has caused Mr. Markham to suffer "positive detriment." Similar regrets must attack the conscience of theatre critics when a play which they have criticised fails to run. There is, surely, no solution to this. Getting the facts correct is not the whole answer. It is the interpretation of them in the same way as the author which is so difficult.]




Eric Ravilious

SIR,—With the South Bank Exhibition nearing its end, it is surprising to me that nowhere, as far as I know, has there been an illustration or reference to the delightful tribute paid to Eric Ravilious in the Lion and Unicorn building. I can only hope that the camera has recorded it, and that it will appear in good time, in order that the name and work of this great artist and industrial designer may be further perpetuated.

GEOFFREY DUNN

Bromley, Kent

[The photograph above shows the reconstruction of "Garden Implements"; a design by Ravilious for Josiah Wedgwood & Sons. Inset above the watering-can is the artist's original sketch.—ED.]



Below, Rest Precinct at Tower Hill. See letter from John H. Markham.

The Failure of Lead Soil Pipes

SIR,—I was indeed very interested to read the article in your issue of July 26, on the use of short lengths of 4-in. lead soil pipe with the requisite branches to take the place of cast iron fittings in a one-pipe plumbing installation, where the remainder of the soil pipe was in cast iron. The trouble you described would have occurred if the whole stack had been in lead. I was consulted, in a recent case, concerning a complete lead soil pipe which was giving trouble. The designer of this soil pipe had had double off-sets fixed at each floor, presumably to allow for the expansion and contraction which he quite rightly expected would take place.

I found that the failures were due to the sudden temperature changes suffered by the stack; the wc discharges being very cold and sometimes those from the bath, lavatory basin and sink being very hot. I have been instructed to remove the complete stack and replace it with one made from a more satisfactory material.

Lead does not contract as much as it expands. Having expanded, it does not return to the same size when the temperature is restored to normal. That this is true can frequently be seen in the case of a long lead bath waste tacked to the outside wall of buildings. You will find that the pipe between the tacks has sagged, with the result that instead of remaining straight, it often becomes wavy.

(The sketch referred to is reproduced here.) In the particular case you have illustrated, it might have been possible, by the correct fixing of the cast iron pipes, to have relieved the lead sections of undue weight, and allowance could have been made for expansion and contraction in each section. The lower floor failed because it is subject to more frequent temperature changes than the sections on the upper floors.


Cast iron and steel soil pipes have a coefficient of expansion corresponding more closely to that of the building itself and, so, when such materials are used, less elaborate precautions to allow for the movement are necessary. I have designed a large number of one-pipe plumbing systems and, like other large plumbing contractors, I experienced great difficulty in obtaining the necessary cast iron fittings. The standard fittings are not really adaptable to the one-pipe plumbing system and I started making my own substitutes. Because of its durability and because of the ease of working it, I chose copper. But, realizing that its coefficient of

expand
that c
sion j
interv
have
compl
bad p
notori
plete
tical

I M
firm
quant
suit th
be wo
in one
conj
and
branch
by ere
best.
would
archit
sets f
galvan
branch
rect p
time,
pipe
would
of the
of cou
one in
less
pointe

The
troub
descri
of the
prefat
like t
if steel
shoul
of an
the el
ing o
which


Birm



SIR,—
tradit
the p
rence.
factor
the w
tors c
was d
The
that
choic
prop
lead
cast i
ably
been
and s
pipe,
servic

L
th
C
[Bot
ferrin
nique
1951,
unusu

TIMBER STORAGE SHED AT SHOREHAM



In 1949, a storage shed (span 87 ft.) was erected at Shoreham, to demonstrate the possibilities of timber as a modern structural material. A 105-ft. span extension (left) was completed recently, using 3-pin portal frames (above). All timber was stress graded. Cost was only 3s. 3d. per cu. ft.


expansion is about 50 per cent. greater than that of the building, I arranged for expansion joints to be inserted at the necessary intervals at the height of the stack. It might have been cheaper to weld a copper stack complete from top to bottom but this is very bad practice. There have been one or two notorious cases of failure due to this complete welding up of the stack into one vertical vent.

I have since been fortunate in finding a firm willing to manufacture large or small quantities of soil pipe to my own design, to suit the particular building in which I may be working in. They are delivered to the site in one piece, ready for quick installation in conjunction with straight lengths of cast iron and with the wc, bath, basin and sink branches ready fixed in the position which, by erecting a prototype, was found to be the best. The firm to which I refer (and I would be pleased to give any enquiring architect its name) also make these soil pipe sets from heavy gauge steel pipe, which is galvanized inside and out after the branches have all been welded into the correct positions. I find that the installation time, using one of these preformed soil pipe sections, is considerably less than it would be if cast iron were used and the cost of the completely installed drainage unit is, of course, very much below that of a similar one in lead besides being more durable and less free from the trouble which you pointed out to your readers.

The only thing to be done with the troublesome mixed installation which you describe in your issue, is to take out each of the lead soil units and replace it with a prefabricated steel or copper one. I would like to warn your readers, however, that, if steel is chosen as a substitute material, they should do as I do and recommend the use of an insulating nipple which will prevent the electrical contact between the zinc coating of the soil stack and the copper pipes which lead into it.

W. E. WRIGHT

Birmingham



SIR.—There would appear to be some contradictory statements in the description of the possible cause of this unusual occurrence. 1. The work was performed satisfactorily; 2. the stacks were supported; 3. the weight of the stack was one of the factors causing the pipes to fail; 4. the failure was due etc., to hot water from bath wastes.

The example as reported suggests to us that the design is quite practicable, the choice of materials reasonable, but that proper recognition of the physical limits of lead was lacking when fixing the vertical cast iron pipes. It is, in our view, reasonably certain that if the cast iron pipe had been properly and separately supported, and some support given to the vertical lead pipe, the installation would give satisfactory service.

H. C. HARRIS

Lead Technical Information Bureau of the Lead Industries Development Council
London

[Both writers of the letters above are referring to an account in the Current Technique feature in the JOURNAL of July 26, 1951, page 114. The feature described an unusual failure of lead soil pipes.—ED.]



This week's Technical Section (page 353 onwards) deals with the Building Research Congress which closes in London today. The Congress was opened at the Institute of Civil Engineers on September 11 by Lord Samuel, the president, who is seen in the centre of this picture, and the first speaker (shown here) was Dr. F. M. Lea. On the right is K. Alsop, secretary of the organizing committee of the Congress. See also news item on page 342.



LONDON OF THE FUTURE EXHIBITION



Three of the fourteen designs for the future development of London, prepared by the Civic Design Staff and students of the School of Architecture, Polish University College, London, which are now on view at the ICA Gallery in Dover Street. Above, rehabilitation of the South Bank, by W. Henneberg and M. Mlek, with extension of the Port of London on the left, high blocks of flats in the background and offices and cultural buildings on the river bank. Bottom, project by T. Zawadzki for Piccadilly, with high level pedestrian way over the street. Through traffic goes underground. Centre, plan by K. Kopolka for linking Trafalgar and Leicester Square with a pedestrian way.



BUILDING RESEARCH

Opening of Congress

The opening session of the Building Research Congress, 1951, the first international congress of its kind, took place in the Great Hall of the Institution of Civil Engineers. After reading a message from the King, sent from Balmoral Castle, the president, Lord Samuel, gave an address of welcome to the 1,200 members and delegates from more than 50 countries.

The meeting continued with a speech by Dr. F. M. Lea, Director of Building Research DSIR. He said that experience in research pointed to the need for integration of results. Like many other branches of applied research serving a broad field of industry, it did not split neatly into the formal divisions of the sciences. The combination of modern technology and traditional method in the building industry was an uneasy process in which there were many pitfalls. The means by which the time-lag between research and application could be reduced were of vital concern. With divided responsibility collaboration was essential if branches were not to find very human reasons for failure to secure collective advance.

The meeting concluded with some brief remarks by Alister McDonald, the chairman of the Organising Committee.

RESEARCH COMMITTEE

Discussion on International Collaboration

At the second meeting of the Building Research Organizing Committee, which was held at Skindles Hotel, Maidenhead, from September 6 to 10, existing arrangements for international collaboration were examined, three subjects for immediate investigation were chosen and note was taken of the first edition of a *Directory of Building Research and Development Organizations in Europe*, a UN publication.

It will be remembered that the Committee, which consists of representatives of seven countries and seven non-governmental international organizations, under the chairmanship of R. Fitzmaurice, is a subsidiary organ of the United Nations Economic Commission and was appointed to examine the need for—and possible nature of—new arrangements for international collaboration in building research.


A thorough survey of the work of each international organization in the field of building research had been prepared as a

WINN

The lim
at Dum
Dunoon,
RIBA,

UPP


WINNING DESIGN FOR THE DUNOON PAVILION COMPETITION



The limited competition for a new pavilion and concert hall at Dunoon, promoted by the Town Council of the Burgh of Dunoon, and assessed by A. Graham Henderson, President, RIBA, was won by Ninian Johnson, of Glasgow, with the


design shown here and on pages 344-5. Six firms were chosen to compete, being selected, by Graham Henderson, with a view to giving an opportunity to junior firms in south-west Scotland.

Upper ground floor plan, and, inset, site plan




UPPER GROUND FLOOR


DUNOON PAVILION AND CONCERT HALL COMPETITION: WINNING DESIGN




Lower ground floor plan



Section E-E




Elevation to gardens




Entresol, and top, gallery floor.

The existing pavilion in Dunoon was recently partly destroyed by fire. The same site, the most prominent one in the town when viewed from the sea, is to be used for the new pavilion. The following accommodation was required to be provided:—A main conference hall of about 7,000 sq. ft., for dancing and badminton, with a balcony to seat 500. A lesser hall, of 4,200 sq. ft., to seat 700, to be used for concerts. A tea-room, seating 200, and kitchen. Shops on the street frontage, and the requisite cloak-room and lavatory accommodation.


DESIGN BY NINIAN JOHNSON




SECTION A-A



SECTION B-B



SECTION C-C



SECTION D-D

The assessor, A. Graham Henderson, comments:—"This is a very able design and its particular features are (1) it encroaches least on the Castle Gardens area; (2) it provides easy and convenient access both for those arriving on foot and in cars. In particular, the cover provided for car entry is a good feature; (3) the disposition of the three major elements, large hall, concert hall and front buildings, is such that they can be built separately, although obviously the large hall and front buildings should, if possible, be built together; (4) its general architectural treatment is suitable for, and suggestive of, the uses to which the buildings are to be devoted; (5) the spacious nature of the main crush hall which leads to the three main apartments to be used by the public and the direct and dignified approach to these apartments. There are minor defects in this design—in particular, the arrangement of gallery in the main hall which is placed wholly at one end, but I am satisfied that such defects as the design has will far outweigh its general merits relative to the other designs submitted."

basis for discussion at the recent meeting. The report of this survey stated that "the most important aspects of building research which are to present the subject of systematic or effective arrangements for international collaboration are research into concrete and other building materials through the Union of Laboratories, research into illumination organized by the International Commission on Illumination, and research into soil mechanics arranged by the International Society of Soil Mechanics and Foundation Engineering. This leaves a large, indeed the greater part of the field of building research as a whole not covered by any effective arrangements for international collaboration. Important examples which can be cited are the whole field of building methods and operations, building design, and large parts of such fields as building structures, user requirements, town planning and building economics."

Subject to small amendments in detail, the Committee accepted the report prepared as a fair statement of the existing arrangements for international collaboration and of the manifold gaps in the existing arrangements.

The three subjects chosen on which international collaboration should begin right away were:—(1) The volume of habitable rooms, with particular relation to ceiling heights; (2) the use of common flues venting several heating appliances in multi-storey dwellings, and (3) the studies of the economy of multi-storey dwellings in terms of variations in height and width on plan.

The Committee considered that the subjects chosen would be very suitable as a test of methods of international collaboration, as many fields of research activity would have to take part.

The way is now clear for an examination by the Committee of the need for new international arrangements for collaboration and the nature of such arrangements. This task will be undertaken at the next meeting of the Committee to be held in Geneva next March.

HOUSING

Figures for July

The number of permanent houses completed in Great Britain in July was 15,965. This is 1,238 less than the figure for June. The number of houses completed under the post-war programme is now 1,086,715 (929,569 permanent and 157,146 temporary).

AA

Symposium on College Design

The success of the Symposium on Hospital Planning, held in December, 1950, has encouraged the AA Council to organize a second Symposium to be held at 134, Bedford Square, W.C.2, on Wednesday, November 14, this time on the subject of "The Design and Planning of Colleges for Further Education." The meeting will again last for one day, from 9.30 a.m. until 6 p.m. Architects and educationalists will speak on various aspects of the subject and take part in discussions.

A summary of the papers will be circulated to those attending, who are advised by the AA to consult the Ministry of Education Bulletin No. 5. Accommodation is limited. Members should make early application for places, and those wishing to bring non-member guests specially interested in the subject are asked to submit their names at the same time. The fee for members and their guests will again be one guinea each.

FESTIVAL OF BRITAIN PRESS AND RADIO CLUB : AT GREAT



This club is housed in two floors of a building converted for the purpose by Hilton Wright, who was also responsible for the decorations. Left : the main bar, on the first floor. John Morton and Tom Lupton, who were associate architects for this, also designed the fixed seating and some of the bar furniture. - The dining recess to the left of this picture indicates the view point from which the photograph, top right, was taken. Lucien Day designed the curtains. The wallpaper has sage and olive green stripes. Below is the main room on the ground floor. The information desk was originally designed as a bar. The photograph, centre, right, shows part of the ground floor lounge. Its window overlooks a courtyard leading into Great



Scot
blue
print
pleat
lounge
floor

are j
colou
signe
tray
The
desig

SCOTLAND YARD



Scotland Yard. The upholstery is navy blue and the deep red wallpaper was printed in flock. Lampshades are of pleated paper. Another part of this lounge (bottom) has a raised bar with cork flooring. The tables on the steps, which



are fixed in place, are painted in different colours. The smaller tables beyond, designed by Nigel Walters, have removable tray tops which can be replaced by cushions. The basket backed chair was specially designed for the club by Tom Lupton.



DIARY

Symposium on Prestressed Concrete Statistically Indeterminate Structures. At 52, Grosvenor Gardens, S.W.1. (Sponsor, CCA).

SEPT. 24 TO 25

The Reconstruction of Rotterdam. Speakers: J. Meertens, J.P., van Bruggen, J. A. C. Tillemma, C. van Traa, A. Bos. (Sponsor: HC.) At 13, Suffolk Street, S.W.1. 5.30 p.m.

SEPT. 25

18th Annual Conference of Smoke Abatement Society. At Blackpool. (Details from Society, Chandos House, Buckingham Gate, S.W.1.).

SEPT. 26 TO 28

London: An Adventure in Town Planning. Exhibition of work by Assist. Professor Smigielski, staff and students of the School of Architecture, Polish University College. At ICA, 17-18 Dover Street, Piccadilly, W.1. Weekdays 10 a.m. to 6 p.m.

UNTIL OCT. 6

Exhibition of British Popular and Traditional Art. Sub-title: Black Eyes and Lemonade. At the Whitechapel Art Gallery. Daily except Mondays, 11 a.m. to 6 p.m. Sundays, 2 p.m. to 6 p.m.

UNTIL OCT. 6

Exhibition of Architecture. Sponsored by the Institute of Registered Architects. The above exhibition will be on view at the following places:—Mile End Library, Stepney (until Sept. 22); East Finchley Library (Sept. 24-Oct. 6); Thomas Parsons Showrooms, 70, Grosvenor Street, W.1. (Oct. 8-19); Council Office, Surbiton (Oct. 22-27); Building Exhibition, Olympia (Nov. 14-28.)

ERNEST WATKINS

The Architect and Current Affairs

Architects, particularly in private practice, live in a world of contract. Apart from the main contract, they are surrounded by a host of others, with contractors and sub-contractors. Today, most of these contracts are based on standard printed forms, adapted to the circumstances of each case. Occasionally, the adaptation is imperfectly done. Sometimes there is a gap left in the provisions, sometimes there are discrepancies between one section of the print and another, and sometimes there is a conflict between what is printed and what some party claims was said and agreed at the time.

A recent decision in the Court of Appeal shows the legal rules governing that last situation. A cattle dealer put up some Guernsey cattle for sale in the market. The auction catalogue contained a printed clause which read: "No animal . . . is sold with a warranty unless specifically mentioned at the time of offering, and no warranty so given shall have any legal force or effect unless the terms thereof appear on the purchaser's account." Bidding for one animal hung fire and before any bids were made the owner stated he would absolutely guarantee her in every respect and that he would be willing to take her back if she turned out not to be what he stated she was. The animal was sold for £65. Four months later it had died from tuberculosis. The buyer claimed back the £65. The seller pleaded, first, that he had not given any warranty (his evidence on that was not accepted by the judge) and, secondly, that the buyer had no legal right to claim because of the printed clause in the auction catalogue.

The Court of Appeal confirmed the buyer's right to recover the £65. In substance it

held that the contract under which the animal was sold came into existence only after the seller had, in effect, said, "The animal will be sold on the faith of the verbal statements I have made, to the exclusion of anything in the printed form which would seem to rule out any verbal statements." In other words, it may be that the words and actions of the parties themselves during the making of the contract show that a particular printed clause, apparently a part of the contract, was never intended to be included. A quotation from the judgment of Lord Justice Denning sets out the general position of those who wish to rely on printed notices and conditions: "A party who is liable at law cannot escape liability by simply putting up a printed notice, or issuing a printed catalogue, containing exempting conditions. He must go further and show affirmatively that it is a contractual document and accepted as such by the party affected." This was not the case with this catalogue."

A COMMON CONTRACT PROBLEM

A second recent decision in the Court of Appeal illustrates another point on contract not infrequently encountered. One party, say the owner of a building, has some work done for him in the building. It is done badly someone suffers injury as a consequence, and the building owner is faced with a claim for damages. He settles the claim and then calls on the person whose negligent work was responsible for the injury, to pay over the amount he himself has paid out. How far can he say, "I acted reasonably in settling that claim. It is not open to you to question what I did. You are bound to pay over the amount I paid out, as representing the damage I suffered through your negligence." Or, to put it another way, if one party bases his claim on a settlement he has made, can the other party challenge that settlement and demand that the person who made it prove all over again how it was arrived at?

This case concerned some bituminous adhesive mastic sold to the Dutch Government. It was defective and the claims based on the defects were agreed to, during the course of an arbitration, at £43,000 and costs. The intermediaries then claimed the £43,000 and costs from the suppliers, basing their claim on the fact that that was the amount paid to the Dutch Government under legal advice. The judgment of the Court can be given in the headnote to the case: "The party making the settlement must show not merely that he acted reasonably in settling the claim against him, but also that the settlement arrived at was in itself reasonable; but the Judge at the trial must consider the evidence, and if he came to the conclusion that, in the circumstances, the settlement was reasonable the amount paid in settlement by the plaintiff was the measure of damage recoverable by the plaintiff from the defendant."

Finally, I have been given the report of a case in a county court in the Midlands, one which is in very much the same territory. It raised no principle; its application is practical. A firm of flooring contractors sold and installed in a motor showrooms a floor of plastic tiles. Unfortunately, after the tiles were laid it was found that they took the imprint of the tyres of cars standing on them, while, if petrol were spilt, it marked the tiles where it dripped. When the flooring contractors claimed for their bill, the owners of the showrooms counter-claimed for the cost of replacing the floor, and for loss of the use of the premises while the replacement work was being done. The decision went in favour of the show-room proprietors. The moral of this story would seem to be: "Don't specify a particular article for a job unless you know all about both the article and the conditions it will have to face in service." This would seem straightforward advice, but —

HOUSE


in NORTH END, HAMPSTEAD HEATH, LONDON N.W.3
designed by the ARCHITECTS' CO-OPERATIVE PARTNERSHIP

A small house was required for the client and her husband, who designed it particularly for ease of running and the maximum feeling of space inside. The site consists of a plot approximately 70 ft. square at the end of a long narrow garden belonging to the client's parents. The type of plan used claims to provide privacy where necessary, and yet condenses space which is needed purely for circulation to less than 2 per cent. of the floor area.


The garden front looking north-west.




The first floor living room and balcony, with outside stair to the garden on the right and staircase to the ground floor on the left.



Section A-A



PLAN.—The plan was kept as free as possible within the limitations of the structure, with the living room on the first floor due to the enclosed nature of the site. It was also desired that any future children should have their own access to the garden and separation from the rest of the house when required, by the conversion of the ground-floor bedroom to a nursery. If economic conditions



Ground and first floor plans and site layout
[Scale: $\frac{1}{4}$ " = 1' 0"]



View from the garden looking north.

HOUSE

in NORTH END, HAMPSTEAD HEATH, LONDON N.W.3
designed by the ARCHITECTS' CO-OPERATIVE PARTNERSHIP

had allowed, the architectural expression would have been very different, with the use of a lighter form of construction.

CONSTRUCTION.—There are 11-in. cavity load-bearing walls with a $4\frac{1}{2}$ -in. brick outer leaf and a $4\frac{1}{4}$ -in. breeze inner leaf. The first floor is of lattice steel joists carried out on the south-east facade to sup-

port the balcony. Partitions are of breeze blocks and the roof is of timber trusses.

FINISHES.—Corrugated iron, screed and quarry tiles are laid on the first floor lattice joists and the ground floor ceiling is of plaster board. The roof is covered with blue-grey Penrhyn slates and the facing bricks are buff-yellow in colour. The specially-






ks and

quarry
nd the
roof is
facing
cially-

CEILINGS | BUILDING BOARD

22.D14

The Architects' Journal Library of Information Sheets 329. Editor: Cotterell Butler, A.R.I.B.A.



FULL-SIZE DETAILS.

TENTEST 4FT. PANEL SYSTEM OF BOARD FIXING FOR SUSPENDED CEILINGS.

Manufacturer: Tentest Fibre Board Co. Ltd., Specialised Construction Department.

22 D14 • TENTEST • 4FT. PANEL SYSTEM OF BOARD FIXING FOR SUSPENDED CEILINGS

This Sheet describes a system of board fixing which combines the use of Tentest insulating board with steel or aluminium alloy supporting members. The system is mainly applicable to flat or curved ceilings.

General System

The boards are carried on tee sections which are slotted at approximately 9-in. intervals to take spring-steel fixing clips which hold the boards in position. All sections are flush-jointed on the underside and mild-steel reinforcing battens, fixed at approximately 1 ft. 4 in. centres to the top surface of the boards, prevent the boards from sagging. The board is trimmed at the walls by means of an aluminium-alloy angle section plugged and screwed direct to the wall face or by a channel section screwed from the underside to a timber ground.

The main tees are supported on clips or strap hangers suspended from the main structure at not more than 10-ft. centres.

Components

Main tees : These are of extruded aluminium-alloy or cold rolled steel and are available in two sizes—1½ in. for 10-ft. maximum spans and 1⅜ in. for 8-ft. maximum spans both sections having flanges 1⅜ in. wide.

Main tee splice plates : These are of steel and are used for jointing the main tee sections.

Noggings : These are of aluminium alloy and measure ⅝ in. by 1⅝ in. They are fitted at either end with mild-steel extension pieces which rest on the flanges of the main tees.

Reinforcing battens : These are of mild steel and measure ¾ in. by ¾ in. They are fixed to the top surface of the boards with coil springs (see detail) at 9-in. centres and run parallel to the noggings. The battens are fixed to the boards before the boards are lifted into position.

Clips : Spring-steel clips in conjunction with mild

steel lever clips are used, as shown, to secure the boards to the main tees and noggings.

Wall finishing angle and channel : These are of aluminium alloy and measure 1⅝ in. by 1⅝ in. and ⅞ in. by ⅞ in., respectively.

Insulating Boards

Tentest standard insulating boards ½ in. thick are fixed in lengths of up to 10 ft. by 4 ft. wide.

Finish

The aluminium-alloy sections are normally supplied in their natural finish.

Sound Absorption

½-in. Tentest insulating board has a sound absorption coefficient of 0.30 at 500 cycles per second.

Thermal Insulation

The thermal conductivity coefficient (k) of Tentest insulating board is 0.37 B.Th.U./sq. ft./hr./1°F./in. thickness.

Acoustic Boards

Perforated acoustic tiles and the Tentest Company's "Rabbit Warren" S.C. acoustic board (in sizes up to 10 ft. by 4 ft. wide) can also be fixed by this method. Details are given on Sheet 27.B1.

Compiled from information supplied by :

Tentest Fibre Board Co., Ltd., Specialised Construction Dept.
Head Office : 75, Crescent West, Hadley Wood,
Barnet, Herts.


Telephone : Barnet 5501 (5 lines).
London Office : 18, Pall Mall, London, S.W.1.
Telephone : Whitehall 9366

FLOORS FINISHES | RUBBER


19.F2

The Architects' Journal Library of Information Sheets 330. Editor: Cotterell Butler, A.R.I.B.A.

19.F2



SQUARE NOSINGS. (scale $\frac{3}{4}$ full size)



ROUND NOSINGS. (scale $\frac{3}{4}$ full size)



COMBINED TREADS, NOSINGS AND RISERS. (scale $\frac{3}{4}$ full size)

RUBBER STAIR TREADS, NOSINGS AND RISERS.

Compiled from information supplied by The British Rubber Development Board.

19.F2 RUBBER STAIR TREADS, NOSINGS AND RISERS

This Sheet describes various rubber stair treads, nosings and risers. The nosings may be used with rubber or any other sheet flooring and are selected from the wide range which is available. Nosings may be either smooth-surfaced or ribbed.

General

Rubber nosings may be obtained to fit treads of any normal depth or thickness, any projection and shape of nosing and any width of stair. Nosings of any section may be formed to fit the contours of curtail steps or other features. Separate treads, risers and nosings are especially recommended in cases of heavy traffic as they enable the nosings alone to be replaced when they become worn.

Square Nosings

These may have rubberised canvas flanges to fit under the tread and in some cases the riser as well. Alternatively the nosing may be returned to butt against the riser, or tapered or moulded to meet the riser.

Round Nosings

These may have rubberised flanges to fit under the tread and a variety of mouldings is obtainable.

Combined Treads, Nosings and Risers

The drawings at the bottom of the Sheet show some typical sections which can be made to order.

Preparation of Surfaces

Similar sub-structure conditions are required to those specified for rubber floors. See Sheet 19.F1. Mouldings under nosings should not be fitted to new staircases and it is advisable to remove them from existing staircases.

Laying

Before laying the rubber, the stairs should be made smooth, clean and dry. The adhesive should be applied to both the stair surfaces and rubber in accordance with the rubber manufacturer's or laying contractor's recommendations. The adhesive should

be allowed to become substantially dry and tacky before the rubber is laid in position. When placing the rubber in position the surface should be smoothed out and particular care taken to avoid the trapping of air.

Adhesives

Details regarding adhesives are given on Sheet 12.N1.

Colours

Treads and risers can be supplied in a wide range of plain or marbled colours. Nosings are usually supplied in a wide range of plain colours and white, the latter being particularly suitable in public buildings. 1, 2 or 3-line borders and nosings may be supplied in self-colour or marbled patterns.

British Standard

Rubber treads, nosings and risers are formed from solid rubber which should comply with the requirements of British Standard 1711 : 1951 *Solid rubber flooring*.

Further Information


The British Rubber Development Board maintains a Technical Information Bureau which is available to answer questions and advise on technical problems dealing with this subject generally.

Compiled from information supplied by :

The British Rubber Development Board.

Address : Market Buildings, Mark Lane, London, E.C.3.

Telephone : Mansion House 9383/4.



Details of first floor balcony and outside staircase (Scale: 1/4" and 3/4" = 1' 0")

designed windows are of wood painted white and are thought to be of a maximum size compatible with the æsthetic form of the building. All walls are plastered internally and painted white. The ground floor is covered with deal blocks, the bathroom

HOUSE

in NORTH END, HAMPSTEAD
HEATH, LONDON, N.W. 3
designed by the ARCHITECTS'
CO-OPERATIVE PARTNERSHIP



Above, living room on the left and bathroom and lobby on the right. Right, the garden door to the dining room under the first floor balcony.





Left, the ground floor dining room with the hatch to the kitchen on the left of the staircase. Below, left, the living room with the main bedroom seen through the door on the left. Below right, looking west with the garden entrance on the right.

HOUSE

in NORTH END, HAMPSTEAD HEATH, LONDON, N.W.3
designed by the ARCHITECTS' CO-OPERATIVE PARTNERSHIP

floor is of black and white vitreous tiles and elsewhere quarry tiles are used.

SERVICES.—Heating is by radiant heat effected by circulating hot air in the first-floor cavity formed by steel joists, as a closed circuit. This gives floor heating to first floor and ceiling heating to ground floor. The boiler, which burns anthracite, also heats the water. There is no flue other than for the boiler.

The general contractor were Yeomans & Partners, Ltd. For sub-contractors, see page 364.



Contin
Build
1951,
marie
of M
(Swe
Stock
summ
(Stru
BUI
The
GEN
RESE
ha
conclu
facts.
tion it
rate in
But en
distinct
is not
enginee
butes
Durin
great i
materi
weight
creased
mainly
strengt
work l
of a si
concre
formed
cent. o
in slab
cold-w
stress
cally a
cent.
regard
Swedis
cent., l
econom
There
in mo
investi
urgent
ledge
and co
allowa
quently
designe
But in
eccentr
irregul
of elas
greater
past. A
lation
theory
prelim
approx
stated
be dist
and ex
of reso
plore.
once a
One
explor
webs i
plastic
the us
science
very go
and s
theory

Continuing our reports of the Building Research Congress, 1951, we publish below sum-

TECHNICAL SECTION

maries of papers presented to Division I, Part 2, of the Congress, under the general title of "The Influence of Modern Research on Structural Design." Starting with an introductory paper by G. Wastlund, (Sweden), Professor of Structural Engineering and Bridge Building, Royal Institute of Technology, Stockholm, there followed four sections, dealing in turn with concrete, steel, timber and light alloys. These summaries, together with the comments at the end, were prepared by the JOURNAL's Specialist Editor No. 13 (Structural Engineering). (All illustrations are reproduced by permission of the Congress.)

BUILDING RESEARCH CONGRESS, 1951

The Influence of Modern Research on Structural Design

GENERAL REVIEW by G. Wastlund.

RESEARCH is an exhaustive investigation having for its aim the revision of accepted conclusions in the light of newly discovered facts. As applied to a discovery or invention it is a systematic study of the separate influences on the factors in its make-up. But engineering is a science in which the distinction between research and practice is not well defined, so that every progressive engineer developing new structures contributes to research.

During the last 50 years there have been great improvements in structural design and materials; for example, in Stockholm, the weight of apartment buildings has decreased from 860 to 450 lbs. per sq. ft. due, mainly, to improved materials of higher strength. More recently, welding in bridge-work has saved 20 per cent. on the weight of a similar riveted structure. In reinforced concrete the introduction of high-tensile deformed lug reinforcement has saved 44 per cent. on the weight of plain steel bars used in slabs under similar conditions. In Austria cold-worked deformed bars, of allowable stress 50,000 lb. per sq. in., are so economically advantageous as to form about 80 per cent. of steel reinforcement used. With regard to timber, the amount used for Swedish houses has fallen by about 12 per cent., largely as a result of more careful and economical design.

There are, however, a number of points in modern research which require further investigation. For a start, there is still an urgent need for deeper theoretical knowledge. Building materials, particularly steel and concrete, have improved in quality and allowable stresses have increased. Consequently, structural members can now be designed much more slenderly than hitherto. But in slender structures, the influence of eccentric loads, of defects in materials, of irregularities in shape and dimensions, and of elastic and plastic deformations are much greater than in the heavier structures of the past. An improvement in methods of calculation is therefore necessary. However, theory can be exact only in relation to the preliminary assumptions, and these are often approximated to the actual conditions. As stated above, research and practice cannot be distinctly defined and often developments and experiments have indicated the channel of research which the theorists should explore. Their findings can then be verified once again by experiment.

One field which the theorists might well explore further is that of the buckling of webs in steel plate girders within the semi-plastic or plastic region. This will involve the use of a new branch of theoretical science—"rheology"—which deals with very general relations between deformations and stresses, independently of classical theory. "Rheology" is today at much the

same position as was the theory of elasticity in 1821 when the general elastic equations were formulated by Navier.

Another group of problems suitable for theoretical analysis is connected with the behaviour of structures under the action of dynamic forces. For bridges with increased spans and greater slenderness the dynamic effect of traffic and wind load has become very important. In buildings, dynamic problems are now given greater consideration on account of the new severe requirements regarding sound insulation and the elimination of vibration due to machines, traffic, etc. The effects of detonations in the air and in the earth, or impact from shells, fall into a similar field of investigation; so do the effects of earthquakes.

Experimental research, as distinct from pure theory, serves to deepen our knowledge of building materials and structures. It is necessary to study not only the various properties of building materials and the effects on them of external factors, we must also understand the reasons for these effects. This can be done both by observation and by theoretical deduction.

Recent trends in experimental research have tended to unite and relate the different natural and engineering sciences in a way which allows progress in one science to cause unexpected developments in another. As a natural consequence of this, the importance of physics and chemistry for experimental building research has increased considerably. In particular, materials research needs all the help that can be afforded by these sciences. Suitable examples for this field of research include: brittleness of steel and light alloys (particularly in connection with welding), the plastic deformation of concrete, deterioration of concrete due to freezing and thawing, and the shrinkage and inner stresses of concrete. Well-equipped laboratories are essential for the progress expected to be achieved. Expensive equipment, such as the electron microscope, X-ray diffraction apparatus for crystal analysis, and the spectrograph, are invaluable in materials research. The study of metals—clays, lime and cement—also falls within the scope of this research. Revolutionary changes in the manufacture of steel have resulted from fundamental research and, with the more recent application of physics in building science, a radical improvement in materials is to be expected in the future, which may revolutionise building construction as new materials have done many times before.

In modern research on structural engineering, new developments in measuring methods have been of vital importance. Inventions such as electric strain gauges and inductive and magnetostrictive gauges have made new investigations possible. Also, tests of models

of bridges and other structures can be made more accurately than hitherto as a result of the use of new modelling materials, such as plexiglass. Structural elements can be considered in the laboratory under static and dynamic action, and short-term and long-term influences can be taken into account. Comparisons can be now made of the behaviour of existing structures by means of direct measurements.

The main materials under consideration in Division I of the Congress are steel, reinforced and prestressed concrete and wood. Steel can be used conveniently for structures which have to be erected quickly or which may be changed, moved or strengthened at a later date. It is suited to large-span structures, where dead weight is important and where the cost (compared with that of reinforced concrete) is favourable. Steel structures can on the whole, give a more slender design. Disadvantages include unsatisfactory fire resistance, the difficulty of maintaining protection against rusting, and the fact that the natural resources from which steel comes are widespread and so valuable for other purposes that they must be utilized carefully.

Concrete, if well made, provides an adaptable, durable material suitable for most common requirements. It is cheaper than steel and provides satisfactory fire resistance. Reinforced concrete is, in many countries, the dominant structural material, except for long spans. Its disadvantages include high dead weight, low tensile strength, swelling and shrinkage, and the necessity of using formwork for casting. The site work involved is comparatively lengthy and governs the quality of the concrete. Resistance to freezing and thawing and chemical action is far from satisfactory. Prestressing can eliminate much formwork on the site and provide better quality control. Cracking is, thereby, minimised and durability increased.

Wood is often used as a structural material, particularly in timber-producing countries, such as Sweden. It is easy to handle and provides reasonable strength in at least one direction. Its disadvantages are many: combustibility, swelling, shrinkage, creep, variability of moisture content, knots, etc. However, it can be treated against attacks by insects and animals and the effects of moist air.


For roofs reinforced concrete can be economical if the roof plate can be incorporated in the structure, as in T-beams or shell roofs. Prestressed concrete and reinforced lightweight concrete can be used effectively for prefabricated roof slabs. Lightweight slabs spanning up to 20 ft. have been manufactured in Sweden.

In general, the choice of material depends on: the type of building, supply of mate-

floor
h the
tchen
the
elow,
room
bed-
rough
left.
oking
arden
right.



Roof covered with light-weight concrete roof planks. Details of beam reinforced with deformed lug bars.



materials, cost (including maintenance, insurance, etc.), strength, weight, durability, insulation properties, climate, aesthetics, supply of labour and machinery, erection methods and resistance to fire, shocks, etc. It is important that the architect, when designing a building, should consider many physical properties of the materials he proposes to use. For example, the transmission of water, vapour and heat must be carefully calculated. Take the single-storey factory building with a flat roof, so typical of industrial buildings of the last 20 years. In northern countries many defects often arise: condensation of water, decreasing thermal insulation, deterioration by freezing and thawing, water percolation, swelling, cracking of the felt roof covering, etc. Research has found answers to some of these problems, but it is necessary to design the buildings and choose materials with due regard to the humidity, thermal conditions, special requirements of the building and, of course, the climate.

Structurally we can distinguish between certain major groups of buildings, such as flat buildings, buildings with several storeys, halls without cranes, with light cranes and with heavy cranes. But the structural form will finally depend not only on the type of building, but also on foundation conditions, span lengths, lighting, pipes and ducts to be drawn and possible future extensions or changes in the use of the building. Moreover all factors influencing the choice of the materials to be used also influence the structural form.

As to the future, discovery and invention will probably provide the greatest gains and new materials and erection methods may once again revolutionize building and engineering. Theory, being mathematical in character, provides a slower contribution. Aluminium alloys, while being too expensive today will probably soon be in common use for structural work. It is not yet possible to say what part will be played by synthetic materials but they will undoubtedly come into use in some way or other. New materials having better heat-insulating properties will be produced. If these could be combined with load-bearing properties they might lead to lighter, and perhaps thinner, structural elements. It is to be hoped that research will also eliminate many of the disadvantages of our traditional materials.

The four papers on reinforced and prestressed concrete were given by Hjalmar Granholm (Professor of Building Technics, Chalmers University of Technology, Gothenburg), F. G. Thomas of the BRS, Watford, A. R. Collins (technical director of the C & C A, London) and A. L. L. Baker (Professor of Concrete Technology, Imperial College, London).

CONCRETE

In the four papers which followed Professor Wastlund's introduction were considered various modern developments in research on reinforced concrete, prestressed concrete and shell construction.

H. Granholm's paper was devoted to a discussion of the merits of high-tensile indented bars. His arguments are based on Swedish practice and his own research work. The limit of the permissible stress in reinforcing steel is occasioned by the risk of cracks arising in the concrete rather than by the ability of the metallurgist to produce steel with a higher yield limit and a higher ultimate strength. This problem is concerned with the bond between concrete and its reinforcement, and great efforts have, therefore, been made to achieve a closer bond. Two methods suggested are, firstly, the use of smaller diameter rods and, secondly, the use of rods with a corrugated surface. When the latter type, under 16 mm. diam. are used, Swedish regulations allow a stress of 31,000 lb. per sq. in. and Professor Granholm's investigation suggests a possible increase to 42,000 or even 55,000. He quoted the example of a beam used in industrial property in Stockholm. Because of the use of tightly-


packed, light reinforcement, cracking after six years was negligible. Further research will be carried out on the problems of using corrugations to increase bond.

The remainder of the paper was devoted to an explanation of the method of calculation which is based on the plastic properties of the concrete and the steel. Professor Granholm considers that the accepted theory based on Hooke's Law is unable to represent properly the conditions in a structure at or near breaking point, and that dimensioning by the breaking-load method should supersede the elastic method.

This point was carried further in the paper by F. G. Thomas, in which he considered the ultimate strength of columns, walls and beams. Formulae were suggested for the design of axially-loaded columns and beams, but a satisfactory method for designing columns subjected to bending is not yet available. Work carried out at the Building Research Station on creep, shrinkage and cracking and their effects on structures was described. In the field of fire resistance a method has been evolved for comparing tests under laboratory conditions with the actual conditions of natural fires. It is considered that to reduce the size of columns when high-grade concrete is used would be a disadvantage, and the high proportions of steel might lead to a proportionally high loss of strength in the event of fire.

Most of the research work which has been carried out on reinforced concrete has had some bearing on prestressing, but some of the most significant discoveries are those leading to a better understanding of creep. However, much of the work on prestressed concrete will be of benefit also to users of ordinary reinforced concrete. Dr. Collins set out in great detail in his paper the various aspects of prestressed concrete research now being carried out. The work on creep, mentioned above, has been concerned primarily with concrete which we would now describe as being of only medium quality. With the development of concrete with a 28-day crushing strength of 20,000 lb. per sq. in., much new data are required. The production of such high strengths requires vibration and, despite the wealth of conflicting evidence, Dr. Collins considers that it should be possible to determine optimum conditions for various uses. A fundamental investigation appears to be necessary. More study of the behaviour of high-tensile steel at high temperatures is required and such study may prove the advisability of using alloy steels where fire risks are great. Research on the use of alloy steels and high-tensile steels in larger diameter rods also seems desirable.

In the application to structures, prestressed concrete may be used in flat slab construction, though trouble may arise in bending of the outer columns. A similar problem arises in obtaining continuity in prestressed frame construction. Road slabs have already been designed with combined longitudinal and transverse prestressing, with the idea of



Standard Swedish indented reinforcing bar.

increasing load carrying capacity, but the saving in slab thickness may not compensate for the cost of the complicated arrangements required for two-way prestressing. An alternative is longitudinal prestressing, which can be applied at low cost. It is employed mainly to reduce the need for joints.

In his paper on shell construction A. L. L. Baker considered problems affecting the design of part-cylindrical shells. Jenkins's elastic theory gives accurate results under working load conditions when the shell is not cracked and there is no plasticity or tendency to buckle. But rupture theories appear to give more accurate values of ultimate strength, despite approximations with regard to stress distributions, because they take into account the effect on stress distribution of cracking, buckling and ultimate strains of steel and concrete. It is hoped that trial designs and tests will indicate the suitability of the various design methods for many types of shell, both for working and ultimate loads. The author described a method of force net analysis, which helps in determining fairly quickly the best shape for the shell and which gives approximate analytical results, neglecting the effects of longitudinal slab bending and torsion. He suggested that experience may prove that this type of analysis is satisfactory for design purposes. Experiments at Imperial College were described and show close agreement with the theories of Jenkins and Schorer.

The three papers on structural steelwork design were given by George Winter (Head of the Dept. of Structural Engineering, Cornell University, USA), F. A. Partridge, of a famous British firm of engineers, and J. F. Baker (Head of the Dept. of Engineering, Cambridge University). The fourth paper in this section, on the application of welding to steel structures, was by F. Campus (Professor at the University of Liege, Belgium).

STEELWORK AND WELDING


In the first of the four papers on research in structural steelwork, G. Winter discussed three separate topics: new tendencies in the established field of traditional steel structures fabricated from standard, hot-rolled members; new uses of steel in forms other than hot-rolled shapes; and general tendencies in structural design. Hot-rolled members can be the basis of floor, roof and wall supports but they cannot be used economically for the actual floor, roof or wall. In the past, these have usually been constructed of other materials. However, corrugated steel for roof and wall sheeting has been in use for some time and, recently, steel roof decking has come into standard use. Professor Winter has been in charge of research at Cornell University since 1939 and efforts made there have culminated in the adoption of a Code of Practice for Light Gauge Steel Standard Members, so that, with both the

practical and the legal aspects removed, the use of light-gauge steel for structural purposes has become widespread. It is used for structural elements of conventional shape (Fig. 1) and also in the form of load-carrying panels for floors, roofs and walls (Fig. 2). Light-gauge floors have been used in heavy frame structures of 30 or more storeys, resulting in reduced deadweight, quicker construction and increased space for services. A similar development is taking place in the use of light-gauge structural sections for wall and floor framing, roof trusses, etc., but


this has been retarded by the shortage of sheet steel.

With regard to general tendencies in steel design, Professor Winter's paper overlapped both that of F. A. Partridge and that of Professor J. F. Baker. The latter has been intimately concerned in investigating the behaviour of steel-framed buildings since 1929, in an attempt to derive rational and, therefore, more economical methods of design. The study of the frames of actual buildings in course of construction, together with comprehensive laboratory investiga-

Test on a portal frame in a study of redistribution of moments. Considerable increase of load was carried after incipient failure of the column-head section. The horizontal reactions at the foot of the columns was measured with helical springs, which were adjusted to give zero spread of the feet. (Crown Copyright Reserved.)



3-in. thick prestressed shell under test at Imperial College.



Reinforced concrete shell at Imperial College after collapse due to longitudinal compression accompanied by buckling.







Fig. 3.

tions of beam to stanchion connections, led to the production in 1936 of certain "Recommendations for Design." But this design method, based on elastic behaviour, was not acceptable to the industry because of its relative complexity. The increased reliability of welding now makes possible rigidly jointed frames and attention has, therefore, turned to steel structures in the plastic range, and it is hoped that a simple method of design will be evolved as a result of the consideration now being given to the condition of structures at the point of collapse. While it cannot yet be claimed that the behaviour of structures within the plastic range is understood thoroughly, the boundary of knowledge has been advanced sufficiently to indicate that these hopes are justified.


The collapse loads of portal frames in which axial loads are small can be calculated readily by the method. Thus, a fixed-base frame as shown in Fig. 3, loaded vertically at the centre and horizontally at beam level, will fail according to one of the "modes" shown in Fig. 4. The mode of collapse in any particular case depends on the ratios of the loads and the full plastic moments of the beam and stanchions. Small-scale tests and full-scale frames have confirmed that these assumed modes of collapse are correct. The full-scale work indicated, however, that certain factors, such as strain hardening, limiting deflections and lateral instability of the members, which had little effect on these particular tests, might assume much greater




● PLASTIC HINGES

Fig. 4.

Right, Fig. 1. Light-gauge steel structural sections.



Right, Fig. 2. Light-gauge steel decks and panels.



importance for frames of other designs subjected to other load conditions.

Professor Winter drew attention to the fact that the extreme simplicity of the analysis applies only if the structure is subjected to one single pattern of loading. If various types and character of loading have to be considered, as is usual in most practical structures, a complete elastic analysis must be carried out, in addition to the plastic analysis; also, the plastic analysis is realistic only if the structure is capable of developing complete plastic hinges, and if these hinges are, in turn, capable of undergoing considerable plastic rotation without the occurrence either of local buckling or of brittle fracture. Whether this finding can be generalized to include all continuous steel structures remains to be proved. Nevertheless, it is certain that the theory has not only enhanced our basic understanding of structural action, but that its influence on practical design is already making itself felt. For example, the USA basic design code now allows an increase of 20 per cent. in allowable stress at interior supports of continuous beams and in extreme fibres of columns subjected to combined bending and direct stresses.

The final paper in the steel section was by F. Campus of Belgium, who dealt with research into the welding of steel structures. The use of welding in steel structures is of fairly recent origin—a matter of some twenty years—and research is in its early stages; certainly, its final goal of a widely-accepted code of practice has yet to be achieved. The contractors' objections to welding are obvious—its more extensive use would render obsolete the plant and workshops used for the fabrication of riveted and bolted work, which represents large amounts of invested capital. Hence finance is not forthcoming for the extension of this research.

However, research concerning welding itself is very well advanced. Gas welding and electric arc welding are in brisk competition, the latter being more appropriate for steel structures, while the use of spot welding may be suitable for the fabrication of light-gauge, cold-formed steel members. The quality of weld metal now obtainable may be considered suitable for all purposes. Both static and dynamic strengths of single welds are well known and, provided the welds are sound and free from important defects, are perfectly reliable.

Stresses due to welding can also be predicted (with some approximation in cases of restraint) and often reach the elastic limit. With reliable data regarding shrinkage and thermal expansion, it is possible to make good use of the prestress due to welding.

Two papers were given on Timber. The first, by Philip Reece, of the TDA, London, on structural uses of timber in the UK; the second, by Carson Morrison, associate Professor of Civil Engineering, University of Toronto, Canada, on glued laminated timber.

TIMBER

P. O. Reece reviewed the structural use of timber in the United Kingdom. It is evident that, between 1939 and the present day, timber has changed from being a relatively cheap and plentiful material, occupying a position of primary importance in British economy, to one which is relatively costly and scarce. There are three aspects of timber economy: complete elimination, reduction in use, and balanced consumption. In the first case, substitute materials must be found; in the second, design must be improved and sizes, safety margins and waste reduced; in the third, the use of home-grown timber saves imported timber and the use of hardwood and plywood saves softwood. Sizes and margins have now been reduced to a point consistent with safety and it appears that little further progress can be made in the reduction of waste. Curtailment of home felling has restricted the substitution of home-grown for imported timber and the increasing importance of the cost factor has hampered the substitution of sterling hardwoods for softwoods.

It is considered that, at the present time, the most profitable field for research lies in improving the design of softwood structures, in the development of uses for hardwoods in which their higher cost is justified, and in the development of structural uses for plywood, as increasing supplies permit. The outstanding virtue of timber as a structural material is its stiffness per unit weight and its cost. The most promising

field for research, in fact, is in the use of timber components in elastic structures, through the use of shear. An increase in the loads on buildings, large floor areas, bridges, etc. An increase in the capacity of the structure. Woods are accepted as given. Timber is a great asset in jointing, efficient bolts, nails, gluing, and nailing. The growth of timber is determined by which of the are: timber, the use of timber, a paper on the use of recent timber, be produced, state, materials, steelwork, when for str, beams, a subs, its mo, as cur, of var

field for engineering research lies, therefore, in the direction of structures or components which are liable to fail through elastic instability or bending rather than through direct tension, compression or shear. This points to structures or components which are large in relation to the loads they have to carry: single storey buildings of all kinds, especially those of large height and span; roofs of all kinds; floors of moderate or low loading; footbridges; towers; pylons; etc.

An important development is the codification of working stresses and design procedure. A classification of structural softwoods with basic stresses, which has been accepted by the Timber Code Committee, is given in Table I.

Timber is weak in shear and the development of efficient shear-resistant joints is a great advance in timber engineering. The jointing materials in order of structural efficiency are: adhesives, timber connectors, bolts, nails and screws. Since the war, attention has been given to the connector, as gluing is essentially a prefabrication technique and prefabrication has almost been ruled out by the scarcity of timber.

The general purpose of research is to determine the class and form of structure to which a material is inherently suited and to codify design procedure. Various aspects of the latter which require investigation are: strength properties of commercial timbers, methods of jointing, the application of structural theory to an anisotropic material and preservation.

Glued laminated timber was described in a paper by C. F. Morrison of Canada. The use of laminated timber is comparatively recent and, by shop processes, there can be produced a timber unit larger and stronger than can be found in its natural state. It is not a substitute or inferior material but has, in fact, replaced structural steelwork to a considerable degree, even when steel is in good supply. When used for straight members, such as columns and beams, laminated timber can be considered a substitute for sawn solid members, but its more usual and more effective uses are as curved rafters, truss chords and arches of various shapes. Because of the thinness

Right, section of 3-hinged arch using $\frac{3}{4}$ -in. laminations of southern yellow pine. Note arch form and clamping device.


Bottom, a laboratory test on 12-ft. length of standard house roof of 21 ft. 6 in. span. Load is distributed through steel tapes from link system.



TABLE I

Class	Standard Name	Flexure and compression parallel to grain	Tension	Modulus of Elasticity		Shear parallel to grain	Compression perpendicular to grain
				Mean	Min.		
All values are in lb./sq. in.							
A	Douglas fir (coast) Longleaf pitch pine Shortleaf pitch pine	1,000	1,500	1 600,000	1,000,000	100	350
B	Canadian spruce European larch Redwood Whitewood Western hemlock	800	1,200	1,200,000	750,000	100	250
Mean value of Modulus may be used for rafters and floor joists. Min. value is appropriate to principals, hinders, or other components acting alone							

Mean value of Modulus may be used for rafters and floor joists.
Min. value is appropriate to principals, binders, or other components acting alone



of the laminations, it is possible to dry the material in much less time than would be required for large structural members. But a disadvantage is that the total cost of a member, including cost of the timber, drying and surfacing the laminations, glue, its application, assembly, application of pressure and curing, is high.

Only one paper was presented to the Congress on the subject of light alloys. This was by A. G. Pugsley, Professor of Civil Engineering at the University of Bristol. The discussion on this paper brought to a close Division I of the Congress.

RESEARCH ON THE DESIGN OF LIGHT ALLOY STRUCTURES


Professor Pugsley's paper was devoted mainly to a consideration of the stability of structural sections. Research at Bristol and Newcastle has covered torsional properties of sections, lateral stability of beams, and torsional and local stability of struts. Investigation of torsional properties at Bristol has indicated that practical limits to the use of light alloy sections in torsion are likely to arise either by the onset of permanent twist as the proof torque is reached, or by the occurrence of excessive elastic twists. A proof torque should be adopted corresponding, perhaps, to a permanent twist of 0.001 radians per inch length.

The modulus of elasticity of light alloys, being approximately one third that of steel, indicates an increased liability to lateral instability. Experiments suggest that, where joists or floor slabs sit directly on the section in question, a surprising resistance against lateral instability is provided.

In the case of torsional stability in struts, research has indicated which sections are most liable to instability and it is hoped that the theory will be developed to provide some simple method of design. Local stability investigations have already contributed to fundamental knowledge of buckling. Alternative remedies are to make thicker some of the present standard sections or to stabilize outstanding flanges and thin webs by beads, lips or longitudinal corrugations, as shown in the diagram below.

Joining of light alloys may be by aluminium or steel rivets, welding or adhesive materials. Research on all kinds is in progress in this country and has so far indicated that the conventional theory for steel rivet design may need some extension or reorientation for aluminium work.

Local instability of a thin light alloy channel section.



Although using an inert gas to envelop the welding area has given some success, little use has yet been made of welding. Special adhesives have been used successfully in aircraft work, but they require to be set under pressure and at a controlled temperature.

The following comments on the papers summarised above are, like the summaries, by the JOURNAL'S Specialist Editor No. 13 (Structural Engineering).

The papers in Division I Part II give a fairly comprehensive picture of the scope of present research as applied to concrete, steel, timber and light alloys. Despite Professor Wastlund's attempt to define research in engineering, it appears rather difficult to distinguish between developments which have arisen from practice and those resulting from research. In the end, however, the interest of the architect or builder is directed to the development itself and its effect on aesthetics, the economy of materials and labour and the cost of building.

The authors of the papers all seemed to agree that the aim of research should be to investigate more fully the nature of the materials under consideration. The plastic theory of design was advocated both for steel and concrete, and will show an economy in material. The properties of steel were well defined and it seems reasonable to suggest that the main efforts in plastic design should be directed towards structural steel. A laboratory for the British Welding Research Association has been constructed as a series of single-storey, four-member frames, designed on the plastic theory and the frames show a saving of 17 per cent. in weight over frames designed on the classical method. For such frames the design procedure is straightforward but the full value of this theory will not be felt

until its scope has been extended to more complicated framed structures, without undue complication of the design method. Far more knowledge of the physical properties of concrete is required, however, before the plastic theory can achieve similar results in reinforced concrete and, for full economy, a much tighter control will be required of the quality of site concrete—a none too easy task in building work.


The only reference to reinforcing steel was to the use of the deformed high tensile rod. The claims that there is less liability to cracking, in view of the smaller diameter of the bar, and that higher allowable bond stress can be used are sound, and there is a saving in weight of steel of about 40 per cent. On the other hand, the cost of the steel in the work is 25-30 per cent. higher and the actual saving in total cost is very small.

In the field of prestressed concrete the scope for research is enormous and, with greater knowledge of creep in concrete and steel, bond, shrinkage and anchorage losses, we may expect more economy in material. With the development of higher strength concretes, the design of slender structures of much larger spans will be possible. Under our present hostages, prestressed concrete saves both concrete and steel. The use of longitudinal prestressing for roads can cut out expensive joints and maintenance at joints.

It was surprising to find only one slight reference to prestressed structural steel members. Professor Magnel has done considerable work on this subject and it was dealt with at some length by Professor Soete of Belgium in a paper to the 1951 International Welding Congress.

The development of light-gauge steel members in the USA is interesting but is of little help to the present building problems in this country. When more sheet steel is available, its use for floors and wall panels may lead to a reduction in dead weight.

Aluminium is still in its infancy as a structural building material and, at present, its high price prevents serious competition with steel on the initial building costs. It is best used under such conditions of low live to dead load ratios as in the new hangar for BEA at London Airport.



Some special light alloy sections suggested by Temple. A, angle section strut. B, beam with high torsional stiffness. C, I-section strut. D, plate stiffener.

specify
a paint
you CAN
specify...



There can be no doubt about what goes into a Genuine White Lead Paint : its formulation is rigidly determined by a British Standard


Specification—No. 261/1936. There can be no doubt, either, about the protection it gives against all weathers, and, with a 100% basic carbonate white lead paint—such as Cookson's Crescent Brand—there is never any doubt about its long term economy. We mean economy—in spite of the present cost of lead paints. For the paint represents the least part of the cost of an average painting job : labour, scaffolding, and preparation are the major cost items. Long life in the paint is the real economy—and

WHITE LEAD PAINT LASTS

ASSOCIATED LEAD MANUFACTURERS LIMITED

IBEX HOUSE, MINORIES, LONDON, EC3 . CRESCENT HOUSE, NEWCASTLE . LEAD WORKS LANE, CHESTER
EXPORT ENQUIRIES TO: THE ASSOCIATED LEAD MANUFACTURERS EXPORT CO. LTD. IBEX HOUSE, MINORIES, LONDON, EC3





Fifty years ago (or less) a phrase like "The decorative possibilities of glass" could have referred to windows moulded in imitation frost-spangles, to panels rich with ruby interlacings, to gilded humming birds on overmantels. Today it could not. Shall we regret the change? Chance Reeded and Reedlyte glasses are of the present time. Indoors and out, in flats, hotels and offices, in screens, partitions, lights, they give *directional emphasis* without fuss, *privacy* without obscurity, *texture* without traps for dust.



CHANCE REEDED

- Narrow Reeded ($\frac{1}{8}$ in. ribs)
- Broad Reeded ($\frac{3}{8}$ in. ribs)
- Major Reeded ($1\frac{1}{2}$ in. ribs)
- Cross Reeded ($\frac{1}{2}$ in. ribs)

CHANCE REEDLYTE

- A stipple-finish version of Reeded to give increased obscuring power.
- Narrow Reedlyte ($\frac{1}{8}$ in. ribs)
- Broad Reedlyte ($\frac{3}{8}$ in. ribs)

The maximum size of the above glasses is 100 in. x 42 in.

Free samples of glass and detailed literature will be forwarded on request.

FOR SCIENCE, INDUSTRY AND THE HOME

CHANCE BROTHERS LIMITED, Glass Works, Smethwick 40, Birmingham. Telephone: West Bromwich 1824
LONDON OFFICE: 28 St. James's Square, London, S.W.1. Telephone: Whitehall 6002. Branch Works at Glasgow, St. Helens and Malvern

The
Buil
Buil
pape
is re
shou

D I
IN

The
with
survey
consid
Even
resear
applie
mater
invest
ticabl
been
fore.
divisi
omitt
studie
overl
the st
omit
lines
mity
these
stagn
prese
some
main
subje

OBJEC
Near
mater
indire
use, a
with
speci
weath
sistat
assen
rain;
withs
is, of
Que
mate
engin
fundi
impa
the
mate
jects
and
follo
part
natu
dural
mate
influe
whic
tance
natu
spher
the
inter
mate
parti
fied.
walls
reaso
avail
type
cons
quire
ence,
the
relat
great

The introductory paper to Division 2 of the Congress—the division dealing with Building Materials—was given by Dr. T. W. Parker, Deputy Director of Building Research at the Building Research Station, Watford. This important paper, which was entitled “General Trends in Research on Building Materials”, is reprinted below in full. In it, Dr. Parker emphasized that materials research should include the study of fundamental problems as well as day-to-day work.

DIVISION 2 : BUILDING MATERIALS

INTRODUCTION by Dr. T. W. Parker (Great Britain)

The division of this Congress which deals with research on building materials has to survey a wide range of subjects on which a considerable amount of work has been done. Even though it is recognized that building research has come late into the field of the applied sciences, the study of building materials has reached a stage of detailed investigations such that it would be impracticable to touch on all the items which have been pursued. Certain of them have, therefore, been selected for discussion in this division, while others have had to be omitted. In dealing thus with detailed studies, however, it is important neither to overlook the broad trends which have led to the studies taking their present form, nor to omit to consider the most fruitful broad lines of direction for the future. A unanimity of viewpoint is unlikely on either of these; it would indeed be almost evidence of stagnation of thought if it were so. The present paper, therefore, while presenting some views by one author, is intended mainly as a basis for discussion of the subject.

OBJECTIVES OF RESEARCH

Nearly all forms of research on building materials can be traced either directly or indirectly to questions of performance in use, and until recently have dealt in effect with the cure or avoidance of failure in three specific directions: stability, durability, and weather resistance. The term weather resistance is used to mean the ability of an assemblage of materials to exclude wind and rain; the alternative meaning of ability to withstand the weather without disintegrating is, of course, included in the term durability.

Questions of stability and the strength of materials are traditionally associated with engineering studies, although the more fundamental properties of materials which impart cohesion and strength remain within the purview of those studying building materials. There remain then the major subjects of durability and weather resistance, and more or less automatically there must follow a pattern of investigation. The first part must deal with the identification of the natural or man-made influences which affect durability; the second, the properties of materials which are affected by these influences; and the third, the properties which produce good or bad weather resistance. On the first, most attention has naturally been paid to the action of atmospheric conditions, while a peculiarity about the second is that it has necessitated the intensive separate study of individual materials. Until recently, it has not been particularly fruitful to study materials classified, say, into materials for roofing or for walls, or into any other classification. The reason is probably that the actual materials available to the builder are so diverse in type, both physically and chemically, that a considerable degree of specialising is required. The diversity is such that the differences in importance that one or other of the factors in natural weathering possess in relation to the different materials has a greater bearing on the applied science of

building than whether the materials are to be used in one or other positions on the outside face of a building.

The properties of a material which bear on its ability to protect the interior of the building against the weather, and particularly against rain penetration, are not necessarily the same as those which affect durability. They are, however, linked. An attempted improvement in the one might indirectly result in a change for better or worse in the other. Experience has shown that although we may start with the general idea of investigating durability and weather resistance the investigations turn to detailed studies of the properties of the individual materials themselves as soon as sufficient knowledge of the problems makes these studies possible. The advantage lies in the resulting greater ability to forecast behaviour under a wider range of conditions or alternatively to forecast the effect of modifications in the structure of the materials. A practical advantage of real importance lies also in the greater possibility of reducing the time needed before forecasts of behaviour can be given, as compared with the time required when an opinion is based on systematic observations on exposure sites.

It cannot yet be said that research into these detailed fundamental properties has progressed very far, although considerable advances have been made in some directions. The ultimate reliance on trial exposures even in advanced cases indicates a lack of confidence at the present time in the deductions drawn from fundamental studies; this lack of confidence can only arise from realisation of insufficiency of knowledge bearing on the problems.

With the background knowledge from the study of the materials which has already been gained, it is fair to consider two questions. These are dealt with in turn below:—

(a) To what extent has it been possible to systematize the examination of materials for durability and weather resistance? This question can be set in simpler form by means of a direct example. Given a new material of unknown composition, is it possible to operate an accepted schedule of tests that will give results leading to a reliable forecast of probable durability? The short and obvious answer is that there is no such schedule. Nevertheless, it is not necessary to investigate every new material afresh. Previous experience does help to shorten the amount of investigation necessary. It is suggested that sooner or later it will be a useful step to compare the lines of importance which have been found for the different materials and to attempt to bring together common factors or common methods of attack, for all climates. At the present time, the kind of information obtained in one country is seldom easily applied in another. For example, the kind of information secured for a material to be used in the United Kingdom often shows gaps if applied to use in the tropics. Yet with a slight extension of investigation it ought to be easily possible to produce data

and conclusions which could be more widely applied. This point extends beyond the discussion of durability to many other functional requirements. Either for helping international trade in building materials or for a more rapid interchange of new techniques of building, some agreed means of providing the right kind of technical data would be an obvious benefit. In its widest sense this question is not simply one of international standardization although it is true that the latter would form some part of it. The author has not attempted in the present paper to formulate any definite suggestions; a number of the papers before the division are relevant to it and to anticipate them in this way would lead to repetition.

(b) the second question is whether the emphasis on durability and rain resistance as the most important items in investigating building materials should persist at the present time or whether the concentration of effort could most profitably be turned elsewhere.

It will not be disputed that the two problems are important, at least in Great Britain. When damp penetration occurs in a building it is always a source of trouble and expense to the occupants or owners, and if an order of priority had to be given on functional requirements it is probable that the provision of a dry interior would be placed next in importance after stability. On the other hand, the outlook on the need for durability has undoubtedly changed with changing social and economic circumstances. In Great Britain the emphasis is much less on extreme durability, because fewer buildings of the monumental type are being built. On the other hand there is still a demand for adequate durability over the periods for which a building will probably be useful. The investigation of durability produces a good deal of data on the nature of maintenance requirements. The fact that considerable or frequent maintenance costs may be forecast is a deterrent to using less durable materials. But more exact knowledge on probable maintenance requirements does produce a condition in which the architect or builder can balance the possibility of using perhaps a more expensive starting material against that of using a less expensive and less durable material if it is known that the latter can be maintained by periodic but inexpensive treatment.

It is the author's view that, even in the changing social and economic circumstances of today, the investigation of durability remains of importance, but that other aspects have also become important at the present time.

THE EXTENSION OF OBJECTIVES

The trend of research on building materials must obviously take cognizance of the trends of research and of current problems in allied fields, particularly in other branches of building research and in building in general. In the latter, prominent items, not necessarily in order of importance, include the following:—

(a) the identification of functional requirements of buildings.



BERLEI FACTORY, SLOUGH



For 40 years Doloment Jointless Flooring has been considered an essential in factories where delicate materials are handled or valuable precision machinery is operated. Because it will not produce dust under the heaviest traffic Doloment is ideal for these purposes, also it is warm and resilient with excellent thermal insulating properties. It makes for cleaner, healthier buildings, less noise and vibration, and reduced maintenance costs.

Write for full details to :

JACONELLO LTD.
AND
BRITISH DOLOMENT CO. (1938) LTD.

147 Victoria Street, London, S.W.1 Tel. Vic 3043 (6 Lines)

*The Original
Jointless Flooring*

**SOME TYPES OF
FACTORIES IN WHICH
DOLOMENT FLOORING
IS INSTALLED**

British Railways. Ilford.
Fitting & Machine Shops.

L.M. Van Moppes & Sons Ltd.
Basingstoke
Diamond Cutting Tools

Elizabeth Arden Ltd. Acton.
Soap & Perfumery Mnfrs.

G.E.C. Birmingham, Coventry,
Wembley.
Machine Shops.

London Knitwear Co. Folkestone.
Knitwear Mnfrs.

Hudson Bay Company. London.
Furriers.

Smith & Nephew. Hull.
Elastoplast Mnfrs.

Berlei. Slough.
Corset Mnfrs.

Vitamins Ltd. Hammersmith, London.
Patent Foods.

SPECIFY DOLOMENT THE JOINTLESS DUSTLESS FLOORING

- (b) The current problem of reduction in cost of building.
- (c) The current problem of increasing speed of erection.
- (d) The current problem of the use of substitutes.
- (e) The most effective use of national resources of building materials.

IDENTIFICATION OF FUNCTIONAL REQUIREMENTS

The original direction of research towards the functional requirements of stability, durability and weather resistance has already been noted. Freedom from excessive fire hazards might have been added to these, since conscious steps to minimize the risk of conflagrations in towns have been taken at least since the Great Fire of London in the 17th century. Although the nature of the materials themselves have an obvious bearing on fire behaviour, it is the behaviour of the structure as a whole, or at least the behaviour of major elements (party walls, floors, roofs and so on) which is of most importance. In this sense, although it falls outside the main scope of building material research, it has nevertheless to be borne in mind as a limiting feature in the development of materials which at times has produced special materials research features on its own account. Examples include studies on the improvement of the fire behaviour of concrete through the use of aggregates differing from the normal and the development of lightweight protections to steel of the gypsum-vermiculite type, while a considerable field of research developed during the war on modifications to materials or of surface finishes to them designed to minimize surface spread of flame. All of these are included in what may properly be designated as research on materials although they are only a preliminary to research on the functional requirements of the structure.

In the same way, the more quantitative treatments of other functional requirements of buildings, such as thermal and sound insulation, either weight the choice of worthwhile developments in research or lead to special directions of research aimed at producing properties which will ease the fulfilling of one or other requirement. The advantage of a way of research which investigates each type of material separately is that it can, on the whole, readily absorb these additional demands by some expansion of the existing studies. Advances in other fields of building research always affect building materials usage in varying degree; the direct practical application of these advances often makes new demands affecting the suitability of materials. Ideally it is desirable that progress on the materials side should always be a step in advance so that it is possible to meet the demands when they arise. Clearly the only way this can be done is to extend research on any given material to the limit of knowledge of its structure and properties even in directions which cannot be seen to be immediately useful. Examples of the value of this are not lacking, particularly in the field of the chemistry of cements, but there are limits to the available resources both of investigators and money, and such forms of research have to compete with the demands for data to meet urgent day-to-day problems. It is fortunate that the need to preserve a proportion of longer range fundamental research seems to be widely accepted in the field of building research in general and building materials in particular. There is scope for much more as circumstances permit, for only in some isolated directions are the boundaries of the more fundamental investigations much in advance either of practice or of the more directly applied research.

THE PROBLEM OF REDUCTION IN COSTS

The high cost of building is probably the most serious problem facing the building

industry today. The relative proportion of cost due to materials and to labour differs in different countries, but the cost of materials is never negligible and is often the greater part. The problem is so urgent and widespread that it might be expected that a high concentration of effort of research would have reduction in costs as its objective. At first sight, it does not appear that there is this concentration of effort, because the modes of attack are not always obviously related to this objective. The problem has, in fact, considerable complications and it is worth while to examine the position in more detail.

In the first place, the major building materials are mostly either natural products or products removed from the natural by only one or two stages of simple processing and are already very cheap if compared either by unit volume or unit weight with materials used in other industries. The expense lies less in the cost per unit than in the number of units required for even the smallest building. The general direction of research on materials has been towards improved quality of performance, because of a user-need for something better than existed. But the scope for improvement without introducing additions to the manufacturing processes is limited in many cases, so that the search for improvement in quality would often tend to increase rather than to decrease the first cost of materials. This subject is considered in a separate section below.

In the second place, there is the possibility of reducing the amount of material required for any given building. This can be considered both in terms of planning of occupancy space and also by refinements in structural design. The latter is closely linked with performance of materials. For example, much possible refinement is lost if the variability of a product is high. On the other hand, to improve quality by a reduction in variability may increase the cost of the materials. The balance between these two is an important problem which is recognized in papers given later on some specific examples.

Apart from these, the influence of the cost question on building materials research is shown by a shift of concentration on to those materials which are least expensive, often in the direction of trying to improve them sufficiently but at minimum cost, so that they become capable of being used in positions requiring fairly high quality. For example, it may be possible to raise the quality of a material, previously used only in interiors, so that it can be used on external elements, as has been done in the United Kingdom with clinker blocks. Another direction is in investigating the possibilities of inexpensive by-products or waste products from other industries. Furnace clinker as used in clinker blocks is one example, blast-furnace slag is a second; both have been used successfully. Other examples are pulverized fuel ash, sawdust, slate waste, and so on.

It is necessary also to consider how a reduction in the standard of quality needed to meet accepted functional requirements would achieve the desired results. However, it is not difficult to show that the results might be much below what was desired. It has already been noted that economies in structural design may require a higher quality, at least in degree of variability. A reduction in quality would have the converse effect from the structural point of view and would probably mean that more material would be required. A lower standard of durability might mean no more than higher maintenance costs, but it might mean a performance capable of being maintained only with the greatest difficulty. A lowering in quality in the sense of reduced thermal insulation would tend to defeat its own ends in affecting fuel economy adversely, and so on. The

case for maintaining a standard of good quality in building materials and in the combination of materials making a structure a strong one. If the building industry had strong technical staffing, it would be possible to suggest one or two ways in which a reduction in standards could be attempted, using additional technical devices to avoid the extra elements of risk incurred, but a general lowering would seem inadvisable.

INCREASED SPEED OF ERECTION

The speeding up of building operations after the 1914-18 war produced problems and troubles in the finished building; the need to solve these was one of the factors in the United Kingdom which led to the founding of a Building Research Station. The speed-up in this case was attempted while very largely retaining the use of traditional materials.

When the attempt to reduce the number of man-hours for a given building is made by means of non-traditional methods, as at the present time, problems are presented at once in the building material field. The relative importance of the different materials is altered and, within any one material type, the relative importance of different properties is also altered. For example, a move towards "dry" construction brings into prominence the extended use of sheet materials and of jointing mastics, and emphasizes the need for certain properties in these which they may not have had before. Experience in this country does also suggest that it increases the need for close linking of all branches of building research, especially in those cases where the absence of traditional experience means that the ultimate performance has to be deduced solely from a scientific or technical analysis. An example may illustrate this point. In the United Kingdom, traditional building has not made much use of impermeable outer claddings, except to a certain degree on roofs. There is also a discernible difference between the broad design of roofs and walls. Roofs make use of a series of materials each performing one function—an outer layer as the weather-resisting skin, a second insulating layer, and a third for structural support. The wall materials, on the other hand, frequently have multiple functions—weather resisting, structural and insulating. If we now consider a non-traditional construction in which the outer layer is impermeable in both walls and roof, e.g., metal sheeting, and in which walls and roofs both contain single-purpose materials, we have to try to foresee at what possible points problems may occur. Some will be obvious; the durability of the metal and the greater difficulty of avoiding rain penetration at joints are examples. Others are less obvious purely from the building material point of view. They do not become obvious until the whole structure is considered, together with factors such as the heating and ventilation, the appliances to be used by the occupants, and so on. When this is done, a problem such as that of avoidance of condensation in the interior may become considerable and only soluble by joint investigation.

A great deal of time has had to be spent during and since the war on the development of materials or on the transfer or adaptation of materials to serve functions caused by the absence or scarcity of the accepted materials. The accepted materials may have become scarce because of the inability to match an increased volume of building by an increased production, but frequently the cause of scarcity has been outside the normal field of building altogether. Especially in the last case there is little opportunity to foresee the scarcity and to carry out the necessary research in advance. The result is that when investigation comes to be made, there is an unavoidable waste, since the



CRAFTSMANSHIP & SERVICE ...



When placing your contracts within the Building Industry, you will wish to receive that precious blend of Craftsmanship, Service and Efficiency which creates lasting value.

We base our ideas on the craftsmanship of the past with the efficiency of the present, and can offer you the benefit of our experience.

We really ENJOY giving advice of such a service as ours and it has often been our pleasure to be entrusted with most important commissions.

WALTER LILLY

AND COMPANY LIMITED


DECORATORS *Building Contractors* ENGINEERS

WESTMINSTER

ST. ANN'S STREET, WESTMINSTER, S.W.1.

and at Streatham

Telephone: ABBEY 4661 (10 lines)




Puzzled?

If ever you find yourself in difficulties when working with laminated plastics, this may interest you. We are continually developing better ways of fixing WARERITE Materials, and when it comes to solving problems, we haven't been beaten yet! So when you strike any tricky snags put our technical staff on their mettle—they're only too glad to help. Many useful hints are given in recent Warerite booklets— if you would like copies of them or advice don't hesitate to write or 'phone—

WARERITE

REGD. TRADE MARK

LAMINATED PLASTICS



MADE BY WARERITE LIMITED (UNIT OF BAKELITE LTD) · WARE · HERTS · TELEPHONE WARE 502

Manufacturers of Decorative Laminates for over 20 years

urgency
Further,
scarcity
be reliev
the adop
than to t
of perm
accepted
the cons
develop
those of
ample o
wood bo
The p
linked w
ated fro
have of
look to
in ways
identific
have lai
cedure
become
have ad
ing.

THE EFF

Among
research
the int
where t
crafts.
occurre
for tran
product
is, how
cost m
do dep
tion of
material
aspect
emerg
need m
quality
exempl
able p
sands.
a few
insisten
all circ
of sup
adequa
sources
may b
material
which
used n
research
design.
modifi
culties

RESEAR

All
can be
manuf
identifi
finishe
manuf
the pr
which
too fa

The
a dec
mater
is dire
papers
in thi
with
plant
exper
accep
ductio
insuff
reser
work
buildi
dom
the e
build
perier

urgency for quick results is increased. Further, the lack of knowledge whether the scarcity will be prolonged or whether it may be relieved at short notice tends to lead to the adoption of temporary expedients rather than to the discovery of alternative materials of permanent value. Where it has been accepted that a shortage is likely to continue, the converse has happened; the incentive to develop alternative materials has produced those of permanent value. A notable example of this is in the alternatives to soft-wood boards found for floor surfacing.

The problem of alternatives is quite closely linked with the problems which have emanated from non-traditional building. Solutions have often involved changes in design outlook to make use of other known materials in ways different from normal; problems of identification of desirable properties, which have lain dormant while some accepted procedure was giving trouble-free results, have become live and the solutions in either case have advanced the general science of building.

THE EFFECTIVE USE OF NATIONAL RESOURCES

Amongst the early problems of building research were those which were caused by the introduction of materials into regions where they were unfamiliar to the traditional crafts. It is usually considered that this occurred partly through increasing facilities for transport and the greater use of mass-production methods of manufacture. There is, however, a limit to this movement of low-cost materials. Most industrial countries do depend to a large extent on the production of most of their own major building materials. From this point of view, an aspect affecting research on materials may emerge. The general aim of high quality may need modification to an aim of adequate quality. Again illustrating this with an example, it is possible to specify the desirable properties of building and concreting sands. The highest quality may be limited to a few natural deposits. If there is too much insistence on the highest quality product in all circumstances, it may lead to exhaustion of supplies. A lower grade would often be adequate and more economical of the resources available. On the other hand, there may be no sources of the most desirable material, but only supplies of material which would give less than perfect results if used normally, and this calls for a form of research to show in what way (whether by design, or by altered craft processes, or by modified manufacturing process) these difficulties can be overcome.

RESEARCH ON MANUFACTURE OF MATERIALS

All the types of research described above can be applied for the benefit of materials manufacture in the sense that they tend to identify the properties to be aimed at in the finished product. They can also be used in manufacturing research designed to cheapen the product by providing check points at which it becomes risky to alter properties too far.

The benefits which might be realized by a decrease in the variability of building materials has already been mentioned and is directly or indirectly the subject of other papers. While the basis on which progress in this direction can be realized must start with laboratory work, it also requires pilot plant work as well. Such work can be very expensive on its own account, and if we accept that its main justification must be reduction in costs of the finished building, it is insufficient merely to carry it out as technical research; cost analysis aimed at relating the work continuously to the cost of finished building is desirable. In the United Kingdom there has been a number of examples of the extension of this form of research on building materials within recent years. Experience at the Building Research Station

has shown that, as might be expected, there is a difference in the nature of the results aimed at, depending on the background science of the investigator in charge. Building material research has to some extent become the province of the chemist or the practitioner of related sciences. In the case of pilot plant work, the natural trend is then to examine the process in comparison with the usually more highly controlled laboratory process and to check either that the stages of the process produce identical reaction products, or, if these differ, to show what amendment of conditions are needed. The points at which quality control tests can be made and the nature of the tests may also be determined. The engineer's approach may well differ from this, with greater emphasis on production efficiency. For full value from the work a combination of the two is required. Although this is a very obvious comment, so well recognized in the chemical industry as might appear to make it superfluous, many of the processes in materials manufacture are not within the usual scope of the chemical engineer and hitherto it is only in isolated cases that methods of attack have been applied to them similar to those the chemist and chemical engineer would normally apply to products in the chemical industry. In the author's view, an extension of this sort is likely to prove of more immediate benefit than in almost any other field of materials research.

THE INTERPRETATION OF RESEARCH RESULTS

Since the war, a great deal more attention has been paid to what may perhaps best be described as the technique or techniques of transferring research findings into active practical application. While this applies to all aspects of building research, there are one or two features which apply more particularly to materials research. They have some influence on the research itself, particularly on the point to which the research needs to be carried.

The problem as a whole occurs to a large extent because of the traditional background of the building industry, which did not start on the basis of some fundamental discovery in pure science and is therefore not organized around scientific control. The applied arts have a firm interest and practice in producing its products (*i.e.*, buildings) and the application of science to it therefore needs a different approach from that adopted in many recently developed industries.

The methods and actual subjects of research which have developed on building materials have moved away from the original practical problems which led to their initiation. The tendency is towards an attempt, where possible, to reduce the findings to general principles. It is, however, important to keep in mind that there is no particular advantage in this approach unless the industry is organized in such a way that it can adapt and apply the general principles to practical problems arising in the construction of individual buildings, in which there are always many additional complicating factors. To be completely effective there would need to be a technical side to the industry itself fully complementary to the research side. In so far as this has not been completely achieved, the results of research may not be as fully effective as they might be. Pending its achievement, a partial solution may be to extend the investigation to cover a sufficient number of direct practical applications to serve as direct examples of the kind of building procedure and design needed to apply the particular principles which have been uncovered.

A more rapid outlet for a good deal of building materials research, and one in which the materials side is more favourably placed than other fields of building research, occurs when the results need not be applied directly

during actual construction. For example, when an improvement in quality can be taken into the provision of a standard specification, the actual application of the research which led to this improvement becomes the concern of the manufacturer rather than the builder. There is no disturbance of building procedure other than that of ensuring the use of products made to the standard. However, the effort to apply research in terms of quality tests in a standard does affect the amount and kind of work to be done. One of the difficulties about such control tests is the need to make them sufficiently simple to permit them to be used freely without delaying production or making the cost of testing prohibitive.

It is a very far-reaching demand to make, that properties, often of a fundamental kind, should be assessable by very simple field tests. Nevertheless, in the author's view, it is one of the outstanding problems to be faced in materials research.

Other applications of materials research may not be of a type affecting a standard specification, but may still be related to manufacture of the material rather than its use. The building materials manufacture part of the building industry has necessarily a rather greater technical basis, at least in many parts of it, than the design and construction side and the channel for application of research is to that extent easier and more rapid. It is never easy to give figures to support a review of the extent to which research results have been applied, but a general impression from the Building Research Station's experience is that when an advance has been accepted in manufacture of a particular material, application in the industry itself is accelerated and kept at an effective level because it has at its disposal the manufacturers' organizations for technical sales services and so on.

GENERAL CONCLUSIONS

In this paper it has only been possible to consider general trends, and much of very great interest has had to be omitted. Within the limits of the subject matter discussed, the following appear to the author to be the more important conclusions:—

Within the existing pattern of building material research as it has existed now for many years, room must be made for wider studies than those which relate only to durability and weather resistance. In doing so, the importance of comprehensive studies, including more long range and fundamental research, on the individual building materials is increased. Research on building materials has never been completely independent of the problems of the building industry as a whole, but at the present time there are some problems of building which, so far as the materials side is concerned, can only be attacked by a much closer integration than has existed before. Examples of these problems include the need to reduce costs of, and man-hours in, construction, and the developments in non-traditional building. It means, in effect, that there have to exist, side by side, subject research and project research, the latter being directed at problems of buildings as a whole.

In addition, on the exclusively materials side, increased attention to research of the pilot plant type and production type is needed. Many processes have been virtually untouched so far by this kind of research.

The need for development of sufficiently reliable but very simple field tests is an urgent matter. The spread of the use of science in building requires them, while they will also be needed to help to keep costs down in modification of processes designed to reduce variability. In the last case, the cost of testing can add appreciably to the cost of the finished product.

TUCKER'S 'Armourply'

**DOORS • COUNTERS
AND TABLE TOPS
CUBICLE UNITS
REFRIGERATORS**

*Metal
Faced
Plywood*

**INSULATING PANELS
ESCALATOR PANELS
ROOF PANELS
VEHICLE BODIES**

Combines light weight with strength in a wide range of decorative and utility surfaces.

Manufactured by

WILLIAM MALLINSON & SONS LTD

180 - 150 HACKNEY ROAD, LONDON, E.2

• Telephone : SHOREDITCH 8888 - 8811

• Telegrams : ALMONER, LONDON



THIRST-QUENCHERS IN CHIEF TO THE BRITISH PUBLIC

"Stotts of Oldham" are the actual designers and makers of over 100 different types and sizes of water boilers, heated by all fuels; manufactured throughout in Oldham. There is a model just right for your needs.

Send now for Catalogue No. A.A.6



One of the many 'Stott' Installations at the South Bank Exhibition.

This feature covers both the production and marketing of new materials and designs of equipment as well as the general trend of developments within the Building Industry.

THE INDUSTRY

By Brian Grant


DATA ON SOLID FUEL

John Pinckheard's *Architectural Design Data for Solid Fuel*, published by the Coal Utilisation Joint Council, is an exceptionally thorough treatise on methods of delivery, storage and handling of solid fuel. The majority of the information cannot, of course, be new, but it is very useful to have it all in one volume. It is not possible to review the publication in full, but there are one or two minor points which perhaps deserve mention; many readers may not know of them. There is, for example, the question of the deterioration of coal whilst in storage: the loss in calorific value due to oxidation seldom exceeds 1 per cent. (less for anthracite), a much lower figure than I had imagined, and less than normal variations in combustion efficiency. General physical deterioration—increased moisture content and frost disintegration—may account for a further 1 per cent., but this will apply mainly to fuel stored in the open. Spontaneous combustion is liable to occur only in large coal stacks of 200 tons or more.

Delivery methods, too, seem to be improving a little, notably in the growing use of tipper trucks which rise with a scissors action. These are capable of discharging through a vertical trap in the wall instead of into a pavement trap. At least one firm has lorries with built-in conveyor belts which can discharge across a pavement or into a trap even higher than can be reached with the type of lorry described above. Both these developments seem likely to simplify the planning of access areas for delivery.

The book is devoted mainly to the larger types of building and covers all the fuel problems from delivery to ash removal. Get this book and keep it for reference. (*The Coal Utilisation Joint Council, 3 Upper Belgrave Street, London, S.W.1.*)

One of the new Creda Unity ranges (the smaller model) designed for restaurants and canteens.



the access tunnels of stations is a far from easy problem, largely because of the low ceilings, but the photograph below shows that the result can be quite cheerful. This shows the work which Falks have done at Waterloo, where a good deal of trouble has been taken because it is, after all, the main underground entrance. Fluorescent fittings on battens have been used, and, although they are installed with the lamps exposed to view, the brightness contrast is small because all the ceilings are very light. (*Falk, Stadelmann & Co. Ltd., 89-93, Farringdon Road, London, E.C.1.*)

ELECTRIC COOKERS

The photograph above shows one of the Creda Unity island and wall type ranges which can be built up into cooking units of any size. The individual oven and hot plate units are made in two different types, the larger having two 16 in. by 12 in. hotplates each with a loading of 4 kw., two hotplates 6 in. by 8 in., at 1½ kw. each, and an oven of 24 in. cube, with a loading of 6.4 kw. In the smaller model, one of the 16 in. by 12 in. plates is omitted and the oven is smaller—18 in. by 18 in. by 24 in., with a loading of 4.4 kw. Dimensions are 3 ft. 5½ in. wide by 2 ft. 4½ in. deep for the larger model, while in the smaller model, the width is reduced to 2 ft. 11½ in. The height of both types is the same—2 ft. 10 in. to the top of the hotplate.


These cookers are for large-scale restaurant

and canteen work and are designed so that they may be used in long rows against a wall or back to back forming an island in a large kitchen. Standard finish is in grey mottle, though other colours can be supplied at extra cost. Construction seems sturdy enough to stand up to the inevitable abuse and all electrical components are accessible from the front so that replacements can easily be carried out.

Although larger cookers are built up of separate units, the usual trouble of grease and liquids seeping down between the ovens is avoided by using a simple channel so that the hotplate becomes, in effect, continuous. Ovens have four standard shelf positions and hotplates have 3-heat switches, though Simmerstat switches are available as an alternative. (*Simplex Electric Co. Ltd., Broadwell, Oldbury, Birmingham.*)

UNIT BUILDINGS

The constructional perspective below shows the method by which the "Stafford" prefabricated building is erected. The system, which was designed by P. L. Bruning, consists of only five different components, and can be used for single storey buildings of all kinds. It should be quick to erect, even when using comparatively unskilled labour. The various component parts are recoverable if the completed building should have to be modified. (*Stafford Concrete Buildings, Ltd., Rickerscote Road, Stafford.*)



LIGHTING IN THE UNDERGROUND

Even the least observant will have noticed that a lot of Underground stations have been brightened up for the Festival, mostly with tiles and paint and fluorescent lighting. To light the rather gloomy flights of stairs and

Above, Falks lighting in Waterloo Station. Right, diagrammatic perspective of the "Stafford" building system.

Readers requiring up-to-date information on building products and services may complete and post this form to *The Architects' Journal*, 9, 11 and 13, Queen Anne's Gate, S.W.1.

ENQUIRY FORM

I am interested in the following advertisements appearing in this issue of "*The Architects' Journal*." (BLOCK LETTERS, and list in alphabetical order of manufacturers names please).

Please ask manufacturers to send further particulars to:—

NAME

PROFESSION or TRADE

ADDRESS

A.J. 20.9.51

Buildings Illustrated

House in North End, Hampstead Heath, London, N.W.3. (Pages 348-350.) Architect: Architects' Co-operative Partnership. General Contractors: Yeomans & Partners, Limited. Sub-Contractors: Structural steel, Sommerfeld Limited; central heating, Weatherfoil Heating Systems; boiler, Janitor Boilers Limited; door and window furniture, James Gibbons Limited; casements, Boulton & Paul Limited.

Announcements

Mr. R. W. Taylor, A.M.I.E.E., will take up an appointment on October 1 with Crompton Parkinson Ltd., as Product Sales Manager of the Nelson stud welding service. Mr. Taylor recently resigned his position as Sales Manager to Cyc-Arc Ltd. Before joining that company he was Sales Manager and Director of the Power Equipment Co. Ltd., Hendon, from 1945-48. Mr. Taylor will take over from Mr. R. V. Powditch, O.B.E., T.D., A.M.I.E.E., A.I.M.E.C.H.E., who becomes Product Sales Manager, Crompton Parkinson FHP motors, on October 1.

Mr. Grahame Martin Turner, a Director of Thomas De La Rue & Co. Ltd., left London recently for a 30,000-mile tour of New Zealand and Australia. He will study the scope for the application in Australasia of Formica, his company's laminated plastic, particularly for use in the building industry, both domestically and industrially.

On Wednesday last, Mr. George Strauss, M.P., Minister of Supply, opened a large new alarm clock factory for Smiths English Clocks Ltd. at Farm Lane, Gowkthrappe, near Wishaw, Lanarkshire. The factory was

planned after a team of experts had visited and made a careful study of many of the world's outstanding flow production factories in the USA, the United Kingdom and Europe. The colour scheme of the factory and its equipment has been planned with the help of the British Colour Council in order to give the maximum light, pleasure and relief from eyestrain.

Messrs. Walter Lilly & Co. Ltd. have appointed their contracts manager, Mr. Henry J. Scholey, to the board of directors of the company.

Mr. Granville F. Siegerts, of 1, Electric Parade, Seven Kings Road, Ilford, Essex, has taken into partnership Mr. Philip Lebor, DIP. ARCH., A.R.I.B.A. The style of the firm will in future be known as Siegerts & Lebor. Trade data and catalogues will be welcomed.

We regret to announce the death at his home "Craigielea," The Avenue, Hale, Cheshire, of Mr. C. Macfarlane Cullen, Chairman and Joint Managing Director of D. Anderson & Son Ltd., Stretford, Manchester, Belfast and London. Mr. Cullen was a Director of the British Plaster Board Ltd.

The 20th Annual Conference of the Institute of Housing Inc. takes place at the Spa Grand Hall, Scarborough, Yorkshire, today and tomorrow. It will be attended by between 1,000 and 1,100 officers and members of housing committees from local authorities in all parts of Britain. The theme of the Conference is "The Economics of Housing." There is to be an opening address by Mr. G. S. Lindgren, MP, Parliamentary Secretary to the MOLGP. The remainder of the Conference will be devoted to the presentation and discussion of three papers: (1) "Productivity in the Building Industry," by Sir Thomas Bennett; (2) "The Economics of Maintenance," by H. C. Hampton," and (3) "Making Ends Meet," by Hugh R. Ralph.



Borough of Camberwell Housing.

Architects: Messrs. John Grey & Partners, F.R.I.B.A., A.A.Dip.

Finlock Gutters eliminate painting and maintenance to the eaves.

FINLOCK GUTTERS LTD., 20, ST. JOHN'S ROAD, TUNBRIDGE WELLS, KENT

WORKS AT: LEEDS, YORKSHIRE.
EDINBURGH, SCOTLAND.
CWMBRAN, SOUTH WALES.

BARNSTAPLE, DEVONSHIRE.
SOUTHAM, WARWICKSHIRE.
TUNBRIDGE WELLS, KENT.

Telephone: Tunbridge Wells 20396/7

FINLOCK

Regd. Trade Mark

SAVE £30 PER PAIR OF HOUSES


Omissions

9 yds. 11 in. Brickwork	160 ft. super of Roofing
160 ft. of 2 in. by 3 in. Fascia	80 ft. of Tilt Fillet
80 ft. of C.I. Gutter	80 ft. of Soffit Beam Filling
2 Outlets	4 Stopped Ends
2 Offsets	2 Lead Slates
Painting Gutters—Fascia—Soffit	
Reduction in Down Pipes and Drainage	

Additions

FINLOCK PRE-CAST EAVES
COMPLETE WITH ALL FITTINGS
FIXED IN ONE DAY.

Over 100 County, City and Local Authorities are now using Finlock Gutters for their 1951 Programmes for every conceivable type of building: Police Housing, Schools, Libraries, Municipal Housing. Acclaimed by Architects and the Trade as the finest advance in building construction. Our statements with regard to saving in cost are being confirmed every day by Quantity Surveyors. The actual amount varies and is dependent on the existing specification. Finlock greatly improves the appearance of a building and being of fine waterproof concrete, reduces maintenance costs appreciably. Roof maintenance is greatly facilitated by the use of Finlock Gutters and painting is reduced to doors and windows.



**ADVANCE CONTROL
OF TEMPERATURE
ON H.W.
HEATING SYSTEMS**

The Sarco E.T.O. Controller anticipates the effect indoors of any external temperature change.

It is a self-contained fully-automatic control for accelerated hot-water heating systems, providing equable indoor temperatures under conditions of changing outdoor temperatures.

It controls heat supply at the minimum required to balance heat losses whatever the outside temperature conditions, giving maximum fuel economy.

It can be designed to suit heat emission curves appropriate to the type of heating surface installed.

It can, after installation, be corrected to allow for any variation between design and site conditions.

A boiler is subjected to less strain, and corrosion troubles avoided, because the boiler can be operated at a constant water temperature.

The E.T.O. is non-electric, entirely self-operating and direct-acting. It has packless glands which eliminate the trouble so commonly experienced with ordinary glands.

It is reasonable in cost; easy to install; easy on maintenance.

For more information, please send the request slip to SARCO THERMOSTATS LTD., CHELTENHAM, GLOS.

SARCO E.T.O. CONTROLLER

REQUEST SLIP FOR ADDITIONAL INFORMATION


NAME:

ADDRESS:



AR2853

GENTS' PRODUCTS IN WHITEHALL...



(Ministry of Works photograph - Crown Copyright reserved)

The New Government Offices, Whitehall Gardens

In any large establishment of this kind three services are essential to ensure efficiency, safety and security. They are:

1. Correct time in all departments.
2. Facilities for giving instant warning in case of fire.
3. Automatic supervision of nightwatchmen.

Throughout the new Government Offices in Whitehall Gardens these duties will be entrusted to equipment made by

**GENTS'
OF LEICESTER**

**CLOCKS · FIRE ALARMS
WATCHMAN'S RECORDERS**

For descriptive literature write to:

GENT & CO. LTD · FARADAY WORKS · LEICESTER

London: 47 Victoria St., S.W.1

Newcastle 1: Tangent House, Leazes Park Road

Other products include: STAFF LOCATORS, LUMINOUS CALL SYSTEMS, TELEPHONES, PROCESS TIMERS, MINE SIGNALLING EQUIPMENT, LIQUID LEVEL CONTROL EQUIPMENT, TOWER CLOCKS, BELLS AND INDICATORS, BURGLAR ALARMS, ETC.

SITE INVESTIGATION

*The essential preliminary
to the economical design
of foundations
for building construction*

In addition to our Test Boring facilities, we are able to offer the services of our Soil Mechanics Laboratory, which is fully equipped to carry out a complete series of laboratory tests with modern apparatus. On completion of the tests, comprehensive reports are provided showing the properties of the soil samples, the results of the various tests, and their practical application to the foundation problem under consideration. The work, both in the field and in the laboratory, is supervised by qualified engineers who have made a special study of the subject.




Test boring operations in progress.



A Section of our Soil Mechanics Laboratory.

LE GRAND SUTCLIFF & GELL LTD.

SOUTHALL • LONDON • Telephones: Southall 2211 (7 lines) • Telegrams: "Le-grand" Southall



★ *The joint
that outlasts the system!*

Securex joints give long, hard wear - in fact, they'll outlast the system. Solder and packing have been eliminated - in their place is the precision Securex joint that is made of copper and will neither fur nor rust. The principle of Securex construction is, like most ingenious devices, simple. Two countersunk compression surfaces, compress the expanded pipe ends against an inner ring of conical section by rotation of the outer nut. Increase of internal pressure tightens the joint.

"The joint that outlasts the system" is no idle boast. If you want to save time, trouble and expense, use Securex for all your joint problems. We will be pleased to supply full particulars.

SOLE MANUFACTURERS

JAMES H. LAMONT & CO. LTD.

Engineers Brassfounders

GYLEMUIR WORKS, CORSTORPHINE, EDINBURGH 12, SCOTLAND

Telephone: Corstorphine 66641-2 Telegrams: "Solderless, Edinburgh."

LONDON OFFICE: NORFOLK HOUSE, LAURENCE POUNTNEY HILL, E.C.4

Telephone: Maida House 5700 Telegrams: "Yuteka Cannon, London"

SECUREX
SOLDERLESS COMPRESSION
JOINTS

BUILD WITH STRAMIT


... and you build with Speed



Stramit roof deck laid in aluminium alloy purlins: weatherproofed with copper. Nottage Primary School, Porthcawl, Glam.
Architects: F. R. Bates & Son, Newport, Mon. Contractors: Gee, Walker & Slater Ltd., Swansea. Copper Roofing: Hugh Twaddle & Son Ltd., Glasgow, C.I. Purlins, Trusses: Structural & Mechanical Engineers Ltd., Slough, Bucks.

**WHETHER YOU BUILD
WITH ALUMINIUM,
STEEL OR TIMBER,
STRAMIT PROVIDES THE
SPEEDIEST, CHEAPEST
ROOF DECK**

*Full details and services of Technical
Representatives available on request*



**STRAMIT
BOARDS LIMITED**


DEPT. A, PACKET BOAT DOCK, COWLEY
PEACHEY, NEAR UXBRIDGE, MIDDLESEX
Tel.: West Drayton 3021

★ We offer immediate delivery of STRAMIT and Aluminium accessories



FOR

**SCHOOLS
FACTORIES
OFFICES
CINEMAS
HALLS**



Sound Absorption...

The problem of sound absorption is engaging the attention of Architects and Designers throughout the World.

Many have found Unitone Acoustiles the perfect medium for acoustical correction. These ivory coated tiles, which need no further decoration are easily fixed to existing surfaces at low cost and little inconvenience.

Send for full details, samples and prices to:



SCHARIN PRODUCTS LIMITED

21, John Adam Street, Adelphi, London, W.C.2

Phone: TRAfalgar 3356-7

CYCLONE FANS **INSTALLED...**


IN THE ROYAL FESTIVAL HALL

The Royal Festival Hall, only permanent building on the Festival of Britain Exhibition Site is destined to become one of the foremost music centres in the world.

For such a building the silence and reliability of the ventilating and air conditioning plant is of paramount importance.

Fifty Fans of our design and manufacture have been installed in the heating, ventilating and air conditioning systems. Also 3 large Cyclone Air Washers form part of the air conditioning section of the scheme.

Cyclone Fans and Equipment have been supplied for many other permanent buildings which will play an important part in the Festival of Britain.



Acknowledgments:

The Royal Festival Hall, 1951 Festival of Britain. Main Contractors: Holland & Hannen & Cubitts, Ltd., Structural Consultants: Scott & Wilson. Designed by: Robert H. Matthews, A.R.I.B.A. Architect, London County Council and Staff. Air Conditioning by: Matthew Hall & Co. Ltd.

PHONE
SWINTON
2273 (4 lines)

MATTHEWS & YATES LTD

(Member of the Fan Manufacturers' Association, Ltd.)

SWINTON (MANCHESTER) and 20 BEDFORD ROW, LONDON, W.C.1

Also at GLASGOW - LEEDS - BIRMINGHAM - CARDIFF

PHONE
LONDON
CHANCERY
7823 (3 lines)

Furniture for Special Needs

Certain places of importance, such as offices, hotels and showrooms, need and deserve special furniture. Heal's are happy to undertake this work and a specific example is shown in this photograph. We can either work to your own plans or can design and produce complete furnishing and decoration schemes in our own studio. In either case we shall try to interpret your ideas as sympathetically as possible and we hope that our long experience of working to architects' plans may prove helpful to you.



The Board Room, Messrs. Abbot Duplicate Book Co. Ltd., Kings Langley, the well-known printers, showing the furniture recently designed and supplied by Heal's Contracts Ltd. The table is in two parts and is of elm and cherry-mahogany with bleached mahogany mouldings on the legs. The chairs are covered in blue hide and the rust Wilton carpet has a blue spot design. The curtains are of pale blue brocade with wooden pelmets.

HEAL'S CONTRACTS LTD

196 TOTTENHAM COURT ROAD, LONDON, W.1.


TELEPHONE: MUSEUM 1666

TELEGRAMS: FOURPOSTER, RATH LONDON



Overhead Efficiency without Overhead Expense!

We may justifiably claim that a Paragon Glazed Roof or Lantern Light, once installed, "stays put" for the lifetime of the building without any necessity for that periodical maintenance characteristic of less thorough installations. The reason is that all products used in our manufactures, as well as the process of manufacture itself (which is carried out entirely in our Works), are subject to the closest scrutiny as to quality and detail. May we suggest that the experience of upwards of 40 years of all the varied aspects of roof glazing are not without value?




★ We shall welcome the opportunity to tell you more in our Brochure "A" about Paragon Glazing.

PARAGON GLAZING CO. LTD.
1 VICTORIA STREET, LONDON, S.W.1
Telephone: ABBey 2348 (P.B.X.)
Telegrams: "Eclairage, Sowest," London.

PARAGON GLAZING

Above all, —easy on the eye, easy to erect, easy to maintain



These are examples from the wide range of lighting fittings in our publication S.P.7121/21. Avail yourself of the help and advice of lighting specialists and install

METROVICK
Lighting



METROPOLITAN-VICKERS ELECTRICAL CO. LTD.

ST. PAUL'S CORNER, 1-3 ST, PAUL'S CHURCHYARD, LONDON E.C.4.

Member of the A.E.I. group of companies

S/F001



PAVING FLAGS

Made strictly to British Standard Specification 368.

Granite paving is available from stock. Hydraulically pressed, clean, flat, regular in thickness and die square. Standard colours: Grey, Pink, Buff. Standard textures: Mesh and Pimple. Non-slip and guaranteed resistant to frost. Every flag is cured for a minimum period of four weeks.

Size.	No. per Ton.	Area per Ton.
3' 0" x 2' 0" x 2 1/2"	13	2 1/2" thick .. 8 1/2 yds. super
2' 6" x 2' 0" x 2 1/2"	15	
2' 0" x 2' 0" x 2 1/2"	19	
1' 6" x 2' 0" x 2 1/2"	25	
3' 0" x 2' 0" x 2"	15 1/2	2" thick .. 10 yds. super
2' 6" x 2' 0" x 2"	18 1/2	
2' 0" x 2' 0" x 2"	23	
1' 6" x 2' 0" x 2"	31	
2' 0" x 2' 0" x 1 1/2"	25	1 1/2" thick .. 13 1/2 yds. super
1' 6" x 2' 0" x 1 1/2"	31	
1' 6" x 2' 0" x 1"	41	


Gravel or Slag Aggregate Flags are also made when required. Special shapes and sizes cast to order.

TARMAC LIMITED, VINCULUM DEPT.

ETTINGSALL, WOLVERHAMPTON

Telephone: BILSTON 41101/8 (8 lines).

Hydraulic presses at Willenhall, S. Staffs., Kidsgrove, N. Staffs., Iwer, Bucks. and Littlehampton, Sussex.
London Office: 50, Park Street, W.1. Phone: GROsvenor 1422/5 (4 lines).





THE beauty and adaptability of McKechnie extruded sections is exemplified in the architectural metal work produced for the Mann George building in Cape Town. Because of their minute closeness to size and fine finish, McKechnie extrusions help manufacturers to reduce machining time, save materials, tools and labour, and increase output.

If you have a production or machining problem, write to McKechnie Brothers Limited, 14 Berkeley Street, London, W.1.

McKECHNIE metal technique

McKECHNIE BROTHERS LIMITED

METAL WORKS: ROTTON PARK STREET, BIRMINGHAM, 16.
Branch Offices: London, Leeds, Manchester, Newcastle-on-Tyne.

Solder Works: Stratford, London, E.15.

Copper Sulphate and Lithopone Works: Widnes, Lancs.

Enquiries for Lithopone and Solder to: 14, Berkeley Street, London, W.1.
South African Works: McKechnie Brothers S.A. (Pty.) Ltd.,
P.O. Box No. 382, Germiston, S.A.



BRASS and BRONZE
EXTRUSIONS and STAMPINGS

Fluorescent lighting has never been so simple!


MUCH EASIER INSTALLATION AND MAINTENANCE

These very robust new Mazda fittings set new standards of economy in installation and maintenance. The reflector illustrated (F1150/1/8060) is for use with a single Mazda 80 Watt 5 ft. fluorescent lamp. Similar fittings are also available with or without reflector and for use with one or two 80 Watt lamps. All these fittings incorporate the new BTH Choke which is virtually silent in operation but has no compound or other filling.

For leadership in lighting

say **Mazda!**

THE BRITISH THOMSON-HOUSTON CO. LTD.
Crown House, Aldwych, London, W.C.2
(Member of the A.E.I. Group of Companies)



Mazda F1150/1/8060

Designed for simplified installation by conduit, chain or BESA Box. Reflector slides off to expose detachable tray with auxiliary gear and lampholders ready-wired to one connector block. Lamps supported by slide-off end-covers, no spring clips required. Embossed end-plates interlock with adjacent fittings; knock-outs are provided for through wiring.

The fitting is of bonderised sheet-steel heavily stove enamelled in light stone colour and white. All holes in the metal are rubber-bushed.

Reflector may be supplied with or without upward light slots.

M4350

Lead & Gloss combined
for
DECORATION, DURABILITY
and greater covering capacity
with

SULAC



**THE LEAD BASE, HIGH GLOSS
ENAMEL PAINT**

SULAC is the perfect combination of LEAD and GLOSS which produces a brilliant, hard finish of excellent covering power. It is for use inside or Outside on all surfaces of Wood, Metal, Plaster and Stone.

SULAC is economical to use because of its fine obliterating qualities, yet it dries with a high gloss finish without brush marks. Manufactured in white and 24 attractive FAST colours.

WRITE FOR COLOUR CARD & FULL DETAILS TO:—

Sole Manufacturers

STORRY SMITHSON & CO LTD

Paint, Enamel & Varnish Specialists since 1831

BANKSIDE WORKS, HULL

Telephone: 34734 (2 lines)

Telegrams: 'Economic' Hull

and at

London, Liverpool, Glasgow, Newcastle, Cardiff and New York

**"Fine... Let's have
50 photo-copies
by tomorrow!"**



Our chairman is a man of few words: he doesn't believe in talking when pictures can tell the story.

Whenever there's a board meeting, client's visit, or works get-together, everybody has a photo-printed copy of the plan, design, or drawing to be discussed.

The chairman saves his breath, and the firm saves time and money. WEST photoprints cost as little as 5d. each, and can be produced while you wait, or in 24 hours by post. WEST copy anything, by various processes, and reproduce on paper, cloth, cellophane, glass, or metal—in colour if required.

Photoprinting is a valuable business ally—it puts everyone in the picture and helps to put your story across.

WEST


photo-copies

Please write for full details or send your work direct to

A. WEST & PARTNERS LTD.
Established 1888

36, BROADWAY · WESTMINSTER · S.W.1
TELEPHONE: WHITEHALL 5677

E.C.M. LIFTS



Over the last half-century E.C.M. lifts have gained a reputation for reliability in service and up-to-date design.

Our accumulated experience in building all types of lifts is always at your service.

ETCHELLS, CONGDON & MUIR
Limited

ANCOATS • MANCHESTER • ENGLAND

ECM 8




-  Double grip means double strength.
-  Streamlining gives better appearance.
-  Can be 'made' in 10 seconds.
-  Tested to 5,200 lb. per square inch, hydraulic and still sound.
-  All castings gunmetal—water-tested.
-  Can be made and remade any number of times.

The Hanlo Joint has been proved to provide the perfect union for light gauge copper tube. The double grip ferrule ensures an absolutely permanent joint of almost welded strength and yet the joint can be remade any number of times without losing its efficiency. Hanlo is acknowledged by Municipal Authorities and leading Contractors to be the best Compression joint available—the sales figures prove it too!

Ask for details of the Hanlo Pillar Cock adapter

THE COMPRESSION JOINT FOR



LIGHT GAUGE COPPER TUBE



—is made by

Lovell & Hanson Ltd

332, SPON LANE, WEST BROMWICH

Phone: West Bromwich 1681

Grams: "Hanlo" West Bromwich


LONDON OFFICE: 2, Countisbury St. Mark's Hill, Surbiton, Surrey

Phone: Elmbridge 5260

L.G.B.

N.P.L Tests prove amazing efficiency of **(New)** Acoustic Tiles

Soundproofing takes a new step forward! Burgess have produced—and the National Physical Laboratory have tested (Report Ref. 1015 of 12th June 1950) an Acoustic Ceiling Tile with an exceptionally high sound absorption coefficient. (see N.P.L. chart under diagram). Construction—a specially perforated metal tray, size 24in. by 12in. by 1½in., fitted with clips containing a non-inflammable, non-hygroscopic, sound absorbent pad. The clips make for rapid and easy attachment to the specially shaped tee bar runner. The Tiles are stove enamelled which gives this treatment an exceptionally uniform and neat appearance.



REVERBERATION ABSORPTION COEFFICIENTS TO NEAREST 0.05

Frequency c.p.s.	125	250	500	1000	2000	4000	6000	8000
"A" 3/32in. dia. hole.	0.15	0.50	0.75	0.80	0.75	0.75	0.75	0.75
"B" 1/8in. dia. hole.	0.15	0.45	0.70	0.75	0.80	0.85	0.85	0.85

HEAD OFFICE & WORKS
HINCKLEY · LEICESTERSHIRE

LONDON OFFICE
73 HORSEFERRY ROAD, WESTMINSTER, S.W.1

BURGESS

PRODUCTS COMPANY LIMITED

The advertisement shows a cylindrical tubular electric heater. A tag with a string is attached to it, displaying the number '3' and the text 'REASONS WHY'. To the right, the brand name 'Maxheat' is written in a large, stylized script, with 'OVAL' in a bold, sans-serif font inside an oval shape below it. Underneath, the text 'TUBULAR ELECTRIC HEATERS' is printed in a bold, sans-serif font.

TUBULAR ELECTRIC HEATERS

Command the largest sale in the world
Appearance — Efficiency — Economy

Obtainable from all leading stockists or direct from the Wardle factory, where "Prismalux" directional lighting units, "Workslite" reflectors and Wardle floodlights are also made.

Please write for Information Sheet 29.G1, to

THE

Wardle

ENGINEERING CO. LTD., OLD TRAFFORD, MANCHESTER, 16.


Hopwood

PORTITE COMPOUND

TRIED and TESTED

THE WATERPROOFER FOR CAST OR

RE-CONSTRUCTED STONE



Tests made by Harry Stanger, A.M.I.C.E., A.M.I. Mech. E., F.C.S., Testing Works and Chemical Laboratories, Westminster, show conclusively how PORTITE Compound brings Cast Stone to well within the allowable permeability range. PERMEABILITY RATE ($CC/Cm^2/SEC \times 10^6$). Period after start of test: 5 min.; 1 hr.; 2 hrs.; 24 hrs. Cast Concrete Products Association's Specification: maximum allowable permeability in cast stone (uniform throughout); 100; 25; 15; 3. Cast Concrete Untreated: 62.6; 37.3; 18.3; 5.5 (Note allowable maximum exceeded). CAST CONCRETE MADE WITH PORTITE: 19.7; 6.0; 2.3; 1.7.

EVODE PORTITE

is a carefully designed filler, the use of which not only prevents water percolation but also absorption. PORTITE makes precast concrete and reconstructed stone surfaces completely water repellent, and increases their strength. Only $1\frac{1}{2}$ lb. PORTITE required to every 100 lb. of cement; this ratio can be substantially reduced to meet individual requirements.

Stones, tiles, etc., when manufactured without a waterproof, can be made absolutely waterproof by brushing with, or by dipping into, EVODE WINTREX, a colourless liquid, invisible after application.

EVODE LIMITED

GLOVER STREET, STAFFORD

Telephone: 1590-1-2 • Grams: EVODE

SAFWAY UNIT FRAME

Scaffolding & Staging Units

put the scaffolder on your payroll

SAFWAY offers you safer faster scaffolding at less cost, without special experience or training your own men can erect and progress scaffolding which is properly braced, stressed and completely safe, by using the ingenious patented Safway units. Each Safway welded steel frame drops on to adjacent unit and is scientifically braced automatically in a way which makes easy the erection of safe structures. With its limitless versatility Safway is quickly erected around the most irregular frontages. Accessories

Any man of average skill can erect safe scaffolding as and when required with standard SAFWAY Units





and ancillary equipment provide for "special" problems of the widest variety. Safway may be purchased outright, hired or erected on contract from the manufacturers.

STERLING-SAFWAY


STERLING FOUNDRY SPECIALTIES LIMITED
JARROW-ON-TYNE.

Sole Distributors Northern Ireland:
McNeill (Engineering), Limited,
78, Duncrue Street, Belfast.

These illustrations show the exceptional versatility



of Safway. Send for the Catalogue.



SMITHS

famous for

all time...

make the

finest


MASTER

CLOCKS

and

TIME

RECORDERS



Installations may be purchased outright or arranged on rental terms. Write to us for full details or call at our Showrooms for a practical demonstration.

**ENGLISH CLOCK
SYSTEMS LTD**

Speedometer House, 179-185 Great Portland St, London W.1


Langham 7226

THE INDUSTRIAL BRANCH OF

SMITHS ENGLISH



CLOCKS LIMITED



THE ORIGINAL
SOLENT
REGD.



Specially made and highly recommended
for Institutions, Hospitals, Schools, etc.

With a reputation for
QUALITY, DURABILITY

and

RESISTANCE TO SEA AIR

LISLE MUNDAY & Co. LTD

Head Office: SOLENT PAINT WORKS
SOUTHAMPTON

FORESIGHT
PATENT - GRATES

The ROSSLYN

OVEN - OVER - FIRE
ALL - NIGHT - BURNING
COMBINATION GRATE

★ ON THE GOVERNMENT LIST



OF APPROVED APPLIANCES
for the Housing Programme

Outstanding features are:—

CONTINUOUS BURNING at very low
cost—normally 1 lb. of coke per hour;

UNLIMITED HOT WATER, DAY AND
NIGHT with minimum attention;

UNIFORM OVEN TEMPERATURE make
the oven always available for immediate
use.

MAXIMUM EFFICIENCY and ACCURATE
CONTROL by single Damper and Spin
Wheel.

The ROSSLYN is a soundly constructed, self-contained, all-purpose cooker capable of amazing performance. Supplied in Porcelain finishes—SPRING GREEN, SANDRINGHAM, MOTTLE BROWN, BLACK. This model has recently undergone severe efficiency tests. Details, prices and sizes sent on request.


SAMUEL SMITH & SONS, LTD.,
BEEHIVE FOUNDRY, SMETHWICK 41 STAFFS

THE CITY OF LONDON

a record of Destruction and Survival

with a Report on Reconstruction
by the planning consultants:

C. H. Holden and W. G. Holford



THIS IS THE STORY of the development of the City of London from Roman Times to the present day.

Here you can see the first known picture of London, made in A.D. 296, and follow the story through the growth of the mediaeval precincts, the Great Fire, Wren's plans for the City, and the Victorian improvements. A series of brilliant and hitherto unpublished photographs provide the first comprehensive record of the 1940-45 bomb damage when a third of the City was destroyed, when twenty of Wren's City churches were ruined and dramatic new views of St. Paul's were revealed over the wastes of rubble. The proposals for reconstruction prepared for the Corporation of London by the consultants, Dr. C. H. Holden and Professor W. G. Holford, are shown in full detail.


Here also an attempt is made to portray that complicated and diverse character which is peculiar to the City, that strange agglomeration of the monumental and intimate, tall business houses overlooking the intricacy of narrow alleys and quiet churchyards, the river, and the concentration of commercial and trade centres—banking, insurance, furs, shipping, textiles, wine, printing, markets and exchanges, all compressed into a few acres, an area so small that a pedestrian can comfortably encompass it in an hour or two. What he is likely to see after reconstruction is completed and new buildings are woven in amongst the ancient landmarks is visualized in a series of drawings by Gordon Cullen.

Bound in heavy buckram boards, gold blocked. Size 9½ in. by 7½ in.; 341 pages; over 360 photographs, engravings and maps, 40 of which are in colour. Price 25s., net postage 10d.

THE ARCHITECTURAL PRESS

9-13 Queen Anne's Gate, Westminster, S.W.1

Specify HERMESEAL for all your draught exclusion problems!



Draught exclusion means the prevention of infiltration... Here is a typical example

★ **BEFORE** In recent tests, the average gap around a large number of double hung sash windows (5' 0" x 2' 9") was found to average 1.8", and the infiltration rate through these gaps, under a typical wind speed of 10 m.p.h., was as much as 106.0 cu. ft. per hour per foot of gap, or 1908.0 cu. ft. for the whole window.

★ **AFTER** The rate of infiltration after draught-proofing, was actually reduced to 14.7 cu. ft. per hour per foot of gap, or 264.6 cu. ft. per hour for the whole window. The prevention achieved, therefore, was 1643.4 cu. ft. per hour or 86.1%. Tests on casement windows showed results up to 95%.

Such are the effects of efficient draught-proofing, that the conservation of heat and saving of fuel can be very greatly increased. In general about 50% of all the heat lost through the average window or door can be saved, or at least 20% of that lost throughout the average home, assuming a comprehensive installation.

THE PRODUCT can be fitted to any type of window or door—metal or wood—and consists of a specially designed strip of phosphor-bronze alloy which is guaranteed for ten years.

THE INSTALLATION is permanent and is fitted by our own specially trained staff.

THE COST is calculated on (1) The total footage involved. (2) The number of drop-seals or thresholds required. (3) Any carpentry or sealing work necessary, (4) Fitters' fares and/or subsistence as from nearest branch office.

HERMESEAL


PATENT DRAUGHTPROOF
WINDOW & DOOR EQUIPMENT

BRITISH HERMESEAL LIMITED

Head Office: 4 PARK LANE, LONDON, W.1.

Telephone: GROsvenor 4324 (3 lines).

Specify 'GALEPROOF' WINDOWS— All Wood



A SHANKS' PATENT

Wind, dust and rain cannot penetrate Shanks 'Galeproof' Windows. Sturdily built of selected timber, with check beads worked on solid. 'Galeproof' patent construction permits loose fitting casements to eliminate the bugbear of easing. Low in cost and needing little maintenance, they are repeatedly specified by many local authorities. Shanks 'Galeproof' windows can end your window worries. Why not write now for Folder and Specification Sheet?

★ WE WILL GLADLY SEND A REPRESENTATIVE TO DEMONSTRATE A MODEL WINDOW.

Shanks have been Timber Merchants for 45 years and their Joinery Plant is without equal in the Midlands.

SHANKS

TROUBLE-FREE JOINERY

E. O. SHANKS & SONS LIMITED
Dept. W.1, Lockhurst Lane, Coventry.
Phone 89051 (3 lines).

Established 1905

1653

SOMETHING TO REMEMBER

'FOSALSIL' FLUE LINING BRICKS

FOR CENTRAL HEATING

When faced with the problem of designing a boiler flue, it is worth remembering that the use of Fosalsil Flue bricks overcomes the difficulty of reconciling a construction economical in space and weight with one providing efficient thermal insulation.

This is fully explained and illustrated in the form of a leaflet which will be gladly forwarded to you on request.

MOLER PRODUCTS LTD

HYPHE WORKS : COLCHESTER

Phone: Colchester 3191 (3 lines)



Ingram Farm Estate, Bexhill,
Architect: Bexhill-on-Sea Borough Council,
Dampcourse: Standard Astos.

Astos Dampcourse is designed to fulfil all the demands imposed by modern conditions, from the high load factors in multiple-storey urban construction, to the normal movement stresses encountered in rural buildings on new land. In 24 lineal feet rolls and in all wall widths up to 36 inches. Send for descriptive leaflet No. 555 on standard and lead-lined Astos Dampcourse.

plan to use...

Astos

100% MINERAL
DAMP-COURSE

THE RUBEROID CO., LTD.,
2, COMMONWEALTH HOUSE,
NEW OXFORD STREET,
LONDON, W.C.1

A permanent barrier
against rising damp

DC.110

A new edition of ENGLISH PANORAMA by THOMAS SHARP, M.A., D.LITT.

INNUMERABLE BOOKS DESCRIBING THE English countryside have been published, particularly in the last twenty years. This is a very different sort of book: and it is, we believe, the first and only one of its kind. It is no mere description of beauty spots, but is a carefully-studied and original account of how the English scene in town and countryside has developed down the centuries, ending with a penetrating analysis of the problems of town and country planning with which we are faced today. When it was first published in 1936 it was described as "the most important contribution to the subject which has yet been made" (*Country Life*); "a large-visioned, well-balanced and uncommonly vital book" (*Manchester Guardian*); "as sound and clear as a bell" (*New Statesman*); and it has come to be regarded as something of a classic of its kind. It has been out of print for ten years; and for this new edition it has been in part revised, many new pages have been added, and it is almost entirely newly illustrated. All Thomas Sharp's dozen or more books have been praised for the quality of their writing, as well as for the ideas which they contain; and ENGLISH PANORAMA, along with the rest, though it contains much of interest for the specialist reader, is essentially a spirited and straightforward essay on a subject which should appeal to everyone who has eyes to see.

Bound in full cloth boards. Size 8½ in. by 5½ in.
148 pages, with over fifty half-tone and line illustrations.

12s. 6d. net. Postage inland 7d.


THE ARCHITECTURAL PRESS
9-13 Queen Anne's Gate, Westminster S.W.1

You won't forget the doors, *but-*

are you forgetting the security those doors must provide for your clients? Cases of burglary, still increasing, disclose advanced methods and equipment. Ingersoll have met this challenge with the new Ingersoll 'Steel-Clad' 10 (yes, TEN) lever series of locks—for residential and business property. Ingersoll Steel-Clad locks harmonise with any type of door, and their clean design will please the most fastidious.

UNIQUE MASTER-KEY SYSTEM

Your clients can Ingersoll-lock anything from a two-roomed flat to a group of factories, each with a different and exclusive combination—one master-key to open all. Employees or family can have sub-master keys to open only those buildings or rooms they are authorised to enter.



The Ingersoll Automatic Rim Deadlock

The Ingersoll Braced Mortise Clawbolt Deadlock

The Ingersoll All-Steel Padlock

- Steel-Clad for Maximum Security
- Positive Deadlocking
- Concealed Fixing
- Exclusive Combination
- No unauthorised Duplicating of Keys



AT YOUR SERVICE — THE INGERSOLL SECURITY ADVISORY BUREAU. The services of technical experts are offered to you and your clients. Write for details or, better still, ring BYRon 3456 and ask for a representative to call.

**INGERSOLL SECURITY
ADVISORY BUREAU
INGERSOLL LOCKS
LIMITED**

11, INGERSOLL CORNER, 5TH. RUISLIP,
RUISLIP, MIDDLESEX

A CORNER in CUPBOARDS!

Gaypro Storage Cabinets and Fitments are the last word in modern Kitchen efficiency.

The contents are always visible in glass Trays which are replaceable, dust and damp-proof, and housed in smartly cellulosed White or Cream Plywood Cabinets.

There are ten standard sizes to choose from, including the new Corner Cabinet, and further Models can be made to suit your specifications. Glassware can be supplied for your own installation.

Write for Literature:—



"Gay Improvement"
GROCERY & SPICE CABINETS

GAYPRO PRODUCTS LIMITED

80 GEORGE STREET, BAKER STREET, LONDON, W.1. TEL: WELBECK 9273/6

BUILDING MATERIALS

Science and Practice

by CECIL C. HANDISYDE, A.R.I.B.A.,
A.A. Dip., with a foreword by
A. H. MOBERLY, Chairman of the Text
and Reference Books Committee of the
Royal Institute of British Architects.

THIS, THE FIRST OF THREE BOOKS written and published at the recommendation of the Royal Institute of British Architects, provides up-to-date information on building materials in a form most useful to architectural students and to practising architects. Mr. Handisyde deals both with traditional materials and the many new materials which have come into use during the past two decades and takes full account of the very considerable amount of recent scientific research which has been brought to bear on all materials, old and new alike. He examines thoroughly those problems of increasing concern to architects today—to what extent alternative materials will provide comfortable buildings, warm and quiet and secure against fire, as well as weatherproof and durable.

Bound in full cloth boards. Size 9 ins. by 5½ ins., 336 pages, 58 diagrams and photographs. Price 25s., postage 10d.

THE ARCHITECTURAL PRESS

9-13 Queen Anne's Gate, Westminster, S.W.1

THE COLLEGE OF ESTATE MANAGEMENT

St. Albans Grove, Kensington, W.8.

Day and Evening Courses for the following Examinations:—
University of London Degree of B.Sc. (Estate Management) commence in October. (Day courses only. Completed application forms must be submitted by May 31st.)
Royal Institution of Chartered Surveyors (Building, Quantities and Valuations subdivisions) commence in April. (Completed application forms must be submitted by December 31st.)

Postal Courses

B.Sc. (Estate Management), commence in January and July.
The Royal Institution of Chartered Surveyors, Institution of Municipal Engineers, Royal Sanitary Institute, commence in April and October.

Town Planning Institute, commence in May and October.
Applicants for Postal Courses must submit their forms two complete calendar months before the date on which the course begins.

Applications to: The Secretary. Telephone: Western 1546

books

an illustrated catalogue of books on
architecture, planning building practice
and kindred subjects will be sent on
application to

THE ARCHITECTURAL PRESS
9-13 Queen Anne's Gate Westminster SW1



The Sign of Quality

PANELLED & FLUSH DOORS

To B.S.S. or Architects' special designs; made from kiln dried timber accurately machined; flush work power pressed.

WINDOWS

To a design and standard of dependability which will satisfy the most discriminating mind.

CUPBOARD UNITS

With our modern drying kilns and up-to-date equipment we produce a higher standard of kitchen furniture.

STAIRS


Ensure easy fitting of M.J.W. stairs, with much less trouble and cost for the contractor.

Consult the firm of 30 years' sound experience

THE MIDLAND JOINERY WORKS LIMITED
BURTON-ON-TRENT

Telephone: Burton-on-Trent 3685 (3 lines)

ONE OF THE BEST NAMES IN JOINERY



IT'S SO EZEE...

... when you have modern streamlined cabinets which literally flow together to sheathe your kitchen in gleaming cream, with Formica counter tops in a favourite colour, which can be supplied in one piece up to 9 ft. long.

You have a choice of seven different widths of counter and wall cabinets. All cabinets are made of zinc-coated steel that resists heat moisture and rust, ensuring great rigidity and durability.

Sink units from £52. Complete kitchens average £200 to £300

Visit our showrooms or write for latest brochure T.I. and full Trade Terms.

EZEE KITCHENS LIMITED
341a SAUCHIEHALL STREET, GLASGOW

Telephone: DOUGLAS 4956

London Showroom: **8 LANDSDOWNE ROW (off Berkley St.), W.1**
Telephone: GROSVENOR 5068

CLASSIFIED ADVERTISEMENTS

Advertisements should be addressed to the Advt. Manager, "The Architects' Journal," 9, 11 and 13, Queen Anne's Gate, Westminster, S.W.1, and should reach there by first post on Friday morning for inclusion in the following Thursday's paper.

Replies to Box Numbers should be addressed care of "The Architects' Journal," at the address given above.

Public and Official Announcements

25s. per inch; each additional line, 2s.

SURREY COUNTY COUNCIL.

COUNTY ARCHITECT'S DEPARTMENT.
Applications are invited for the appointment of **ASSISTANT QUANTITY SURVEYOR**, Grade VIII, at a commencing salary of £735 rising by annual increments of £25 to a maximum of £810 per annum, plus London allowance of £30 per annum.

Applicants should possess approved qualifications and experience, and preference will be given to those who are Members of the Royal Institution of Chartered Surveyors (Quantities Sub-Division). They should be capable of undertaking all stages of the work for the preparation of Bills of Quantities, including preliminary estimates, the preparation and settlement of final accounts, site measurement, and preparation of interim certificates.

The appointment will be subject to the provisions of the Local Government Act, 1937, and the successful applicant will be required to pass a medical examination.
Applications, stating age, qualifications and experience, and accompanied by copies of three recent testimonials, should be sent to the County Architect, Surrey County Council, County Hall, Kingston-upon-Thames, not later than the 6th October, 1951.

Canvassing, either directly or indirectly, will disqualify a candidate from consideration.
The Council will be unable to provide any housing accommodation and the successful applicant will be expected to make his own arrangements in this direction.

T. W. W. GOODERIDGE,
Clerk of the Council.
County Hall, Kingston-upon-Thames. 4316

CITY OF PLYMOUTH.

CITY ARCHITECT'S DEPARTMENT.

APPOINTMENT OF QUANTITY SURVEYOR.
Applications are invited for the appointment of a Quantity Surveyor A.P.T. Grade V (£570 to £620) on the established staff, subject to the Conditions of Service of the National Joint Council for local authorities administrative, professional, technical and clerical services, the Local Government Superannuation Act, 1937, and one month's notice on either side for termination. Applicants must be thoroughly experienced in all branches of the work of a Quantity Surveyor and should be Corporate Members of the Royal Institution of Chartered Surveyors (Sub-Division III. Quantities). The successful candidate will be required to pass a medical examination.

Applications on forms obtainable from the undersigned, accompanied by copies of not more than three recent testimonials and/or names of persons to whom reference may be made, should be received at my office not later than Saturday, 29th September, 1951.

THE CORPORATION MAY MAKE HOUSING ACCOMMODATION AVAILABLE TO THE SUCCESSFUL MARRIED CANDIDATE IF REQUIRED.

H. J. W. STIRLING, A.R.I.B.A.,
City Architect.
Seymour Road, Plymouth. 4318

NEWCASTLE-UPON-TYNE REGIONAL HOSPITAL BOARD SPECIAL AREA COMMITTEE FOR CUMBERLAND AND NORTH WESTMORLAND. DIVISIONAL ARCHITECT'S OFFICE.

ARCHITECTURAL ASSISTANT.
Grades A.P.T. IV or V, £480 to £525 and £520 to £570 respectively.

Applications are invited for the above permanent appointment in the office of the Divisional Architect for the Special Area (who is on the staff of the Board's Architect). The offices of the Special Area Committee are situated in Carlisle, and the successful applicant will be a member of a team of three concerned solely with practical architectural work. Applicants should at least have passed the Intermediate Examination of the Royal Institution of British Architects, and be studying for the Final Examination. The appointment will be made on either Grade IV or Grade V according to qualifications and experience. Good general experience in design and construction are essential and a knowledge of hospital work is of advantage. The salary scales of professional and technical staff will shortly be regarded with a view to improvement.

The appointment will be subject to the provisions of the National Health Service (Superannuation) Regulations, 1947. The successful candidate will be required to pass a medical examination. Applicants should state: (1) Name and full address; (2) age and whether married; (3) degrees and professional qualifications; (4) experience; (5) present appointment and salary; (6) war service; (7) date available if appointed, and (8) names and addresses of three referees.

Applications to be sent to the Clerk to the Special Area Committee, 1, Lonsdale Street, Carlisle, within 14 days of the appearance of this advertisement. 4365

MINISTRY OF WORKS.

There are vacancies in the Chief Architect's Division for **ARCHITECTURAL ASSISTANTS**, with recognised training and fair experience. Successful candidates will be employed in London and elsewhere on a wide variety of Public Buildings, including Atomic Energy and other Research Establishments, Telephone Exchanges, and Housing.

Salary: Architectural Assistants, £300-£525 per annum. Starting pay will be assessed according to age, qualifications and experience. These rates are for London; a small deduction is made in the Provinces.

Although these are not established posts, some of them have long term possibilities, and competitions are held periodically to fill established vacancies.

Apply in writing, stating age, nationality, full details of experience, and locality preferred, to Chief Architect, Ministry of Works, Abell House, John Islip Street, London, S.W.1, quoting reference WG10/BC. 2914

BOROUGH OF SUTTON AND CHEAM.

BOROUGH ENGINEER AND SURVEYOR'S DEPARTMENT.

APPOINTMENT OF ARCHITECTURAL ASSISTANT.

Applications are invited for the appointment of an Architectural Assistant, in the Department of the Borough Engineer and Surveyor, at a salary in accordance with Grade IV of the A.P.T. Division of the National Scale of Salaries, plus London "weighting." Housing accommodation may be made available if necessary.

The appointment, which is terminable by one month's notice in writing on either side, is on the permanent staff of the Corporation, and is subject to the provisions of the Local Government Superannuation Act, 1937. The successful candidate will be required to pass a medical examination.

Forms of application may be obtained from Mr. N. H. Michell, A.M.I.C.E., M.I.Mun.E., Borough Engineer and Surveyor, to whom they should be returned, accompanied by copies of three recent testimonials, not later than 1st October, 1951, endorsed "Architectural Assistant."

Canvassing, directly or indirectly, will be a disqualification.

A. PRIESTLEY,
Town Clerk.
Municipal Offices, Sutton, Surrey. 4295
August, 1951.

NATIONAL COAL BOARD—NORTH-WESTERN DIVISION.

Applications are invited for the following positions:

(a) **ARCHITECT GRADE II.** Salary scale £450 × £25-£700 per annum. Applicants should be members of the Royal Institution of British Architects with experience in the preparation of sketch plans and full working drawings, negotiations with specialist sub-contractors and supervision of work under construction.

(b) **ARCHITECTURAL ASSISTANT GRADE I.** Salary scale £410 × £20-£550 per annum. Applicants should have recent experience in the preparation of sketch plans and full working drawings for actual contracts. Preference will be given to students of the R.I.B.A.

(c) **ARCHITECTURAL ASSISTANT GRADE II.** Salary scale £300 × £20-£440 per annum. Applicants should have experience in the preparation of working drawings under supervision. A good standard of draughtsmanship will be required and preference will be given to applicants working for the Intermediate R.I.B.A. Examination.

(d) **QUANTITY SURVEYOR GRADE II.** Salary scale £450 × £25-£700 per annum. Applicants should be Members of the Royal Institution of Chartered Surveyors (Quantities Section) with experience in the preparation of estimates, bills of quantities, measuring up and adjustments of final accounts.

Appointments will be made within the salary scales according to the applicants' experience and qualifications.

Applications stating age, education, qualifications, experience and present appointment should be submitted within fourteen days of publication to the Divisional Establishment Officer, National Coal Board, North-Western Division, 40, Portland Street, Manchester, 1.

Applicants should state clearly the appointment for which application is made both in the letter and on the envelope. 4368

BOROUGH OF ILFORD.

APPOINTMENT OF TEMPORARY ARCHITECTURAL ASSISTANT (GRADE IV).

Applications are invited for the position of Temporary Architectural Assistant on the staff of the Borough Engineer's Department.

Salary in accordance with Grade IV of the A.P.T. Division, viz., £530 × £15-£575, plus London weighting.

Candidates should possess approved qualifications and have general Architectural experience in Municipal Buildings, particularly with regard to the preparation of contracts and of working drawings.

The appointment will be subject to one month's notice on either side, to the provisions of the Local Government Superannuation Act, 1937, the National Conditions of Service, and to medical examination.

Forms of application obtainable from the Town Clerk, Town Hall, Ilford, should be returned not later than the 24th September, 1951. 4353

COUNTY BOROUGH OF STOCKPORT.

ARCHITECTURAL ASSISTANTS (GENERAL AND HOUSING).

Applications are invited for the following positions:

ARCHITECTURAL ASSISTANT (GENERAL). Salary A.P.T. Grade V (£570-£620).

ARCHITECTURAL ASSISTANT (HOUSING). Salary A.P.T. Grade III (£500-£545).

TWO TRAINEES. Salary grade, General Division at age 21: Male, £265; female, £195.

The appointments will be subject to the provisions of the Local Government Superannuation Act, 1937, and the successful candidates will be required to pass a medical examination.

Applications, stating age, qualifications, and experience, together with copies of two recent testimonials, must be delivered to me not later than 29th September, 1951.

Candidates must disclose whether to their knowledge they are related to any member or senior official of the Council.

WM. F. GARDNER, M.I.C.E.,
A.M.T.P.I.,
Borough Surveyor.
Town Hall, Stockport. 4325

CHESTER-LE-STREET RURAL DISTRICT COUNCIL.

SENIOR ARCHITECTURAL ASSISTANT.

Applications are invited for the permanent appointment of a Senior Architectural Assistant, on the staff of the Council's Housing Architect and Planning Officer.

Applicants should have had some previous experience in the preparation of layout plans and house type plans for housing schemes, and membership of the Royal Institute of British Architects will be an advantage.

The appointment will be subject to the provisions of the Local Government Superannuation Act, 1937, and the National Joint Council scheme of Conditions of Service for Local Government Officers.

Salary will be in accordance with qualifications and experience as determined by the National Joint Council for Local Authorities Administrative Services, i.e., up to and including Grade V (£570-£620) per annum.

The Council cannot undertake to provide housing accommodation for the successful candidate.

Applications must be made on the prescribed form of application which can be obtained on request and must be delivered to the undersigned, not later than 12 noon, Saturday, 6th October, 1951.

R. C. BELL,
Clerk of the Council.
Union Offices, Chester-le-Street,
Co. Durham. 4366
12th September, 1951.

CITY AND COUNTY OF NEWCASTLE-UPON-TYNE.

CITY ARCHITECT'S DEPARTMENT.

Applications are invited for the following appointments in the Quantity Surveyor's Section:—

(a) **ONE SENIOR ASSISTANT QUANTITY SURVEYOR**, A.P.T. Division Grade VI (£645-£710).

(b) **ONE ASSISTANT QUANTITY SURVEYOR**, A.P.T. Division Grade V (£570-£620). Applicants must have had experience in the preparation of bills of quantities, specifications, estimates, and the settlement of final accounts on all kinds of building contracts. Preference will be given to professional Associates of the Royal Institution of Chartered Surveyors.

The appointments will be subject to the National Conditions of Service as adopted by the City Council, to the provisions of the Local Government Superannuation Act, 1937, and to one month's notice on either side. Successful candidates will be required to pass a medical examination.

Applications stating position applied for, particulars of training, qualifications, experience, present and past appointments, together with copies of two recent testimonials or the names and addresses of two persons to whom reference may be made, should be addressed to George Kenyon, A.R.I.B.A., A.M.T.P.I., City Architect, 18, Cloth Market, Newcastle-upon-Tyne, 1, not later than the 29th September, 1951.

JOHN ATKINSON,
Town Clerk.
Town Hall, Newcastle-upon-Tyne, 1. 4367
11th September, 1951.

BISHOP AUCKLAND URBAN DISTRICT COUNCIL.

TEMPORARY ARCHITECTURAL ASSISTANT.

Applications are invited for the appointment of a Temporary Architectural Assistant to work under the direction of the Council's Architect, Surveyor and Engineer. The salary for the appointment will be in accordance with Grade IV of the A.P.T. Division of the National Scale, viz., £530 × £15-£575 per annum.

Applicants must be Corporate Members of the Royal Institution of British Architects. The appointment will be subject to the Local Government Superannuation Act, 1937, and also to one month's notice on either side.

Applications stating age, qualifications, past and present appointments, experience, and giving the names of two persons to whom reference can be made must reach the undersigned not later than Saturday, 6th October, 1951.

R. W. RYTHE,
Clerk of the Council.
Town Hall, Bishop Auckland. 4361
10th September, 1951.

COUNTY BOROUGH OF GREAT YARMOUTH.
APPOINTMENT OF GENERAL ASSISTANT ARCHITECT.

Applications are invited for the appointment of a General Assistant Architect, in the Borough Engineer's Department, for housing, seaside and general work, at a salary in accordance with A.P.T. Grade VI (£530-£575).

Applicants should have passed the Intermediate Examination of the R.I.B.A. The appointment will be terminable by one month's notice on either side, subject to the provisions of the Local Government Superannuation Act, 1937, and to the passing of a medical examination. The Council are unable to offer housing accommodation to the successful candidate.

Applications, stating age, qualifications and experience, together with the names of three persons to whom reference may be made, should be enclosed in an envelope endorsed "General Assistant Architect," and must be received by me not later than Friday, the 28th September, 1951.

Candidates must disclose in writing whether they are related to any member or officer of the Council. Canvassing, directly or indirectly, will disqualify.

FARRA CONWAY.

Town Clerk.

Town Hall, Great Yarmouth.

4th September, 1951.

4350

GOVERNMENT OF NORTHERN IRELAND.
CIVIL SERVICE COMMISSION.
ASSISTANT QUANTITY SURVEYOR.

Applications are invited for the permanent and pensionable post of Assistant Quantity Surveyor, Class I, in the Ministry of Health and Local Government, Northern Ireland.

Qualifications: Candidates must be Associates of the Royal Institution of Chartered Surveyors (formerly P.A.S.I. Quantities Section). A wide experience of quantity surveying in all its branches is essential. Preference will be given to those with a working knowledge of current housing practice and an aptitude for cost analysis.

Remuneration: The salary scale is £200 rising by annual increments of £25 to £750 (linked to entry at age 26 plus £25 for each year above that age subject to a limit of £650 and minus £25 for each year below that age). This scale will be revised in the near future.

Preference will be given to suitably qualified ex-Servicemen who served in the 1914-18 or 1939-45 wars provided they can, or within a reasonable time will be able to, perform the duties efficiently.

Closing date: Applications must be made on the prescribed form which may be obtained from the Secretary, Civil Service Commission, Stormont, Belfast, and must be returned duly completed with copies of two recent testimonials so as to reach him not later than 8th October, 1951.

4363

CIVIL SERVICE COMMISSION, DUBLIN.
POSITION VACANT.

ARCHITECTURAL INSPECTOR in the Department of Health. Salary scales (approx.): Man, £890-£1,071; woman, £708-£890. Age limits: 27-45 years with extensions of the upper limit in certain cases. Essential qualifications include satisfactory practical experience in the design and construction of buildings, the preparation of designs and contract drawings from sketches or instructions and the supervision of building contracts.

Further particulars obtainable from the Secretary, Civil Service Commission, 45, Upper O'Connell Street, Dublin. Latest time for accepting completed application forms: 5 p.m. on the 16th October, 1951.

4364

SALOP COUNTY COUNCIL.

COUNTY ARCHITECT'S DEPARTMENT.

Applications are invited for the appointment of **SENIOR ASSISTANT ENGINEER**, on A.P.T. Grade VI (£645 rising to £710 per annum). Applicants must be experienced in the preparation of drawings and specifications for central heating and hot-water supply installations, and preference will be given to Associate Members of the Institution of Heating and Ventilating Engineers. The appointment will be subject for its termination to one month's notice in writing on either side; to the terms of the National Joint Council's Scheme of Conditions of Service and to the provisions of the Local Government Superannuation Act, 1937. The successful applicant will be required to pass a medical examination.

Application forms may be obtained from the County Architect, Mr. C. H. Simmons, A.R.I.B.A., Dip.T.P., Column House, London Road, Shrewsbury, to whom they must be returned, accompanied by copies of three recent testimonials, not later than Friday, 5th October, 1951.

G. C. GODBER.

Clerk of the Council.

Shrewsbury.

September, 1951.

4356

BUCKS COUNTY COUNCIL.

The County Architect invites applications from qualified **ASSISTANT ARCHITECTS** who possess a keen and energetic enthusiasm for their profession. Candidates should preferably have been trained at a recognised School of Architecture. Salary Grade VI, £645-£710 per annum.

The appointment is superannuable, and subject to medical examination.

A weekly allowance of 25s. and return fare home once every two months may be paid for six months to newly appointed married officers of the Council unable to find accommodation.

Further particulars and form of application may be obtained from the County Architect, County Offices, Aylesbury, to whom applications must be delivered by 1st October, 1951.

4356

LINDSEY COUNTY COUNCIL.
COUNTY ARCHITECT'S DEPARTMENT.
Vacancies on the permanent staff as follows:—

(a) **ARCHITECTURAL ASSISTANT.** A.P.T., IV (£530-£575).

(b) **ARCHITECTURAL ASSISTANT.** A.P.T., III (£500-£545).

Applicants should have passed the Intermediate Examination of the R.I.B.A. or its equivalent, and have had practical experience.

N.J.C. Conditions of Service. Canvassing will disqualify.

Allowance of 25s. per week and return fare home bi-monthly may be paid up to six months to married men unable to find housing accommodation.

Relationship to a member or senior officer of the Council is to be disclosed in writing by any applicant with his application.

Applications, stating age, qualifications and experience, with the names of two persons to whom reference can be made, to be sent to the undersigned not later than Thursday, 27th September, 1951.

A. RONALD CLARK, A.R.I.B.A.,

A.M.T.P.I.

County Offices, Lincoln.

County Architect

4352

BOROUGH OF CHELTENHAM.
APPOINTMENT OF SENIOR ARCHITECTURAL ASSISTANT.

Applications are invited for the appointment of a Senior Architectural Assistant in the Department of the Borough Surveyor, at a salary and subject to the conditions contained in the National Scheme of Salaries and Conditions of Service—namely, A.P.T., Grade VII, £685-£760 per annum.

Applicants should be qualified, and experienced in the design of Public Buildings, Housing and Ancillary Buildings in connection with Estate Development.

The appointment is subject to one month's notice on either side, and the successful applicant will be required to pass a medical examination and contribute to the Council's Superannuation Fund.

Applications, endorsed "Senior Architectural Assistant," stating age, qualifications, experience, and giving the names of two referees, to reach Mr. G. Gould Marsland, M.B.E., B.Sc., M.Inst.C.E., Borough Surveyor, Municipal Offices, Cheltenham, not later than Saturday, 29th September, 1951.

4351

CROWN AGENTS FOR THE COLONIES.

ARCHITECTURAL ASSISTANT required by the Government of Northern Rhodesia for the Public Works Department, for one tour of 36 months. Commencing salary according to age and experience, in the scale £510 rising to £865 a year, plus cost of living allowance, at present equal to 15 per cent. of salary. Gratuity of £25 for each three months' service on satisfactory completion of contract. Free passages. Liberal leave on full salary. Candidates 23 years or over should be students of the Royal Institute of British Architects or have had four years' practical experience. (Candidates will be accepted at the minimum of the scale from age 21 years if they have passed the Intermediate examination of the Institute.) A knowledge of survey work and modern school practice would be an advantage.

Apply at once by letter, stating age, full names in block letters and full particulars of qualifications and experience, and mentioning this paper to the Crown Agents for the Colonies, 4, Millbank, London, S.W.1, quoting M.27758 A, on both letter and envelope. The Crown Agents cannot undertake to acknowledge all applications and will communicate only with applicants selected for further consideration.

4362

LONDON ELECTRICITY BOARD.

ASSISTANT QUANTITY SURVEYORS.

Applications are invited for the above positions in the Construction Branch of the Chief Engineer's Department at LESCO House, Stamford Street, S.E.1.

Applicants should be experienced in the preparation of Bills of Quantities in all their stages, measurement of Variations and remeasurement of Contracts, and will work under the direction of a Chartered Quantity Surveyor.

The posts have been graded under the National Joint Board agreement of February 17, 1950, as Grade V (Schedule C). Salary range: £607 19s. to £814 15s. per annum inclusive, the commencing salary being dependent upon qualifications and experience. This grading is subject to the approval of the District Joint Board and confirmation by the National Joint Board.

Application forms obtainable from Establishment Officer, 46, New Broad Street, E.C.2, to be returned duly completed within 10 days from the appearance of this advertisement. Please enclose addressed foolscap envelope and quote Ref. EST/V/1216/A on envelope and all correspondence.

4349

LONDON COUNTY COUNCIL.

ARCHITECT'S DEPARTMENT.

Applications are invited for positions of **ARCHITECT** Grade III (£550-£700) and **TECHNICAL ASSISTANT** (up to £550) for architectural work on new housing, schools and other public buildings. The positions are superannuable, and the above rates are subject to an addition of 10 per cent. on the first £600 and 7½ per cent. on any remainder. Application forms from the Architect, The County Hall, S.E.1, enclosing stamped addressed foolscap envelope and quoting AR/EK/A. Canvassing disqualifies. (514) 3914

LANCASHIRE COUNTY COUNCIL.
Applications are invited for the following appointments in the County Planning Department:—

(1) **SENIOR PLANNING ASSISTANTS (ARCHITECTURAL)**, A.P.T. VI (£645-£710) required at Headquarters, Preston. Duties include design and preparation of detailed layouts for housing schemes, village extensions, and central area improvements. Candidates must be qualified Architects.

(2) **PLANNING ASSISTANT**, A.P.T. I-V (£440-£620), required at the Liverpool Divisional Office. Salary commensurate with qualifications and experience. Candidates for Grade V should be qualified by professional examination as Architects, Surveyors, Engineers or Town Planners, and for Grades I-IV should possess a University Degree or the Intermediate Certificate of an appropriate professional body.

Applications, stating clearly appointment applied for, and giving the names, addresses and qualifications of two referees (preferably one should be present employer), should reach the County Planning Officer, East Cliff County Offices, Preston, by Monday, 15th October, 1951.

CARDIGANSHIRE COUNTY PLANNING COMMITTEE.
APPOINTMENT OF PLANNING ASSISTANT (GRADE VI).

Applications are invited for the post of Planning Assistant in the County Planning Department, at a salary in accordance with A.P.T., Grade VI (£645-£710).

Applicants should be Members or Associate Members of the T.P.I., preferably with complementary qualifications, and should be experienced in the preparation of Development Plans and Planning Surveys, any experience in the supervision of staff is essential.

The post is established, pensionable, subject to medical assessment and prescribed conditions. The Council cannot undertake to provide housing accommodation for the person appointed.

Applicants should give particulars of age, education, technical training, qualifications, experience, present salary, present and previous appointments which, together with the names of two referees, must reach the undersigned not later than noon on Saturday, 6th October, 1951.

J. E. R. CARSON.

Clerk of the County Council.

Cambrian Chambers, Aberystwyth.

4370

SHEFFIELD REGIONAL HOSPITAL BOARD.
Applications are invited for the following permanent appointment in the Architectural Division of the Headquarters' Staff of the Board:—

TWO SENIOR ASSISTANT ARCHITECTS. Grade A.P.T. VIII (£686+£25-£760 per annum). (The salary scales are at present under review.)

Applicants must be Members of the Royal Institute of British Architects, and have had experience in the design and construction of Hospitals and be capable of carrying out and advising on large building contracts.

Appointments will be subject to the National Health (Superannuation) Regulations, 1947, and will be terminable by one month's notice. Applications stating age, qualifications, present position and past experience, together with the names of three referees, should be addressed to the Secretary, Sheffield Regional Hospital Board, Fulwood House, Old Fulwood Road, Sheffield, 10, not later than the 6th October, 1951.

4371

COUNTY BOROUGH OF HUDDERSFIELD.
EDUCATION COMMITTEE.

Applications are invited for appointment as **ASSISTANT ARCHITECT** (A.P.T., Grade VI, £645-£710).

This post offers an opportunity for gaining experience in the design and erection of school buildings in modern construction. Candidates must be Registered Architects and preference will be given to applicants who are Members of the R.I.B.A.

The appointment will be subject to one month's written notice on either side, expiring on the last day of any month; to the successful applicant passing a medical examination; to the provisions of the Local Government Superannuation Act, 1937, and to the conditions of service of the National Joint Council.

Applications, stating age, qualifications, present appointment, experience, etc., with copies of two recent testimonials, should be submitted to the undersigned as early as possible, but not later than 10 a.m. Thursday, 27th September, 1951.

H. KAY.

Chief Education Officer.

Education Offices, Ramsden Street,

Huddersfield.

4375

BOROUGH OF BEXLEY.
BOROUGH ENGINEER AND SURVEYOR'S DEPARTMENT.

Applications are invited for the following posts:—

ASSISTANT ARCHITECT (General). Salary within Grade A.P.T. VI (£645-£710 per annum), plus London "weighting" allowance (£30).

ASSISTANT ARCHITECT (General). Salary within Grade A.P.T. V (£570-£620 per annum), plus London "weighting" allowance (£30).

Forus of application with Conditions of Appointment may be obtained from the Borough Engineer and Surveyor, West Lodge, Bexleyheath, to whom completed applications must be returned by Friday, 5th October, 1951.

Canvassing, directly or indirectly, will disqualify.

W. WOODWARD

Town Clerk.

4378

ARCHITECTS, MAINTENANCE SURVEYORS,
QUANTITY SURVEYORS, AND LANDS
OFFICERS.

THE CIVIL SERVICE COMMISSIONERS invite applications for permanent appointments to the basic (Assistant) grades given above in a number of Departments in England and Scotland. Applications will be accepted at any time up to and including 31st December, 1951. Selected candidates will be interviewed as soon as possible after the receipt of their application forms. Successful candidates may expect early appointments. Candidates are advised to apply as early as possible.

All candidates must be at least 25 and under 35 years of age on 1st January, 1951, with extension for regular service in H.M. Forces, and up to two years for permanent Civil Servants. All candidates must have the appropriate professional qualifications and experience.

The London salary scale for men aged 30 and over is £600-£750. Lower starting salary for younger entrants (from £475 at age 25). (The next higher grades are: Main Grade, £750-£825-£1,000; Senior Grade, £1,050-£1,270.) Salaries for women and for officers appointed to the provinces will be somewhat lower.

Forms of application and copies of the regulations with full details of qualifications required from the Civil Service Commission, Scientific Branch, Trinidad House, Old Burlington Street, London, W.1, quoting No. 3405TA. Completed application forms should be returned as soon as possible. 4380

CAMBRIDGESHIRE COUNTY COUNCIL.
COUNTY PLANNING DEPT.

Applications are invited for the appointment of a **PLANNING OFFICER** on Grade A.P.T. VIII, of the National Joint Council's Scales (salary £735 to £810 per annum).

Candidates should hold the qualifications A.R.I.B.A. and A.M.T.P.I., and be able to drive a car. A wide knowledge of modern planning technique will be required, and previous experience in a planning office will be an advantage.

The successful candidate will be in charge of the design aspect of the County Development Plan, including the preparation of schemes for village development and central area redevelopment. He will also be expected to advise on housing layouts and general landscape design.

The appointment is subject to the provisions of the Local Government Superannuation Act, 1937, the Council's Conditions of Service, to the successful candidate satisfactorily passing a medical examination, and to three months' notice on either side of termination of appointment. Financial assistance, up to £2 weekly for a period not exceeding six months, may be given of the person appointed cannot obtain housing accommodation and has to maintain his own present

residence in addition to the expense of lodgings in Cambridge.

Applications, stating age, past and present appointments (with dates), experience, qualifications, present salary and the names of two referees, should be received by the undersigned not later than the 15th October, 1951.

CHARLES PHYTHIAN,

Clerk of the County Council.
Shire Hall, Castle Hill, Cambridge. 4358

CORBY DEVELOPMENT CORPORATION.

Applications are invited from well qualified persons for the appointment of **CHIEF ARCHITECT** at a commencing salary within the range of £1,500-£1,700, according to experience and qualifications.

Candidates must have had considerable experience in the design and execution of large scale housing operations and other buildings for local authorities, and the necessary staff organisation and control. Town Planning experience, though not essential, may be an advantage.

The appointment is under the direction of the General Manager, and is expected to involve large scale construction projects associated with the development of a New Town.

The successful candidate will be required to pass a medical examination, to contribute either to a Superannuation or an Assurance Scheme, and to carry out such duties as the Corporation may require.

Applications, stating age, education, training, qualifications, experience, past and present appointments and salaries, together with the names of two persons to whom reference may be made, must be received by the undersigned not later than Monday, 15th October, 1951. Envelopes and applications should be clearly endorsed "Chief Architect."

R. F. BROOKS GRUNDY,

General Manager.

Corby Development Corporation,
The Stone House, Corby, Northants. 4369

**COUNTY BOROUGH OF BURNLEY.
PLANNING ASSISTANT.**

Applications are invited for the above appointment in the Borough Surveyor's Department at a salary within the range of A.P.T. Grade III (£500-£545 per annum) to Grade V (£570-£620 per annum) according to experience and qualifications.

Applicants should have had experience in a similar capacity and preference will be given to candidates holding a recognised qualification.

Forms of application, etc., may be obtained from the Engineer and Surveyor, 22-24, Nicholas Street, Burnley, to whom applications should be returned not later than Monday, 8th October, 1951.

C. V. THORNLEY,
Town Clerk. 4390

**COUNTY BOROUGH OF HALIFAX.
BOROUGH ENGINEER'S DEPARTMENT.**

Applications are invited for the following appointments:—

(a) **ARCHITECTURAL ASSISTANT** (Education) Grade VI, £645-£710.

(b) **BUILDING MANAGER**, £12 per week.

(c) **QUANTITY SURVEYOR'S CLERK**, Misc. Grade IV, £400-£470.

The successful candidate for post (a) will be engaged on the building and planning of new Schools, should have had previous experience in this branch of architecture and should possess appropriate technical qualifications.

The successful candidate for post (b) will have direct control of the Building Section of the direct labour organisation of the Borough Engineer's Department and it is essential that he should have had extensive experience in the supervision and organisation of building works.

Candidates for post (c) should have had experience in the handling of builders' quantities and should be competent to act as an assistant to the Quantity Surveyor.

The appointments will be subject to the conditions of service adopted by the Corporation and to the Local Government Superannuation Act, 1937.

Candidates must disclose whether to their knowledge they are related to any member of or holder of any senior office under the Council.

Applications stating age, qualifications, present position, salary and experience accompanied by copies of three recent testimonials should be appropriately endorsed and delivered to the undersigned not later than Wednesday, 3rd October, 1951.

RICHARD DE Z. HALL,
Town Clerk.

Town Hall, Halifax.
13th September, 1951. 4384

ROAD HAULAGE EXECUTIVE.

Vacancies in London for **ARCHITECTURAL DRAUGHTSMEN**. Applicants should have passed the Intermediate Examination of the R.I.B.A., be capable of preparing working drawings and details and be neat and accurate draughtsmen with a minimum of five years' experience in drawing offices. Some school training will be an advantage. Salary within the range £520-£550. Applications in duplicate, giving date of birth, qualifications, experience, present post and salary, should reach the Chief Staff and Welfare Officer (S.219), Road Haulage Executive, 222, Marylebone Road, London, N.W.1, within seven days of the appearance of this notice. Selected candidates will be required, if eligible, to join a contributory superannuation scheme. 4386

High Victorian Design

a study of the exhibits of 1851

by NIKOLAUS PEVSNER

TO RUBIN the Crystal Palace was no more than 'a greenhouse larger than ever greenhouse was built', to Tennyson the objects shown within it were 'shapes and hues of Art divine, all of beauty, all of use'. Today the exhibits are considered outrageous 'examples of the hideous and the debased', but the building cannot be too highly praised; it is 'a precept inspiring as the Parthenon, an exemplar vital as the Pont du Gard'.

This complete changeabout in taste, and the contrast in the reaction to the architecture as opposed to the design of 1851 amongst critics of 100 years ago is as puzzling as that amongst critics of today. Obviously there is a problem here, and it is that problem which Dr Pevsner, our most eminent critic of both architecture and design, attempts to solve in the present volume. He finds his solution in a penetrating and detailed examination of a selected 120 1851 exhibits. Why did, for instance, some of the most intelligent critics admire unreservedly the machine carving of Gothic ornaments on a church screen? What frame of mind can explain the Irish bog-oak chair with its two arms formed by wolf-dogs, one at ease and recumbent, the other infuriated and sitting up so that nobody could use the chair in comfort? In answering many such questions Dr Pevsner arrives at certain conclusions which go far in explaining the mentality of the mid-nineteenth century, not only in matters aesthetic, but also in many other matters.

Size, crown 8vo., bound in full cloth boards, with 162 pages containing over 120 illustrations, and with a jacket in colour designed by Gordon Cullen. Price 12s. 6d. net, postage 4d.

THE ARCHITECTURAL PRESS 9-13 QUEEN ANNE'S GATE WESTMINSTER SW1



From Dr Pevsner's book: the Irish bog-oak chair.

**METROPOLITAN BOROUGH OF
PADDINGTON.
APPOINTMENT OF ASSISTANT DIRECTOR
OF HOUSING (TECHNICAL) (A.P.T. X)
(£900-£1,030).**

Applications are invited for this appointment within the above grade.

Candidates must (i) be chartered and registered architects with considerable practical and administrative experience in all branches of building work; (ii) have had good experience in contemporary design; and (iii) be thoroughly conversant with local authority work. Some town planning experience would be an advantage.

The successful candidate will be directly responsible to the Director of Housing for the technical work of the Housing Department. This work includes the design and supervision of large housing schemes, building work for Council departments, liaison with consultants engaged in connection with Council housing schemes and the direct supervision of the technical staff.

Candidates must furnish information under the following headings, viz:—

(i) Age; (ii) qualifications; (iii) present and previous appointments and dates; (iv) experience, and (v) names and addresses of three referees.

Covering envelopes must be endorsed "Appointment A.29" and should reach me by 10 a.m. on 8th October, 1951.

W. H. BENTLEY,
Town Clerk.

Town Hall, Paddington, W.2.
14th September, 1951.

4385

Architectural Appointments Vacant
4 lines or under, 7s. 6d.: each additional line, 2s.

ARCHITECTURAL ASSISTANT required in Westminster office of Consulting Engineers. Apply, stating age, experience, qualifications, and commencing salary required. Box 4292.

IMPERIAL CHEMICAL INDUSTRIES, LTD.,
NOBEL DIVISION, requires **ARCHITECTURAL ASSISTANTS**, to work at Stevenston, Ayrshire. Associate membership of the Royal Institute of British Architects would be an advantage, but not an essential qualification. Applicants should have some experience in factory buildings, offices, canteens, etc. Applications should be made to the Staff Manager, Nobel House, 25, Bothwell Street, Glasgow, C.2.

ARCHITECTURAL ASSISTANTS required immediately in Warrington office for preparation of detailed working drawings. Write, stating experience, qualifications and salary required. to Box 4320.

**BOOTS PURE DRUG CO. LTD.,
NOTTINGHAM.**

ARCHITECT'S DEPARTMENT.

Applications are invited for the appointment of **ARCHITECTURAL ASSISTANTS** to the permanent staff of the above department. Applicants should have had several years experience in an architect's office and be capable of carrying out a job from sketch plan to building stage. Thorough knowledge of building construction and ability to prepare neat, accurate drawings is essential. Ability to calculate to steel and reinforced concrete structures and to prepare attractive sketch plans desirable.

The department has in hand works of a very varied nature including new chemical works, laboratories, experimental farms, office buildings, housing, schools, generating plants and retail shop premises, etc. Permanent and progressive appointment for the right men who will be required occasionally to visit works in progress of building in all parts of the British Isles.

A five-day week is in operation and the successful applicant will be required to pass a medical examination and to join the company's pension scheme.

Write stating age, qualifications, training, experience and salary required to: Chief Architect, Boots Pure Drug Co. Ltd., Station Street, Nottingham. 4387

SENIOR ASSISTANT urgently required for permanent post in large General Practice in Jersey. Applicants should be 28 or over, preferably qualified, and may be interviewed by appointment in London. Assistance can be given in finding housing accommodation in Jersey. Reply, giving details of experience and salary required, Box 4334.

ARCHITECTURAL ASSISTANT, Intermediate standard, required in Architects' office of multiple shop company, interesting work, possibility of permanency. Write Box 4383.

JUNIOR ASSISTANT, about 22 years old, required in London Architect's Department. Must be neat, quick draughtsman, with knowledge of elementary construction and some experience of building surveys. Interesting work, and secure future for suitable applicant. Write, stating age, details of past work, education, and salary required. Box 4382.

JUNIOR ASSISTANT required for Architect's office in London (W.1 area). Interesting work. Progressive appointment offered to keen individual. Salary £350-£450 p.a. Write, stating age, training and experience, to Box 4381.

WANTED immediately in office of Architect dealing with domestic work for London Housing Company, **ARCHITECTURAL ASSISTANT**, of Inter. R.I.B.A. standard, able to prepare designs and working drawings from sketches. Salary £400 to £600 per annum, according to experience and capabilities. Pension Scheme. Box 4374.

TWO ARCHITECTURAL ASSISTANTS required. Salary £400 and £600 p.a. Apply Frederick Gibberd, 8, Percy Street, W.1. 4373

ARCHITECT'S ASSISTANT required by firm of Architects in South-West England; age 30 to 35. State experience and salary required to Box 4372.

ARCHITECTURAL ASSISTANT, with 3 or 4 years of practical office experience, required at once by Architects in South Kensington area. Salary: £350-£500 p.a., according to ability. 5-day week. Apply Box 4359.

ASSISTANT ARCHITECT required in Railway Office in London. Preferably A.R.I.B.A. Must have had several years' practical experience. Responsible for sketches and working drawings, under supervision. Commencing salary approximately £550 per annum. Apply to Civil Engineer, the Railway Executive, Southern Region, Waterloo Station, London, S.E.1. 4347

SENIOR ARCHITECTURAL ASSISTANT required for progressive London office. Considerable experience in construction, supervision, preparation of specifications, etc., essential. Interesting work. Preparedness to do 6-8 month periods abroad an advantage, but not essential. Salary according to experience. Write, giving full details, to James Cubitt & Partners, 25, Gloucester Place, W.1. 4356

ARCHITECTURAL ASSISTANT of Intermediate standard required for West End architect's office. Previous office experience preferable but not essential. Must be capable of preparing working drawings and details from sketch plans, etc. Apply stating age, experience and salary required, etc., to Box 4389.

ARCHITECT'S ASSISTANT required for ecclesiastical and general practice. Apply stating age, experience, and salary required to V. H. Randall Blacking & Robert Potter, F.R.I.B.A., 21, The Close, Salisbury. 4386

Architectural Appointments Wanted

YOUNG Lady, Intermediate R.I.B.A. standard, requires post, preferably West of England. 4 years' office experience. Box 238.

NOEL WOOD MOSAIC

**OFFICES
SCHOOLS
HOSPITALS
FACTORIES**

**WOODBLOCK
FLOORING
AT ITS BEST**

**DURABLE
DECORATIVE
ECONOMICAL
GUARANTEED**

E.J. ELGOOD LTD. INDUSTRIAL FLOORING SPECIALISTS
INSULCRETE WORKS, YEOMAN ST. S.E.8 TELEPHONE: BERmondsey 1144 (6 lines)

STONE CLEANING & RESTORATION

INCLUDING MOSAIC TERRAZZO AND MARBLEWORK

PETER COX & PARTNERS LTD

**TELEPHONE
MAYFAIR
0403**

CONTRACTS UNDERTAKEN
THROUGHOUT THE BRITISH ISLES

**33, NORTH ROW,
PARK LANE,
W.1.**

Architect
London
ASSIS-
able to
gs from
accord-
Pension

NTS re-
Apply
4375
by firm
d; age 30
quired to

h 3 or 4
required
on area,
ly. 5-day

Railway
R.I.B.A.
experience,
drawings,
approx-
Engineer,
Waterloo
4347

TANT re-
ce. Con-
servation,
essential,
6-8 month
essential,
e, giving
tners, 25,
4355
of Inter-
West End
ence pre-
apable of
alls from
experience

ired for
e. Apply
quired to
Potter,
4388

Wanted
standard,
England.

G

ISTS
(lines)

N

V,

ASSOCIATE (31), with ability to accept full responsibility through all stages, seeks progressive appointment, where there is scope for initiative, with prospects, in country practice. Write Box 249.

STUDENT, 5th year U.S. University, seeks experience in British office. Salary required approx. £400. Box 251.

STUDENT (Polish nationality), recently completed the 5-year course at Architectural School (exempt from Intermediate examination), seeks position in London. Private office. Box 250.

ASSOCIATE R.I.B.A. (39) seeks appointment, London or S.W. Many years' varied experience, including L.A. Housing, Surveys. Driving licence. Moderate salary. Box 244.

JUNIOR ASSISTANT (Female), partly trained, with several years' office experience, seeks position with Architect. Box 243.

INDUSTRIOUS ARCH. DRAUGHTSMAN (23) requires position, with prospects, in London or district office. Experienced in working drawings, details, surveys, etc. 245

REGISTERED ARCHITECT of exceptional ability and experience, with reputable employers both home and overseas, seeks position of responsibility with firm producing industrial schemes, public buildings and works, etc. Taking special Final Examination in November. Box 247.

YOUNG MAN (22), Leicester School Arch. Diploma, requires position in a private office of a southern or coastal town. Box 248.

PROBATIONER R.I.B.A. (24) urgently requires job. Holds National Certificate in Building. London or West Essex. R. K. Miller, 32, St. George's Avenue, Forest Gate, E.7. 246

STUDENT (22), recently completed the 5-year course at a recognised school, seeks position in London office. Box 241.

QUALIFIED ARCHITECT seeks part-time work, 3 to 4 days per week, London area. Box 4391.

MALE ARCHITECTURAL ASSISTANT (24), Inter. and Final standard, 5 years' full-time training, seeks post, 15 miles Bath or Bristol area. Box 237.

Other Appointments Vacant

4 lines or under, 7s. 6d.; each additional line, 2s.

THE RAILWAY EXECUTIVE (Western Region) have a vacancy in the Estate and Rating Surveyor's Department, Paddington, for a **TECHNICAL ASSISTANT**. Applicants should be good Architectural Draughtsmen with a sound knowledge of building construction, capable of preparing drawings and specifications and exercising supervision of building work. Salary according to age (£310 at 25), rising to maximum of £515 at 36, with prospects of advancement. Apply in writing to The Estate and Rating Surveyor, 125, Westbourne Terrace, London, W.2. 4346

Services Offered

4 lines or under, 7s. 6d.; each additional line, 2s.

ARCHITECTURAL ASSISTANTS require additional work. Surveying, Levelling, Working Drawings, Details, Tracings, etc. W. Graysmark, 41, Wadham Gardens, Greenford, Middx. 4333

DURING present restrictions on private building, small post-war Partnership with extensive architectural and civil engineering experience is available to give temporary assistance to other professional firms. Box 4375.

LADY ARCHITECT (33), with University degree-diploma and two years' public office experience, going abroad early next year, offers her services for 4-5 months to an Architect or Contractor. Willing to work hard, but only where is sure to find excellent all-round practical experience. Present salary £560; may accept less. Central or West London preferably. Box 4377.

OFFICE requires additional work to keep staff. Operating London, Bedfordshire and Eastern Counties. Work kept strictly confidential. Box 4376.

CAPABLE and efficient **ARCHITECTURAL DRAUGHTSMAN** seeks spare-time work. 30-mile radius of London. Box 4360.

Miscellaneous

4 lines or under, 7s. 6d.; each additional line, 2s.

A. J. BINNS, LTD., Specialists in the supply and fixing of all types of Fencing, Gates and Cloakroom Equipment. Harvest Works, 99-107, St. Paul's Road, N.1. Canonbury 2061.

FRENCH POLISHERS.—Wm. Burton's, for every style of polishing. 26, Foulser Road, Upper Tooting, S.W.17. BAL. 3968. 2617

WINKFIELD MANOR NURSERIES, ASCOT, lay out Rock and Formal Gardens and Labourless "Allweather" Tennis Courts. Eight Chelsea Gold Medals since 1947. Contractors to the Festival of Britain. Winkfield Row 393. 1716

FENCING FOR ALL PURPOSES. Supplied and erected; established 190 years. Parker, Winder & Church, Ltd., 80, Broad Street, Birmingham, 1. Telephone: Midland 5001.

DEMOLITION Site Clearance, by Syd Bishop & Sons, Demolition Contractors, Swanley, Kent. Phone Swanley 2519. 4216

"MAY I ASSIST YOU?" Quantity Surveyor available to prepare Bills of Quantities, quickly. Large War Damage Claims negotiated. Please write and interview will be arranged at once. Box 4315B.

INSURANCE

ARCHITECTS' Indemnity Insurance effected. Please write for Proposal Form to E. J. SAXBY, Incorporated Insurance Broker, 37a, Carfax, Horsham, Sussex. Tel. 990. 2039

Educational Announcements

4 lines or under, 7s. 6d.; each additional line, 2s.

R. I.B.A. and T.P.I. EXAMS.—Stuart Stanley, M.A., F.R.I.B.A., M.T.P.I., T.P.Distn. (Tutor Sch. of Arch. Lon. Univ.), and G. A. Crockett, B.A., A.R.I.B.A. (Medallist), A.M.T.P.I., F.R.S.A., prepare students by correspondence tuition. Stuart Stanley & Crockett, 10, Adelaide Street, Strand, W.C.2. TEM. 1603/4.

WINSTON WALKER is now enrolling Students for his Course of Lectures in Design for the Final of the R.I.B.A. Personal tuition only, and enrolment after interview only. Tel.: SLO. 1410. 4354

RIBA INTER, FINAL & SPECIAL FINAL

Postal Courses in all subjects of the 1951 exam syllabus (including Professional Practice) are conducted by **THE ELLIS SCHOOL OF ARCHITECTURE** Principal: A. B. Waters M.B.E., G.M., F.R.I.B.A., 103B, OLD BROMPTON RD., LONDON, S.W.7 Phone: KEN 8641 and at Worcester

QUANTITY SURVEYING

Postal Courses for R.I.C.S. I.A.A.S. and I.Q.S. Exams in all subjects of each syllabus. Tuition by well qualified tutors under the direction of the Principal, A.B. Waters M.B.E., G.M., F.R.I.B.A., Descriptive booklet on request.

THE ELLIS SCHOOL

103B, OLD BROMPTON RD., LONDON, S.W.7 Phone: KEN 8641 and at Worcester

LINOLEUM

Information Sheets

19/G1, 2, 3 & 4

Reprints available on application to: Linoleum Manufacturers' Association, 273/287, Regent Street, London, W.1.



CHAIN LINK FENCING

A COMPLETE FENCING SERVICE

BOULTON AND PAUL LIMITED

NORWICH

CRC9P



for

PROTECTIVE DECORATION

internal & external



THE ADAMITE COMPANY LIMITED

MANFIELD HOUSE, STRAND, W.C.2



W. J. FURSE & CO. LTD.

12 TRAFFIC STREET, NOTTINGHAM
LONDON: 14 CARTER STREET, WESTMINSTER, S.W.1
BRISTOL: 12 SYDENHAM ROAD, COTHAM 4

WHITE FACING BRICKS

(S. P. W. BRAND)

TELEPHONE & TELEGRAMS
BULWELL 78237-8

M. MCCARTHY & SONS, LTD
BULWELL • NOTTINGHAM

MUMFORD BAILEY & PRESTON LTD


AIR CONDITIONING & HEATING
HOT & COLD WATER SERVICES
SANITARY ENGINEERING ETC.

Offices
at:—
Bournemouth. Tel: 4377. — Plymouth. Tel: 2651
NEWCASTLE HOUSE · CLERKENWELL CLOSE · LONDON · E.C.1
Phone: Clerkenwell 0344 Branches at Bournemouth & Dublin

Alphabetical Index to Advertisers

	PAGE		PAGE		PAGE
Adamite Co., Ltd., The	lxxv	Guest, Keen & Nettlefolds (Midlands), Ltd.	xix	Pilkington Brothers, Ltd.	xiv
Anderson Construction Co., Ltd.	xxxii	G.W.B. Electric Furnaces, Ltd.	xxxvi	Porn & Dunwoody, Ltd.	xxxv
Anderson, D., & Son, Ltd.	lxxvii	Gyproc Products, Ltd.	lxxvii	Pritchett & Gold & E.P.S. Co., Ltd.	xxxv
Architectural Press, Ltd., The	lxxvii, lxx, xxxii	Halden, J., & Co., Ltd.	lxxvii	Prodorite, Ltd.	lxxvii
Associated Lead Manufacturers, Ltd.	lxxvii	Hall, J. & E., Ltd.	lxxvii	Radiation Group Sales, Ltd.	lxxvii
Aygee, Ltd.	lxxvii	Harvey, G. A., & Co. (London), Ltd.	lxxvii	Range Boilers, Ltd.	lxxvii
Barter Trading Corporation, Ltd.	lxxvii	Heal's Contracts, Ltd.	lxxvii	Rolyat Tank Co., Ltd., The	lxxvii
Blackburn, Thomas, & Sons, Ltd.	lxxvii	Heywood, W. H., & Co., Ltd.	lxxvii	Ronuk, Ltd.	lxxvii
Boulton & Paul, Ltd.	lxxvii	Hills (West Bromwich), Ltd.	lxxvii	Rowson, Drew & Clydesdale, Ltd.	lxxvii
Bovis, Ltd.	lxxvii	Hollway, W. F., & Brother, Ltd.	lxxvii	Rubert Co., Ltd., The	lxxvii
Bowker, S. O., Ltd.	lxxvii	Holophane, Ltd.	lxxvii	Sarco Thermostats, Ltd.	lxxvii
Braithwaite & Co., Engineers, Ltd.	lxxvii	Hope, Henry, & Sons, Ltd.	lxxvii	Scaffolding (Great Britain), Ltd.	lxxvii
Briggs, Wm., & Sons, Ltd.	lxxvii	Horseley Bridge & Thomas Piggott, Ltd.	lxxvii	Scharin Products, Ltd.	lxxvii
British Hermesal, Ltd.	lxxvii	Improved Wood Pavement Co.	lxxvii	Seomastic, Ltd.	lxxvii
British Plumber, Ltd.	lxxvii	Ingersoll Locks	lxxvii	Sentex, Ltd.	lxxvii
British Thomson-Houston Co., Ltd. The	lxxvii	Jaconello, Ltd.	lxxvii	Shanks, E. O., & Sons, Ltd.	lxxvii
Broads Manufacturing Co., Ltd.	lxxvii	Kenyon, Wm., & Sons, Ltd.	lxxvii	Sieglwart Floor Co., Ltd., The	lxxvii
Bryce White & Co., Ltd.	lxxvii	Kwikform, Ltd.	lxxvii	Small & Parkes, Ltd.	lxxvii
Burgess Products Co., Ltd.	lxxvii	Lamont, James H., & Co., Ltd.	lxxvii	Smith's Fireproof Floors, Ltd.	lxxvii
Cafferata & Co., Ltd.	lxxvii	Lead Industries Development Council	lxxvii	Smith, Samuel, & Sons, Ltd.	lxxvii
Cargo Fleet Iron Co., Ltd.	lxxvii	Le Grand Sutcliff & Gell, Ltd.	lxxvii	Smith & Westwood, Ltd.	lxxvii
Cement Marketing Co., Ltd., The	lxxvii	Leslie & Co., Ltd.	lxxvii	Southern Lime Association, The	lxxvii
Chance Bros., Ltd.	lxxvii	Lion Foundry Co., Ltd.	lxxvii	Standard Patent Glazing Co., Ltd., The	lxxvii
Chubb & Son's Lock & Safe Co., Ltd.	lxxvii	Lilly, Walter, & Co., Ltd.	lxxvii	Sterling Foundry Specialties, Ltd.	lxxvii
Clarko Ellard Engineering Co., Ltd.	lxxvii	Linoform Manufacturers' Association	lxxvii	Stramit Boards, Ltd.	lxxvii
Coit Ventilation, Ltd.	lxxvii	Lovell & Hanson, Ltd.	lxxvii	Stock Brick Manufacturers' Association, The	lxxvii
Cork Insulation & Asbestos Co., Ltd.	lxxvii	McCall & Co. (Sheffield), Ltd.	lxxvii	Storry, Smithson & Co., Ltd.	lxxvii
Courtney, Pope, Ltd.	lxxvii	McCarthy, M., & Sons, Ltd.	lxxvii	Stott, James, & Co. (Engineers), Ltd.	lxxvii
Cox, Peter & Partners, Ltd.	lxxvii	McKechnie Bros., Ltd.	lxxvii	Stramit Boards, Ltd.	lxxvii
Crane, Ltd.	lxxvii	MacAndrews & Forbes, Ltd.	lxxvii	Sundeala Board Co., Ltd.	lxxvii
Crittall Mfg. Co., Ltd.	lxxvii	Main, R. & A., Ltd.	lxxvii	Tarmac, Ltd.	lxxvii
Davidson, C., & Sons, Ltd.	lxxvii	Mallinson, W., & Sons, Ltd.	lxxvii	Taylor, R. & Co. (Ironfounders), Ltd.	lxxvii
Deans Blinds (Putney), Ltd.	lxxvii	Marbolt Flooring Co., Ltd., The	lxxvii	Tentest Fibre Board Co., Ltd.	lxxvii
Dow-Mac (Products), Ltd.	lxxvii	Marley Tile Co., Ltd., The	lxxvii	Thomas, Richard, & Baldwins, Ltd.	lxxvii
Downing, G. H., & Co., Ltd.	lxxvii	Mason, Joseph, & Co., Ltd.	lxxvii	Thorn, J., & Sons, Ltd.	lxxvii
Dunbrik, Ltd.	lxxvii	Matthews & Yates, Ltd.	lxxvii	Thorp, John B.	lxxvii
Eastwoods, Ltd.	lxxvii	Merchant Trading Co., Ltd., The	lxxvii	T.I. Aluminium, Ltd.	lxxvii
Econa Modern Products, Ltd.	lxxvii	Metropolitan-Vickers Electrical Co., Ltd.	lxxvii	T.M.C. Harwell (Sales), Ltd.	lxxvii
Elgood, E. J., Ltd.	lxxvii	Midland Electric Manufacturing Co., Ltd.	lxxvii	Tretol, Ltd.	lxxvii
Ellison, George, Ltd.	lxxvii	Midland Joinery Works, Ltd., The	lxxvii	Tucker, J. H., & Co., Ltd.	lxxvii
Ellis School of Architecture, The	lxxvii	Midland Woodworking Co., Ltd.	lxxvii	Turner, Charles, & Son, Ltd.	lxxvii
English Clock Systems, Ltd.	lxxvii	Mills Scaffold Co., Ltd.	lxxvii	Twist Reinforcement, Ltd.	lxxvii
Etchells, Congdon & Muir, Ltd.	lxxvii	Moler Products, Ltd.	lxxvii	United Kingdom Provident Institution, The	lxxvii
Evode, Ltd.	lxxvii	Morris, Herbert, Ltd.	lxxvii	United Steel Companies, Ltd., The	lxxvii
Ezee Kitchen Equipment, Ltd.	lxxvii	Mumford, Bailey & Preston, Ltd.	lxxvii	Venus Pencil Co., Ltd., The	lxxvii
Finch, B., & Co., Ltd.	lxxvii	National Federation of Clay Industries	lxxvii	Versil, Ltd.	lxxvii
Finlock Gutters, Ltd.	lxxvii	Neuchatel Asphalte Co., Ltd., The	lxxvii	Vigers Brothers, Ltd.	lxxvii
Fordham Pressings, Ltd.	lxxvii	Newall's Insulation Co., Ltd.	lxxvii	Walpamur Co., Ltd.	lxxvii
Furse, W. J., & Co., Ltd.	lxxvii	New Day Electrical Accessories, Ltd.	lxxvii	Wareite, Ltd.	lxxvii
Galvo (Wire Netting), Ltd.	lxxvii	Newman, Wm., & Sons, Ltd.	lxxvii	Ward, Thomas W., Ltd.	lxxvii
Gas Council, The	lxxvii	Northern Aluminium Co., Ltd.	lxxvii	Wardie Engineering Co., Ltd.	lxxvii
Gyproc Products, Ltd.	lxxvii	Northern Polytechnic	lxxvii	West, A., & Partners, Ltd.	lxxvii
General Electric Co., Ltd., The	lxxvii	Paragon Glazing Co., Ltd.	lxxvii	Wellington Tube Works, Ltd.	lxxvii
Gent & Co., Ltd.	lxxvii	Paul, W. H., Ltd.	lxxvii	Wheatley & Co., Ltd.	lxxvii
Girdling Ferro Concrete Co., Ltd.	lxxvii	Pennycook Patent Glazing & Engineer- ing Co., Ltd.	lxxvii	Wild, M. B., & Co., Ltd.	lxxvii
Greenwood's & Airvac Ventilating Co., Ltd.	lxxvii			Wimpey, George, & Co., Ltd.	lxxvii

For Appointments (Wanted or Vacant), Competitions Open, Drawings, Tracings, etc., Educational, Legal Notices, Miscellaneous Property, Land and Sales, see lxxi, lxxii, lxxiii, lxxiv, lxxv.



Tenby

ACCESSORIES ARE IN SHORT SUPPLY

If your Wholesaler can't always supply your Tenby requirements

"off the shelf", don't blame him.

Shortages of raw material and increasing demands are making it very difficult for us to keep everyone adequately supplied. We are doing our best, and you can help us by remembering that...

A clip on the wall
is worth a gross on the floor!



**ELECTRICAL
ACCESSORIES**

Manufactured by
S. O. BOWKER LTD.
19-21 Warstone Lane, Birmingham 18
Tel: CENTral 3701

PAGE
xiv
xxxv

xlii

xxxvii

xxviii

lv

lviii

xxlii

xxxi

xxviii

xxv

xxvii

lxvi

lxv

lvii

xlvi

lxii

liii

lvii

lx

xlvi

xxii

xvi

lfi

lxiv

lxii

xi

xlvi

xxxvii

8

A

g

BI
es
w
th
do
do
T

L
w
le
p
ch
le
n
th

S


I

(

★

■

A small fitting of



great importance

BLOCKS OF FLATS, housing estates, business premises, warehouses—in every case the security of the front doors and entrances largely depends on one small fitting. The lock you specify.

Lock security.

When you specify Chubb locks you can trust them to prove the wisdom of your choice. These anti-burglar locks have been famous for more than 130 years for their immense strength and

the fact that they are virtually unpickable. They give all the security you'd expect from the world's best locks.

Chubb have designed and constructed locks for most types of property including houses, flats, garages, shops, offices and warehouses.

Should you require complete details of the full Chubb range, we will gladly send further particulars on hearing from you. Write or telephone: Chubb & Son's Lock and Safe Co. Ltd., 40-42 Oxford Street, London, W.1. Telephone MUScum 5822.

Specify **CHUBB** locks

A
RONUK
PRODUCT



★ **WOOD DYE**

THE "1-COAT" TRANSPARENT PENETRATING, PERMANENT PRESERVATIVE STAIN FOR ALL NEW WOODWORK.


It cannot raise the grain.

★ 12 SHADES:
ALL SIZES

ADVISORY SERVICE

Shade cards, panels, full directions and working instructions for contractors' use, estimates and 45 years of specialists' experience are at your service.

RONUK Ltd., Portslade, Sussex
Polishing } 16 South Molton Street
Contract Depot } London, W.1



RUINS THE BEST OF PLANS...



...be sure to specify

BRIGGS


AQUALITE

BITUMEN DAMPCOURSE

'laid in a minute... lasts as long as the wall.'

PREVENTS DAMP AND DRY ROT

WILLIAM BRIGGS & SONS LTD., DUNDEE • LONDON: VAUXHALL GROVE, S.W.8
Branches at Aberdeen, Edinburgh, Glasgow, Leicester, Liverpool, Norwich
D.C.7



★ We stock WALLBOARDS and building boards in many different varieties. Send trade card for details today.

You Buy RIGHT from

BRYCE WHITE & CO. LTD.

LANGLEY, SOUTHAMPTON, BRISTOL & LONDON

ESTABLISHED 1879

Head Office: DESERONTO WHARF, LANGLEY, BUCKS
(Telephone: LANGLEY 232 & SOUTHALL 2231)



FOR THE ERECTION OF GRANDSTANDS

- never forget

MILLS

—THIS ELEPHANT WON'T!

The Dudley Zoo elephant "lending a hand" in the erection of the Grandstand for the Pageant of Dudley.



Steel and Aluminium Scaffolding for sale, contract, or hire. Every requirement met also for ancillary equipment, including: Shuttering • Steel Props • Trench Struts Splitheads • Hoists • Concrete Mixers • Cradles Builders' Hand Carts • Barrows • Trestles, etc.

SIMPLY 'PHONE YOUR NEAREST DEPOT

BELFAST • BIRMINGHAM • BOURNEMOUTH • BRADFORD • BRIGHTON • BRISTOL
CANTERBURY • CARDIFF • COVENTRY • CROYDON • DUBLIN • GLASGOW • HULL
ILFORD • LIVERPOOL • LOWESTOFT • MANCHESTER • NEWCASTLE • NORWICH
PLYMOUTH • PORTSMOUTH • READING • SOUTHAMPTON • SWANSEA • YARMOUTH

MILLS SCAFFOLD CO. LTD., Head Office & Depot: **TRUSSLEY WORKS, HAMMERSMITH GROVE, LONDON, W.6.** Tel: RIVerside 5026/9

